

"Section 756-13. OCCUPANCY PERMIT ---

- A. INSPECTIONS.
 - (1) The Building Inspector shall make a final inspection of all new buildings, additions and alterations. If no violations of this or any other ordinance be found, the Building Inspector shall issue an occupancy permit, stating the purpose for which the building is to be used.
 - (2) No building, nor part thereof, shall be occupied until such certificate has been issued, nor shall any building be occupied in any manner which conflicts with the conditions set forth in the occupancy permit.
- B. USE DISCONTINUED.
 - (1) Whenever any building or portion thereof is being used or occupied contrary to the provisions of this chapter, the Building Inspector shall order such use or occupancy discontinued and the building, or portion thereof, vacated by notice served on any person using or causing such use or occupancy to be continued and such person shall vacate such building or portion thereof within 10 days after receipt of the notice or make the building, or portion thereof, comply with the requirements of this chapter.
 - (2) Any building, structure or premises, or any part thereof, hereafter vacated or damaged by any cause whatsoever so as to jeopardize public safety or health shall not hereafter be occupied or used under an existing occupancy permit or without the same, until an application has been filed and a new occupancy permit issued.
- C. CHANGE.

It shall be unlawful to change the use of any building, structure, premises, or part thereof without first obtaining, from the Building Inspector, an approval of such change in the occupancy or use and an occupancy permit therefor."

Scott Miller, Building Inspector, Village of Fox Point



VILLAGE OF FOX POINT

MILWAUKEE COUNTY WISCONSIN

VILLAGE HALL 7200 N. SANTA MONICA BLVD. FOX POINT 53217-3505 414-351-8900 FAX 414-351-8909

July 30, 2015

Rick & Keri Stratton 3009 N. Hackett Ave. Milwaukee, WI 53211

RE: Occupancy Permit 1015 E. Quarles Place Fox Point, WI 53217

Dear Mr. & Mrs. Stratton:

I made an Occupancy Inspection at the above referenced property on July 29, 2015. The inspection revealed the following code violations, issues and concerns. They are:

- 1) Please provide the Village with a topographical survey showing that you have complied with the grading and drainage plan that was approved by the Building Board and the Director of Public Works/Village Engineer. (ref SPS 320.02(2)(b) & FPC 756-7)
- Please provide a code compliant cover or guard to protect your area well opening. (ref. SPS 321.04(3)(c))
- 3) Please obtain a building permit for the construction of your new fence and arbor. (FPC 745-7(3)(a))
- 4) Please obtain a permit for the installation of your satellite dish. (ref. FPC 455-2)
- 5) Please properly complete your furnace's venting system. (ref. SPS 323.04(b))
- 6) Please properly complete your water heater's venting system. (ref. SPS 323.04(b))
- 7) I observed that the water heater is being supplied by an extension cord. Please eliminate the extension cord and provide a code compliant receptacle outlet to supply electricity to your water heater as required by code. (ref. NEC 400-8)
- 8) Please provide a code compliant Ground-Fault Circuit Interrupter (GFCI) protected, 120-volt, single phase, 15 or 20 ampere receptacle outlet within 25'00" of your air-conditioning unit.
- 9) Please properly close all open electrical boxes. (ref. NEC 210.63)
- I observed that the low-voltage lighting transformer is laying on top of the HVAC ductwork in your basement. Please properly support this transformer as required by code. (ref. NEC 110.3(b))

-1-

- 11) All open wires must terminate in a code compliant electrical box. (ref. NEC 300.15)
- The nonmetallic-sheathed cable branch circuits that come out of the top of the basement service panelboard must be supported within twelve (12) inches of this equipment. (ref. NEC 334.30)
- 13) The nonmetallic-sheathed cables that are located below the first floor joist(s) shall be properly protected from damage as required by code. (ref. NEC 334.15)
- 14) Please properly seal all openings in the basement rim joist. (SPS 321.24)
- 15) Please properly firestop all openings in the first floor system. (SPS 321.085)
- 16) Please properly identify all circuit breakers. (ref. NEC 110.22 & 408.4(A))
- 17) The inspection revealed that your fireplace hearth is only 19 inches deep. This is contrary to section 321.29(6) of the Wisconsin Administrative Code which requires a fireplace hearth depth of 20 inches. As such, please provide the Village with documentation showing that you are complying with the fireplace manufacturer's installation requirements with respect to depth of your fireplace hearth. (ref SPS 321.32 & 321.29(6))
- 18) All 120-volt, single phase, 15 and 20 ampere branch circuits supplying outlets installed in dwelling unit family rooms, dining rooms, living rooms, parlors, libraries, dens, bedrooms, sunrooms, recreational rooms, closets, hallways, or similar rooms shall be protected by an Arc-Fault Circuit Interrupter (AFCI). (ref. 210.12(A))

For the foregoing reasons, I am hereby withholding the issuance of your Occupancy Permit at this time. Please be aware that all of the above stated code violations must be corrected within 30days of the date of this letter unless an extension of time is granted pursuant to section 320.21 of the Wisconsin Administrative Code.

Please feel free to contact me should you have any questions with respect to this letter.

Sincerely,

Scott Miller Building/Plumbing/Electrical Inspector Village of Fox Point

Cc Village Manager Village Attorney Applebrook Construction File

Sue Genrich

From: Sent: To: Subject: Scott Miller Friday, July 31, 2015 12:39 PM Sue Genrich FW: Fireplace

Thanks, Scott Miller

From: Rick Stratton [mailto:rstratton@feed.us] Sent: Friday, July 31, 2015 12:24 PM To: Scott Miller <smiller@vil.fox-point.wi.us> Subject: Fireplace

Hello Scott,

Thank you for your patience on the fireplace hearth issue.

We will not have a fire in the fireplace until we are granted a variance or have the hearth replaced and reinspected.

1

Thanks again for your help through the entire building process and have a good vacation.

Regards, Frederick Stratton (Rick) 1015 E. Quarles Place



VILLAGE OF FOX POINT

MILWAUKEE COUNTY WISCONSIN

VILLAGE HALL 7200 N. SANTA MONICA BLVD. FOX POINT 53217-3505 414-351-8900 FAX 414-351-8909

July 30, 2015

Rick & Keri Stratton 3009 N. Hackett Ave. Milwaukee, WI <u>5</u>3211

RE: Occupancy Permit 1015 E. Quarles Place Fox Point, WI 53217

Dear Mr. & Mrs. Stratton:

l made an Occupancy Inspection at the above referenced property on July 29, 2015. The inspection revealed the following code violations, issues and concerns. They are:

Please provide the Village with a topographical survey showing that you have complied with the grading and drainage plan that was approved by the Building Board and the Director of Public Works/Village Engineer. (ref SPS 320.02(2)(b) & FPC 756-7)

Please provide a code compliant cover or guard to protect your area well opening. (ref. SPS 321.04(3)(c))

 Please obtain a building permit for the construction of your new fence and arbor. (FPC 745-7(3)(a))

Please obtain a permit for the installation of your satellite dish. (ref. FPC 455-2) المرك

Please properly complete your furnace's venting system. (ref. SPS 323.04(b))

6) Please properly complete your water heater's venting system. (ref. SPS 323.04(b))

- I observed that the water heater is being supplied by an extension cord. Please eliminate the extension cord and provide a code compliant receptacle outlet to supply electricity to your water heater as required by code. (ref. NEC 400-8)
- Please provide a code compliant Ground-Fault Circuit Interrupter (GFCI) protected, 120-volt, single phase, 15 or 20 ampere receptacle outlet within 25'00" of your air-conditioning unit. Please properly close all open electrical boxes. (ref. NEC 210.63)

observed that the low-voltage lighting transformer is laying on top of the HVAC ductwork in your basement. Please properly support this transformer as required by code. (ref. NEC 110.3(b))

几月 All open wires must terminate in a code compliant electrical box. (ref. NEC 300.15)

12) The nonmetallic-sheathed cable branch circuits that come out of the top of the basement service panelboard must be supported within twelve (12) inches of this equipment. (ref. NEC 334.30)

13) The nonmetallic-sheathed cables that are located below the first floor joist(s) shall be properly protected from damage as required by code. (ref. NEC 334.15)

Please properly seal all openings in the basement rim joist. (SPS 321.24)

15) Please properly firestop all openings in the first floor system. (SPS 321.085)

Please properly identify all circuit breakers. (ref. NEC 110.22 & 408.4(A))

17) The inspection revealed that your fireplace hearth is only 19 inches deep. This is contrary to section 321.29(6) of the Wisconsin Administrative Code which requires a fireplace hearth depth of 20 inches. As such, please provide the Village with documentation showing that you are complying with the fireplace manufacturer's installation requirements with respect to depth of wour fireplace hearth. (ref SPS 321.32 & 321.29(6))

All 120-volt, single phase, 15 and 20 ampere branch circuits supplying outlets installed in dwelling unit family rooms, dining rooms, living rooms, parlors, libraries, dens, bedrooms, sunrooms, recreational rooms, closets, hallways, or similar rooms shall be protected by an Arc-Fault Circuit Interrupter (AFCI). (ref. 210.12(A))

For the foregoing reasons, I am hereby withholding the issuance of your Occupancy Permit at this time. Please be aware that all of the above stated code violations must be corrected within 30days of the date of this letter unless an extension of time is granted pursuant to section 320.21 of the Wisconsin Administrative Code.

Please feel free to contact me should you have any questions with respect to this letter.

Sincerely,

Scott Miller Building/Plumbing/Electrical Inspector Village of Fox Point


Cc Village Manager Village Attorney Applebrook Construction File

321.29(6) Hearth Extension

Answer:

Question: How is the hearth extension measured?

The hearth or hearth extension is measured from the face of the fireplace opening and <u>not</u> from the front of the firebox, spark screen, or glass doors. The face of the fireplace includes any trim materials provided on the front of the fireplace. Earlier editions of the UDC permitted measurement from the firebox, but as of the 1989 Edition, the measurement is to be taken from the face of the fireplace opening.



Fireplace hearth extension requirements

Scott Miller

From: Sent: To: Cc: Subject: Hubeler, Duane D - DSPS <Duane.Hubeler@Wisconsin.gov> Friday, July 31, 2015 10:25 AM Scott Miller Gregory Norman Hearth Extension

Scott, I just talked with Greg Norman on the hearth extension issue. He sent me a photo which shows the hearth extension is approximately ½ to 1" short of the required 20 inches from the front of the unit. Based on that photo and 2 or 3 past variances, I would say this petition has a high probability of being granted.

Duane Hubeler Engineering Consultant - Uniform Dwelling Code (608) 266-1390 <u>duane.hubeler@wisconsin.gov</u>

The Department offers an e-mail subscription service that provides electronic notification of news and/or notices that may be of interest to you. To sign up for this service, <u>click here</u>.

The DSPS is committed to service excellence. Visit our survey at <u>https://www.surveymonkey.com/s/dspsiscustomersatisfactionbuildingsudc</u> to evaluate your experience with the DSPS.

Scott Miller

From: Sent: To: Subject: Rick Stratton <rstratton@feed.us> Friday, July 31, 2015 12:24 PM Scott Miller Fireplace

Hello Scott,

Thank you for your patience on the fireplace hearth issue.

We will not have a fire in the fireplace until we are granted a variance or have the hearth replaced and reinspected.

Thanks again for your help through the entire building process and have a good vacation.

Regards, Frederick Stratton (Rick) 1015 E. Quarles Place



DIVISION OF INDUSTRY SERVICES PO BOX 7162 MADISON WI 53707-7162 Contact Through Relay http://dsps.wi.gov/programs/industry-services www.wisconsin.gov

> Scott Walker, Governor Dave Ross, Secretary

November 20, 2015

CUST ID No. 1334621

RICK STRATTON 1015 E QUARLES PLACE FOX POINT WI 53217

APPROVAL OF PETITION FOR VARIANCE

SITE:

Rick Stratton and Keri Saragian 1015 E Quarles Place Village of Fox Point, 53217 Milwaukee County

FOR: Petition for Variance

SPS 321.29 (6) (d)

The submittal described above has been reviewed for equivalency to applicable Wisconsin Administrative Codes and compliance with Wisconsin Statutes. The submittal has been CONDITIONALLY APPROVED. The owner, as defined in section 101.01(10), Wisconsin Statutes, is responsible for compliance with all conditions of this petition approval and other applicable code requirements.

The code section petitioned requires a 20-inch hearth extension in front of the fireplace opening.

The variance requested is to allow approximately 1 inch of non-combustible decorative facing to infringe on the required 20-inch measurement.

The intent of the code section petitioned is to prevent a log or ember that may roll out of the firebox from contacting a combustible material.

The petitioner submitted the SB-9890 application form including 8 additional pages of supporting documents.

Reviewer's Comments:

- 1. The municipal building inspection department offered no comment.
- 2. The wording under the UDC code section mentioned above is not completely clear as to where the 20 inch measurement is measured from.
- 3. With this fireplace, it is clear that the firebox ends more than 20 inches from the end of the hearth extension. It is unlikely that any flaming material would be placed outside of the boundary of the firebox.
- 4. The installation instructions for the fireplace imply that measurements may be taken from the firebox rather than from the front of the decorative facing.

Departmental Action: CONDITIONAL APPROVAL

Reviewer's Conditions of Approval: No additional requirements

• All of the petitioner's statements of fact or intent included on the variance application form, any other documents submitted to the Department shall be carried out.. This variance is specific to the subject code section petitioned and the building as it will exist following completion of the current construction project and shall not be used for any additional or future modifications, additions, or alterations to the subject building.

ATTN: One and Two Family Inspector

SCOTT MILLER VILLAGE OF FOX POINT 7200 N SANTA MONICA BLVD FOX POINT WI 53217-3505

> Identification Numbers Transaction ID No. 2632718 Site ID No. 819157

Please refer to both identification numbers, above, in all correspondence with the agency.

t

RICK STRATTON

This decision will become final unless the department within 30 days from the date of this letter receives a written request for a hearing. A request for hearing should be sent to the address shown on this letterhead. A copy of this letter must be included with the request for a hearing. The request for hearing should state the reasons for objecting to the department's decision, because a request for hearing may be denied if it does not present a significant question in fact, law or policy.

Inquiries concerning this correspondence may be made to me at the telephone number listed below, or at the address on this letterhead.

Sincerely,

Duane D Hubeler Eng Conslt Uniform Dwelling , Division of Industry Services (608)266-1390 , Monday-Friday 7:45 AM-4:30 pm duane.hubeler@wisconsin.gov

Fee Required \$ 175.00 175.00 Fee Received \$ Balance Due \$ 0.00

WiSMART code: 7648 -

cc:

| | | 1 | 1 |
|----------------|---|----|-----|
| Date Submitted | B | 29 | /19 |
| | | | |

Village of Fox Point 7200 N. Santa Monica Blvd. Fox Point, WI 53217 (414) 351-8900

No._ /6270

| | APP | LICATION FOF | R BUILDIN | G Compl ated hereafter, | iance |
|-------------------------|---|---|-----------------------|----------------------------|---------------------|
| The undersigned | ed hereby applies for a permit | t to build, in accordance with | he information tabula | ated hereafter, | |
| Type of Project | ARBOR GRODEN | with FENCE Add | ress <u>1015</u> | QUARLES | PURE |
| Resid | ience, Galage, Biole, Ginee, School, Pene | e, bled, bigh, bwhinning i boi, bhdeigibh | nu Storage Tank, Ele. | | |
| Lot | Block | Subdivision_ | | District | |
| | | zoning ordinance? | | | |
| Height of Structure | | | | | |
| | | (feet) Depth (perp | | | |
| Distance: Street Lin | ne to Front Line of Structure_ | | | | (feet) |
| Distance: Side Lot | Line to Structure | | | | |
| Type of Construction | on: | Exte | rior finish | | |
| | | | | Stucco, Siding, Brick Ven | eer, Etc. |
| | d above street grade | | | · | |
| Number of rooms | | B | aths | | |
| Gai | rage | | · | | |
| Estimated cost Bui | ilding | | | | |
| Stru | ucture_500 | | <i>t</i> | | |
| Is there a private gara | nge? | | · | | |
| | | ng ordinance? | | | |
| | | of Stalls | | | |
| | | partment of Industry, Labor an | | | |
| | | e with all applicable sections | | | |
| Herewith are filed t | the following duplicate plans | | in number, wl | hich I certify I will cor | form to in the work |
| hereby applied for: | 4 | . 1. | | 111 - | 1 0 |
| Remarks: CEOI | 4R FENCE POS | TS W DEER M | ESH FENCI | <u>E. 16 × 2</u> | 2' and |
| -8' High | <u>entrance</u> ARBON | TS W/ DEER M | | | |
| | | | | | |
| | | | | | |

Herewith are filed the specifications that describe the work in question and as shown on plans above submitted.

In making the application the undersigned agrees to obey the Fox Point Building and Zoning Codes pertaining to the erection of all structures and also agrees to obey all other ordinances of the Village of Fox Point.

The undersigned, owner or being duly authorized so to do, hereby gives express authorization to the Village of Fox Point, its officers, agents and employees, to enter upon the premises herein described and fill up any excavation, or tear down, remove or enclose the unfinished structure for which a permit is herein requested in the event of cessation of the building, whenever the Building Inspector shall determine that such premises in the unfinished condition of the structure are dangerous to members of the public, including children, even though trespassers. The undersigned further hereby waives all statutory notices and consents to the determination by the Village Board and the levy and placing upon the tax roll of a special assessment in the amount of the cost to the Village, including customary Village overhead charges incurred in filling up any such excavation or tearing down, removing or enclosing any such unfinished structure.

We hereby agree to provide a house number plate or sign readily observable from the public highway which will be installed not less than 15 days after the structure is occupied.

| - | 0.00/01/01 |
|--|---|
| Owner of Structure FREDERICK STRATTON | Arch. or Contr. 7 TSUTLER CHASE |
| Address 1015 EQUARLES PLACE | Address |
| City FOX POINT State WI Zip 532 | 47 City / MEQUON State WI Zip 53092 |
| | |
| Size of Structure 16×22 (sq. ft | Phone $4/4 - 9/5 - 7493$.) Permit Fee $4/40$, 00 Receipt $#8.000534$ |
| Dwelling Contractor Certification No | Expires |
| Dwelling Contractor Qualifier Certification No | Expires |
| Building Contractor Certification No | Applicant Signature |
| Date of Approved 7 | Actifitect, Owner, Builder |

| | -x | | î | 1 - |
|------|-----------|---|----|-----|
| Date | Submitted | 7 | 29 | 115 |
| | | | | |

Village of Fox Point 7200 N. Santa Monica Blvd. Fox Point, WI 53217 (414) 351-8900

No._/6271

| | | APP | LICATIO | N FOR | BUILDI | NG Con | pliance |
|-----------------|---|----------------------|------------------------|---------------|-------------------|---------------------|----------------------------|
| The under | signed hereby ap | plies for a permit | to build, in accor | dance with th | e information tab | | • |
| Type of Projec | t <u>1</u> SA+cli-1 Residence, Garage, Sti | te dish | . Shed. Sign. Swimming | Addre | SS. 10/5 | EQUARI | ES PLACE |
| | | _Block | | Subdivision | . | District | |
| | | | | | | | |
| Height of Strue | cture | | | | | | (stories or feet) |
| | | | | | | /ay) | |
| | | | | | | | (feet) |
| Distance: Side | Lot Line to Stru | cture | | | | | |
| Type of Constr | uction: | Frana Drielt ti | la ata | Exteri | or finish | Stucco, Siding, Br | iolr Vanaar Eta |
| | | | | | | | ick veneer, Etc. |
| | | | | | | | |
| Number of room | _ | | | | | | |
| | - | | | | | | |
| Estimated cost | | | | | | | |
| | - | | | | | | |
| | | · | | | | | |
| Does the contem | plated garage viol | ate the Village zoni | ng ordinance? | | | | |
| | | | | | | e Situated | |
| | | | | | | | nd approval? |
| | | | | | | | ? |
| | | g duplicate plans_ | | | in number, | which I certify I w | ill conform to in the work |
| hereby applied | for: | | <u> </u> | 1 - | 1 | | 1 |
| Remarks: | LIRECTU PI | STI ON | POLE, 3 | · from | WEST 5 | SIDE OF 1 | TOUSE |
| | | | | | | | |

Herewith are filed the specifications that describe the work in question and as shown on plans above submitted.

In making the application the undersigned agrees to obey the Fox Point Building and Zoning Codes pertaining to the erection of all structures and also agrees to obey all other ordinances of the Village of Fox Point.

The undersigned, owner or being duly authorized so to do, hereby gives express authorization to the Village of Fox Point, its officers, agents and employees, to enter upon the premises herein described and fill up any excavation, or tear down, remove or enclose the unfinished structure for which a permit is herein requested in the event of cessation of the building, whenever the Building Inspector shall determine that such premises in the unfinished condition of the structure are dangerous to members of the public, including children, even though trespassers. The undersigned further hereby waives all statutory notices and consents to the determination by the Village Board and the levy and placing upon the tax roll of a special assessment in the amount of the cost to the Village, including customary Village overhead charges incurred in filling up any such excavation or tearing down, removing or enclosing any such unfinished structure.

We hereby agree to provide a house number plate or sign readily observable from the public highway which will be installed not less than 15 days after the structure is occupied.

| Owner of Structure FREDERICK STRATT | tan Arch. or Contr | | |
|--|---------------------------|---------------------------|---|
| Address 1015 E QUAPLES PLACE | Address | | |
| City FOX POINT State WI Zip | 53217 City | StateZip | |
| Phone 414 534 6695 | Phone | | |
| Size of Structure | (sq. ft.) Permit FeeO, OO | Receipt #8.000535 | |
| Dwelling Contractor Certification No | Expires | 8 | |
| Dwelling Contractor Qualifier Certification No | Expires | | |
| Building Contractor Certification No. | Applicant Signature | SPANN | |
| Date of Approved 72/16 | | Architect, Owner, Builder | |
| Builder Inspector | | | 4 |



VILLAGE OF FOX POINT

MILWAUKEE COUNTY

WISCONSIN

VILLAGE HALL 7200 N. SANTA MONICA BLVD. FOX POINT WI 53217-3505 414-351-8900 FAX 414-351-8909

CAUTIONARY STATEMENT TO OWNERS OBTAINING BUILDING PERMITS

101.65(lr) of the Wisconsin Statutes requires municipalities that enforce the Uniform Dwelling Code to provide an owner who applies for a building permit with a statement advising the owner that:

If the owner hires a contractor to perform work under the building permit and the contractor is not bonded or insured as required under s. 101.654 (2) (a), the following consequences might occur:

- (a) The owner may be held liable for any bodily injury to or death of others or for any damage to the property of others that arises out of the work performed under the building permit or that is caused by any negligence by the contractor that occurs in connection with the work performed under the building permit.
- (b) The owner may not be able to collect from the contractor damages for any loss sustained by the owner because of a violation by the contractor of the one- and two- family dwelling code or an ordinance enacted under sub. (1) (a), because of any bodily injury to or death of others or damage to the property of others that arises out of the work performed under the building permit or because of any bodily injury to or death of others or damage to the property of others that is caused by any negligence by the contractor that occurs in connection with the work performed under the building permit.

FREDERICK

Homeowner's Name - PRINTED

Nomeowner's Signature

1015 E QUARLES PL

Fox Point Property Address

Date

Date Submitted 6-8-15

Village of Fox Point 7200 N. Santa Monica Blvd. Fox Point, WI 53217 (414) 351-8900

No._/6225

APPLICATION FOR BUILDING

The undersigned hereby applies for a permit to build, in accordance with the information tabulated hereafter,

| Type of Projec | t / PATO Residence, Gara | BEATING W ge, Store, Office, School, Fence, Shed, S | Address | 1015 E QUARLES PLA | te |
|--------------------|-----------------------------|--|--------------------------------|------------------------------------|--------------|
| Lot | | Block | Subdivision | District | |
| Does contemp | lated structu | re violate the Village zoning | ordinance? | | |
| | | | | | |
| Width (parallel | l to highway |) | (feet) Depth (perpendicula | r to highway) | (feet) |
| Distance: Stree | et Line to Fr | ont Line of Structure | | | (feet) |
| Distance: Side | Lot Line to | Structure | | | , , |
| Type of Constr | ruction: | Frame, Brick-tile, etc. | Exterior finis | h | |
| | | Frame, Brick-tile, etc. | | Stucco, Siding, Brick | Veneer, Etc. |
| Height of front | t yard above | street grade | | | |
| Number of room | ns | | Baths | | |
| - | Garage | | | | |
| Estimated cost. | Building Structure | \$14,000.00 | | | |
| Is there a private | e garage? | | | | |
| Does the conterr | nplated garage | e violate the Village zoning ordi | nance? | | |
| Size | | Number of Stal | ls | Where Situated | |
| Have plans bee | en submitted | to the Wisconsin Department | nt of Industry, Labor and Huma | n Relations for examination and | approval? |
| | | | | visconsin Administrative code? | |
| | | | | n number, which I certify I will c | |
| hereby applied | l for: | | | - | |
| Remarks: | 24 | × 29° PATLO WIT | H 18" SEATING W | THUS ON TWO (2) | SIDES |
| UNTERNA | MAR GR | ILL AT 34" HGH. | | | |
| | | | | | |
| | _ | | | | |

Herewith are filed the specifications that describe the work in question and as shown on plans above submitted.

In making the application the undersigned agrees to obey the Fox Point Building and Zoning Codes pertaining to the erection of all structures and also agrees to obey all other ordinances of the Village of Fox Point.


The undersigned, owner or being duly authorized so to do, hereby gives express authorization to the Village of Fox Point, its officers, agents and employees, to enter upon the premises herein described and fill up any excavation, or tear down, remove or enclose the unfinished structure for which a permit is herein requested in the event of cessation of the building, whenever the Building Inspector shall determine that such premises in the unfinished condition of the structure are dangerous to members of the public, including children, even though trespassers. The undersigned further hereby waives all statutory notices and consents to the determination by the Village Board and the levy and placing upon the tax roll of a special assessment in the amount of the cost to the Village, including customary Village overhead charges incurred in filling up any such excavation or tearing down, removing or enclosing any such unfinished structure.


We hereby agree to provide a house number plate or sign readily observable from the public highway which will be installed not less than 15 days after the structure is occupied.

| Owner of Structure RICK STRATION & KERI STRAJIKN | Arch. or Co | ntr. DBA | BUTER-CHASE C | LUSTOM BUILDORS |
|---|--------------|----------|--------------------------|-----------------|
| Address 3009 N. HACKETT AVE | Address | | <u> </u> | |
| City MILWAUKEE State W Zip 53211 | City | | State | Zip |
| Phone 414 - 534 -6695 | _ Phone | <u> </u> | | |
| |) Permit Fee | 1335 | Receipt_#50 | 253 |
| Dwelling Contractor Certification No. 1269359 | | Expire | <u>s 5/4 16 </u> | |
| Dwelling Contractor Qualifier Certification No. 1003500 | | Expire | 3/14/17 | |
| Building Contractor Certification No | Applicant Si | gnature | egy M- | |
| Date of Approved ble IT | | | V Architect, Owner, Buil | der |
| Builder Inspector | | | | / |

POURED CONCRETE FOOTING , h X ,, 81X <u>S</u> S. Cut our for bliller X 18"X 4 S <u>PAVER PATIO</u> _ @ 28'x 24' Х 18″ х Ч ð DUTDOOR GRILLE & SEAT WALL DETAIL KILK & KOLI STRATTON 1015 E. QUARLES PLAKE

SEATING WALL





.

.

.

Scott Miller

From: Sent: To: Subject: Hubeler, Duane D - DSPS [Duane.Hubeler@Wisconsin.gov] Monday, March 10, 2014 12:42 PM Scott Miller RE:

Having 2 stairways to the first floor will certainly meet the code requirement under s. SPS 321.03 (2) (a).

From: Scott Miller [mailto:smiller@vil.fox-point.wi.us] Sent: Monday, March 10, 2014 7:57 AM To: Hubeler, Duane D - DSPS Subject: FW:

Duane-

In follow-up to this email, please respond in writing to the question in the first paragraph regarding the two stairways. This project is moving along quickly and they will be requesting an inspection sometime soon.

Thanks, Scott Miller

From: Scott Miller Sent: Friday, January 17, 2014 8:50 AM To: Laura Johnson Subject: FW:

From: Hubeler, Duane D - DSPS [mailto:Duane.Hubeler@Wisconsin.gov] Sent: Thursday, January 16, 2014 2:51 PM To: Scott Miller Subject: RE:

From: Scott Miller [mailto:smiller@vil.fox-point.wi.us] Sent: Thursday, January 16, 2014 11:18 AM To: Hubeler, Duane D - DSPS Subject:

Duane-

Thanks for getting back to me with regard to the egress question. Per your voice mail message, it appears that it is okay not to have egress windows on the second story of a dwelling, provided however, that there are two stairways that connect to the first floor. In other words, one of the stairways does not have to discharge to grade. Can you please provide me with something in writing for my file? Please let me know. Also, I have two additional questions. They are:

1) I have a contractor that is applying for a building permit. The application shows that he is planning on installing several load bearing beams. One of the beams is a 4-ply wood and 3-ply A36 steel (7-plys total) built-up flitch

plated beam with 3/8 inch bolts staggered at 24 inches o.c spacing that will be supporting another load bearing beam that attaches to its side. My concern is that the engineering is not stamped by a licensed engineer or architect. The contractor said that his designer is not an engineer. The contractor said that it would cost him an additional \$1200 to provide the Village with "stamped calculations." The contractor further said that we do not have the authority to require stamped calculations. My concern is that if we grant the permit without an engineer's stamp could we be held liable should there be a structural problem in the future? It seems that the code is silent on this issue. If the house in question is post-1980, it comes under the UDC prohibition on requiring an architect or engineer's seal. SPS 320.09 (6) (c) is where the prohibition is. You can certainly require the designer to do the calculations in coordination with the framing plan. Your description doesn't mention any point loads or the depth of the beam - that's where the framing plan comes in. If the beams are going to be connected by a saddle or similar, Simpson can supply the contractor with the calcs for sizing and fastening the saddle - assuming it's a Simpson saddle. If you have very specific structural questions, I recommend you contact Steve Dobratz, who is in charge of the UDC program. His phone is (920) 492-5611.

2) I have another contractor that would like to pour a grade beam for a detached garage this time of year. The ground is frozen. Is this permissible? Can he try to thaw-out the ground prior to pouring the footings? Please let me know. A detached garage is outside the scope of the UDC, so we don't really have a horse in this race. The only way that I have seen that could work in this scenario is tenting over a torpedo heater. It would take quite awhile and cost a lot as most of the heat will go up. Good luck in thawing 2 feet of frost in your clay.

The above contractors to like me to issue their permits asap. So, your prompt reply will be most appreciated.

Please let me know if you have any questions.

Thanks, Scott Miller

REScheck Software Version 4.4.4 Compliance Certificate

Project Title:

| Energy Code: | 2008 IECC |
|--------------------------|----------------------|
| Location: | Fox Point, Wisconsin |
| Construction Type: | Singe-family |
| Englest Type: | New Construction |
| Conditioned Floor Area: | 4,874 112 |
| Clazing Area Percentage: | 18% |
| Heating Begree Days: | 8604 |
| Cimste Zone: | 8 |
| Ferni Eale: | |
| | |

Construction Sile:

OwnerWyent

Designer/Contractor:

| Complance: Passes incing 115 Inside-of | | | |
|---|-----------------|---|-----|
| Complete: 2.2% Easter Than Code | Maximum UAc 757 | Your Life 740 | · · |
| کی کار میں میں میں میں میں کا میں میں کا میں میں کا میں کا میں کا میں کا میں کا کا ایک کا | | r. aristra di constante di consta La constante di const | |

Envelope Assemblies

| Assembly | Grose Area or Perimeter | Carly R-Value | Cont. R-Valoe | Glazing er Docr U-Factor | 114 |
|--|-------------------------------|------------------|------------------|--------------------------------|------|
| Waf 1: Wood Prane, 16" o.c. | 4,549 | 210 | E 13 | | 209 |
| Window 1: Wood Frame Bouble Pane with Law-E | 765 | | | 0310 | 237 |
| Door 1: Sold | <u>17</u> | | | 0.540 | |
| Door 2: Sizes | 87 | | | 0.330 | 25 |
| Basement (Val 1: Solid-Concrete or Masonay Wal height: 8.3 Depth beion grade: 7.3 Insulation depth: 8.3 | 2,903 | 0.0 | 10.3 | | 518 |
| Floor \$: Al-Mood Joist/Trucs/Over Unconditioned Space | 536 | 38.0 | E.3 | | . 17 |
| Floor 2: ACHNood Joich Truss Over Cuiside Air | 21 | 28.0 | £.0 | | 4 |
| Fioor 3: Sub-On-Grade/Unheated Insulation depth: 6.0 | 37 | | 10.3 | | 25 |
| Cetting 8: Fait Cetting or Sciesor Truss | 2,523 | 28 <i>0</i> | <u>5</u> .3 | | 78 |
| Stylight 5: Wood Fizime:Double Pane with Low-E | 36 | | | 0.550 | 22 |
| Celing 2: Saiteonal Celing | 200 | 350 | ·E:3 | | 6 |

ಸರ್ಮಾ ಗಂದವರೆ ಸಂಕರ್ಣದಲ್ಲಿ ನಿರ್ದೇಶವಾರಿಂದ ಇಹಿರುತಿಗೆ ನೀರಿಕ್ಕೆ ಇಂಡಿತ್ಯಾನದೇಶನೆ ರಿಗಾ ಮೋಗುರಾಂದಿಗಿರೆ. ಅಗಾರೂಗಿ ಮಾರ್ :stiff fasjon?

5 10 7 3°C 3 Report date: 05/23/33

app

¥

al dar 4.4.4 molecular and and an all states of the set and beneficial and an addition with the set of the Complance Statement The proposed building design described here is consistent will be building plans, specification, and offen calculations

SAL - SURV

REScheck Software Version 4.4.4 Inspection Checklist

Requirements: 55.0% were addressed directly in the RESoheck software

Text in the "Commenia:Assumptions" column is provided by the user in the REScheck Regularments screen. For each regularment, the user particles that a code regularment will be met and how that is documented, or that an exception is being claimed. Where compliance is itemized in a ceptrate table, a reference to that table is provided.

| 2008 IECC | Pro-Inspection/Plan Review | Plane Verified Value | Field Verfiled Value | Complec? | Comments/Accumptions |
|-----------------------|---|---------------------------------------|--|--|--|
| | Construction drawings and observation demonstrate energy code compliance for the pulking envelope. | | - | Comples Eces Not Comply Not Observable Not Applicable | Requirement will be met Location on planskipeo: Suiding Section - Urfactors will be added |
| [P-22]? | Construction drawings and documentation demonstrate energy code compliance for lighting and mechanical systems. Systems serving multiple deetiling units must demonstrate compliance with lite commencial code. | | | Complex Does Not Comply Not Coservable Not Applicable | |
| 433.5 [FR2]0 17 | Heating and socing equipment is stret per ACCA Manual S based on loads per ACCA Manual J or other approved methods. | Hesting Bruin Cooling: Bruin | Hasting: Eduing: Cooling: Eduing: | Comples Does Not Comply Not Observable Not Applicable | |

Additional Commente/Accumptions:

1 High Impact (Ter 1) 2 Medium Impact (Ter 2) 3 Low Impact (Ter 3)

Fraject Tille:

Osta filename: O/Bocuments and Settings/Joy Feol-StyleIds/My Documents/REScheck/straffon 3.rdt

Report date: CS.CD/13 Fage 3 of 19

| 2069 IECC | Foundation increation | Plans Vertiled Value | Field Verified Value | Complies? | Comments/Assumptions |
|---|---|-------------------------|-------------------------|--|--|
| 432-1.1 (FOS) ¹ -0- | Sias coge insulation R-value. | R Unhested Hested | | Comples Does Not Comply Not Observable Not Applicable | See the Ennelope Acceminics 1956 for writes |
| 233.2, 4 <u>12.2.8</u> [FCQ]' | Sian edge insulation installed per manufacturer's instructions. | | | Comples Does Not Comply Not Copervable Not Applicable | Requirement will be met. Location on planskpec: Suiding section |
| 432.5.1 [FCQ] ² | Sao enge insulation depth/ength. | t | | Comples Does Not Comply Not Observable Not Applicable | See the Lineope Accenticated Structura |
| 432.9.1 [FO4] [:] 12 | Conditioned becement well incutation (Ryalue, Where Interfor Insutation Is (used, verification may need to occur clusing incutation inspection. Not required in warm-humid locations in (Climate Zone 3. | Fr | | Comples Does Not Comply Not Ciservable Not Applicable | See the Envelope Accentities lette Er vertes |
| 333.2 (FCE): (2* | Conditioned basement wall insulation Installed per manufacturaris Instructions | | | Comples Does Not Comply Not Observable | Requirement will be met Location on planetepeo: Building section |
| 4 <u>92.2.7</u> [FCE]: | Conditioned basement wall insulation deoth of burial or distance from top of wall. | t | | Comples Does Not Comply No! Observable No! Applicable | See he invelope Amenöter lebe in valuer |
| 8382.1 FOMP 36 | A protective covering is installed to protect exposed exterior insulation and extends a minimum of 6 in, below grade. | | | Comples Does Not Comply Not Observable Not Applicable | Requirement will be met. Location on plansispec: Suiding sectors |
| 43118 (F012)* | Snow and los-meting system controls installed. | | | Comples Does Not Comaly Not Observable Not Applicable | |

Additional CommentalAccumptions:

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 2)

| 2009 IECC | Franking. (Rezign-In Inspection | Plane Verified Value | Field Verified Value | Complies? | Comments/Assumptions |
|--|--|-------------------------|-------------------------|---|--|
| 4 <u>32 1.1,</u> 432 3.4 [FR1] ¹ 24 | Deer CHactor. | Lī | U | Comples Does Not Comaly Not Observable Not Applicable | See the Envelope Accembles lebr branches. |
| 402.1.1, 472.3.1, 472.3.3, 472.5 (FFZ): 5 | Glazing U-factor (area-weighted average). | v | U | Comples Does Not Comply Not Observable Not Applicable | See the Envelope Assembles tob's to velope |
| 203:1.3 [FF4] [*] 2 | Unactions of teneotration products are determined in accordance with the MFRG test procedure or taken from the default basis. | | | Comples Does Not Comply Not Observable Not Applicable | Requirement will be met Location on plansiepes: will b odded |
| 432.1.1, 432.3.3, 432.5 (FRS) ³ | Skyögit L-factor. | U | U | Comples Does Not Comply Not Observable Not Applicable | See the Unvelope Accemister late for writes. |
| 4 <u>12 2.5</u> [FR3] [;] .2 | Sumoons enclosing consistent space have a maximum fenestration (unaction of 0.50 in Climate Sones 4-6) New glazing separating the sumoom from consistent space must meet code requirements. | U* <u>.</u> | U | Comples Does Not Comply Not Observable Not Applicable | Exception: Regularment is not applicable. |
| 4 <u>92 2,5</u> (FR9)' } ₂ , | Sumooms enclosing consistented space have a maximum skylight U- factor of E.75 in Câmate Zones 4-6. | <u>لة</u> | U | Complets Does Not Comely Not Observable Not Applicable | Exception: Requirement is not applicable. |
| 432.44 (FR33,% | Renestration that is not she built is Ested and abeled as meeting AANI-AWDNAVOSA 121/13_2/A443 or has infibration rates per NFRC 485 that do not exceed code Smis. | | | Comples | Requirement will be met |
| FRIS. | C-rated recessed lighting fatures obsided at howing interfor thick and labeled to indicate 2.0 cfm leakage at 15 Fe. | | | Complex Does Not Comaly Not Coservable Not Applicable | Requirement wil de met. |
| 433.2.1 (FR12)` (2) | Supply ducts in afflics are insulated to R-8. All other ducts in unconditioned spaces or outside the building envelope are insulated to R-6. | F F | R R | Comples Does Not Comply Not Observable Not Applicable | |
| 493.2.2 (FR13) 9 | Al joints and seams of airdusts, air Fanders, fürstbores, and building cavilies used as ream dusts are seated. | | | Comples Does Not Comply Not Observable Not Applicable | |
| 403.213 (FR1:57 ** | Suicing cavites are not used for supply clistic. | | | Complets Does Not Comply Not Observable | |
| 478.2 (FR17)- ² 2 ³ | HNAC piping conveying fulcts above 165 PP or chiled fulcts below 56 PF are insulated to R-3. | Fr | R | Complex Coes Not Comply Not Coservable Not Applicable | |
| 433.4 (FR:18)* | Circulating cervice holiwater pipes are inculated to R-1. | F | R | Comples Does Not Comply Not Coservable | |

| 1 High Impact (Ther 5) | 2 Wedium moset (Tier 2) | 3 Low tapact (Ther 3) |
|------------------------|-------------------------|-----------------------|

21/62/90 :9(20 9 0029) 9 :00 9 9203

| (C 1011) (CC211) (CC3 | ٦. | Medium mosets (That 2) | Ξ | |
|-----------------------|----|------------------------|---|--|
| | | | - | |

.

гасавартизаяналноо іспедіова.

•

| Sequirement 14 De met. Sequirement parageon (17) De Sequirem John H on parage | riemo: toki ceo⊒⊡ Diverset0 (oki⊡ | | | Automatic or gravity damping as bracies on all outdoor ar interest estimatics | ्रंडामच |
|---|--------------------------------------|---------------------------|------------------------|---|-----------|
| วทอชี่จุกบระม ั งมีกรามกรว | Sounding D | Beithe Veitifed Subs V | benney analt. eulav | natiosopal nucleuses (galmere | 2009 IECC |

and nothingly and set that an and a set of the :suff theight

8 10 1 sgart eneciao inied nogari

| (E red) thequal (E) (3 ref) (action musber) (2 (3 red) (required filer 3) | | |
|--|------|-----------------------------|
| 10 molt from the fight for the second s | | e i ta asa kesadan néndin l |
| | | |
| | | |

conoliganusoAlainemme0 inaoölbbA.

| | =\dz3ikgc+,icvi∏ | | · · · · · | | |
|--|---------------------|-------------------|--|---|------------------------------------|
| | | | | | |
| | Vernod to Magood | | | A REAL ADDRESS IN THE REAL ADDRESS ADDR | .[5148] |
| Exception: Regulationer; is not | | | · · · · | belickni z rokrazni orkeo moortuzi | 2322 |
| | ಕಿಡಲುಗಿನ್ನ⊀ (ನಗ⊟) | | | | 7.5 |
| 1 | sidevneset0 tevi⊡ | | | .8-8 2003 start.30 ii) b0-R bits | 54 |
| applicato en | riemos toMezeo3∐ | | | ·누·I Send 관리에서 이나고환 Zones 1~4, | 1311EL: |
| Exception: Regularment is not | ⊐Comp3es | | | Roleinen manism größen moorue | 433314 |
| | £32231064 ; CM[] | | | | - |
| | elazonesato tovi | | | 1 | 7.1 |
| e cestate | vience towneed | | | anotantan sheringiansi | EMB |
| ton sithemanupes : noiseacea | | | | en destriction notification frances | 27562 |
| | | | | ี่กรณารายาว | |
| | | | | ebus feem kalm epoca benofièreo | 51 |
| | | | 1 | and motive sufficient for the second s | isteri |
| | NamoC 10// ceo2 | | | e sed rotaisatiken moorule. 215w web - 51-A to suisv-A marchine. | (186), 705 51 M |
| ton al memorinees : noticeous | :=;du:c)[] | | -3 | ar and a product of the statement of | 8-F L CSF |
| nothes garbles | ********** | | | | 56 |
| 1093929166 NO UC(2007) | · • · · · | | ار المنابقية المنظمة ا منظمة المنظمة ال | | |
| | vernoc to⊀ ceo⊒∏ | | | | ीसंसर्ध जनवन्त्र |
| An se liv transvera | | | <u></u> | nec belizioni of notice on 1544 | 33313 |
| | | | | | |
| | | _ | _ | secores: | 91 |
| | sidzoilogA toM⊡ | ar 19 🗋 | 1943 🗌 | instration results in the second second | ुंडायम् |
| | | 555M 📘 | 525N 🗌 | incuision on the wall extends, the | |
| "王氏是将 书 ,"" | Access tote contact | peony 🔲 | poow 🔲 | Den off to Mitzelife rith New Zeeth | 72727 |
| ədəl vəldirəzər əqələriri. Ərləsi | salamod 🗌 | | | e si shi ", shishfi notestan 95% | 1.6 207 |
| | | | : | C(1.5 TEL:00() | e i |
| Baild by Section Location on Distriction: | | | | ebaeon en rix branz karzele | ્રાઝા |
| | ്വനോ 10% അവ]] | | | ניים העימונים, ב (ווכב הכובטיב' בעם א | 91727 |
| iem eg ikkinemenispefi | a:anco[] | | | Foor insulation installed per | 32313' |
| | · | (|) | | |
| | | 5 | 1 | 4 4 | |
| | | 🖂 🖂 | 🗯 🖂 | | .1140 |
| | | | | | 97.362 |
| | vienco solo consist | -2 | | Foor insulation Realize. | र 35 उ. 2' र 35 र 1' |
| edel reichterie egalennig en sei | Contras | <u></u> | | | |
| | | | | , > | j. |
| | | the second second | |) The second s | E-1 M |
| | wence bW.c≥o3□ | | |) attino be(add) is notisilaria seitatai) (A.) (attino be(add) is notisilaria (A.) | ielnii See J |
| sem se Aw Itempology | | 1 | | l 1 melesus instantes et envises cesi englisetes (15. | . <u>* 196</u> |
| | Londusar | agie a | enre/L | 810 002/2011 5100752240 | 5000 (ECC |
| anotionusaA/aineminoO | foellomo0 | dering dert | beline's and a | epitoecon) epitopea | 00310000 |
| | | 1 | 1 | | |

| 2009 IECC | Final Inspection Providens | Plans Verified Value | Field Verified Value | Complies? | Comments/Accumptions |
|---|---|---------------------------|--------------------------|---|---|
| 402 1.1, 402 2.1, 402 3.2 [11] [11] | Cering insulation Revalue. Where > Re- SD is required, R-SD can be used if insulation is not compressed at eaves. R-SD may be used for SDD fillion 20% (whichever is isso) where sufficient space is not available. | R [] (Wood [] Size) | R Wood Stee! | ☐Compiles ☐Does Not Comply ☐Not Observable ☐Not Applicable | Zee ite inestope Arrentider isde to veder |
| 333.2 | Celling insulation installed per manufacturer's instructions. Blown insulation marked every 320 dR | | | ☐Complex □Does Not Comply □Not Observable □Not Applicable | Requirement will be met. Lacation on planskaped: Eutoing section |
| 472.7.3 (F13): 33 | Alle access hatch and door insulation Revalue of the adjacent assembly. | F. <u></u> | 8 | Comples Coes Not Comply Not Observable Not Applicable | Requirement will be met. Location on plansispect will be added |
| (हा। इ.) ्रे | Sufficing envelope tightness verified by blower door test result of <7 ACH at 50 Pa. This requirement may instead be met via visual inspection, in which case verification may need to occur during insulation inspection. | ACH 53 = | | Comples | Requirement will be mail Location on planckspeo: Note will be added to drawings |
| 432.4.3 (FISF \} | Wood-burning freplaces have gasketed boom and outloor compusition ain | | | Complex Does Not Comply Not Observable Not Applicable | Requirement wil be met. Location on plansispect wil be added |
| | Fost construction react tightness test result of 9 citra to substant, or 12 citra across systems. Or, rough-in test result of 5 citra across systems or 4 citra without air handler. Rough-in test verification may need to occur during Reacting inspection. | cta | d n | Comples Does Not Comply Not Observable Not Applicable | |
| 433.9.1 (F19)* 4_6 | Frogrammable thermostats installed on forced air flamaces. | | | Complet Does Not Comply Not Observable Not Applicable | |
| 435.12 Fil15위 산 | Next pump thermosist installed on heat pumps. | | | Comples | |
| 433.4 [Fi11]) 산 | Circulating service not water systems have submatic or accessible manual controls. | | | Complets Does Not Comply Not Observable | |
| 433.5.1 (F112) ² 2* | Readly accessible switch on heaters for swittming pools. | | | Comples Does Not Comply No! Coservable Not Applicable | |
| 433.5.2 (FI15;3 (_* | Tumer switches on pool heaters and pumps are present. | | | Complets Coes Not Comply Not Observable Not Applicable | |
| 433.5.3 (FLDX) 9 | Heated swimming pools have a cover. Covers on pools heated over 50 % are insulated to 7-12. | | | Complex Does Not Comply Not Coervable | |
| 404.1 [FIS] ¹ 12 | SEN: of large in permanent failures are high efficiely larges. | | | Complex Does Not Comply Not Observable | |

•

| | 1 High Impact (Tiler 5) | 2 Modum Impact (Tlor 2) | 3 Low Impact (Tiler 3) | ĺ |
|------|-------------------------|-------------------------|------------------------|-------------------|
| | | | | |
| łiz- | | | 5 | enoridsie: 66(258 |

| 2008/IECC | Final Inspection Providions | Plans Verified Value | Reid Verified Value | Complies? | Commania:Accumptions |
|-----------------------------------|---|-------------------------|------------------------|--|--|
| 431.3 (F17) ³ 34 | Compliance certificate posted. | | | Complex Does Not Comply Not Observable Not Applicable | Requirement will be met Location on planckspec: Building Beckin - U factors will be added |
| 303.3 [F116] ⁴ 산 | Manufacturer manuals for mechanical and water beating equipment have been provided. | | | Compiles Does Not Compily Not Observable Not Applicable | |

Additional CommentalAccumptions:

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

V Efficiency Certificate

| | Waley Reals |
|--|----------------------------------|
| and the second | Cocking Systems |
| | |
| | inempinel graces & grand |
| 9 9 10 | រងខ្លាំសុខ |
| 070 | Bott |
| 18.0 | weined |
| 15115: | gnành mơi â nunh |
| | :[easeqs banoiñ็อกวรกษ] สาดสวยนี |
| 00 85 | Ceiling J Roof |
| 00104 | 100 B |
| 51'90 | liew |
| | griftel restated |

:sie@

:สายการว

:eury

Date Submitted

Village of Fox Point 7200 N. Santa Monica Blvd. Fox Point, WI 53217 (414) 351-8900

| No | 15547 | (Part2) |
|----|-------|---------|
| | | |

APPLICATION FOR BUILDING

The undersigned hereby applies for a permit to build, in accordance with the information tabulated hereafter,

| Lot | Block | Subdivision | District | |
|---------------------------|--|---------------------------------|--|--------------------|
| | structure violate the Village zoning ord | | | |
| Height of Structure | | | | _(stories or feet) |
| | nighway) | _(feet) Depth (perpendicular t | | |
| Distance: Street Li | ne to Front Line of Structure | | | (feet) |
| Distance: Side Lot | Line to Structure | | | |
| Type of Construction | DD: Frame, Brick-tile, etc. | Exterior finish_ | | |
| | | | Stucco, Siding, Brick Veneer, | Etc. |
| | d above street grade | | | |
| | | Baths | | |
| Gat Estimated cost But | ilding NO CITANGE | | | |
| Str | ucture | | | |
| Is there a private gara | nge? | | | |
| Does the contemplate | ed garage violate the Village zoning ordinance | ce? | | |
| Size | Number of Stalls | | Where Situated | |
| Have plans been su | bmitted to the Wisconsin Department of | f Industry, Labor and Human F | Relations for examination and approv | val? |
| Have plans been ap | proved as being in compliance with all | applicable sections of the Wise | consin Administrative code? | |
| Herewith are filed | the following duplicate plans | in r | number, which I certify I will conform | m to in the work |
| hereby applied for: | | | | |
| Remarks: Mor | DIFICATIONS TO SIDING, | WINDOWS & MIN | OR COSMETTIC IMPROVE | MENTS |

Herewith are filed the specifications that describe the work in question and as shown on plans above submitted.

In making the application the undersigned agrees to obey the Fox Point Building and Zoning Codes pertaining to the erection of all structures and also agrees to obey all other ordinances of the Village of Fox Point.

The undersigned, owner or being duly authorized so to do, hereby gives express authorization to the Village of Fox Point, its officers, agents and employees, to enter upon the premises herein described and fill up any excavation, or tear down, remove or enclose the unfinished structure for which a permit is herein requested in the event of cessation of the building, whenever the Building Inspector shall determine that such premises in the unfinished condition of the structure are dangerous to members of the public, including children, even though trespassers. The undersigned further hereby waives all statutory notices and consents to the determination by the Village Board and the levy and placing upon the tax roll of a special assessment in the amount of the cost to the Village, including customary Village overhead charges incurred in filling up any such excavation or tearing down, removing or enclosing any such unfinished structure.

We hereby agree to provide a house number plate or sign readily observable from the public highway which will be installed not less than 15 days after the structure is occupied.

| Owner of Structure RICK STRATION & KERLI SARAJIAN | Arch. or Contr WillED CONSTRUCTION MGMT LLC |
|--|---|
| Address 3009 N HACKETT AVENUE | Address 2022 E NORAH AVENUE |
| City MILWAUKE State W Zip 53 | City_MILLAAME State_61 Zip 53202 |
| Phone 414 - 534 - 6695 | Phone 414,915-7493 |
| Size of Structure(sq. ft.) I | Permit Fee NC Receipt |
| Dwelling Contractor Certification No. 1269359 | Expires |
| Dwelling Contractor Qualifier Certification No. <u>1003500</u> | Expires |
| Building Contractor Certification No | Applicant Signature |
| Date of Approved | Architect, Owner, Builder |
| Builder Inspector | |

| Wisconsin Division of Safety and Buildings | | | WISCONSIN PERMI | | IFORM I PPLICA' | | ING | | A. | oplicat کری | ipn No. No. | 55 | 47 |
|--|--|--|---|-------------------|-----------------------------------|-----------------------------|-----------------|---------------------------------|------------------------|---------------------------|---------------------------------|---------------------|--------------------|
| Wisconsin Stats. 101.63, | 101.73 | | on back of second r government agenc | | | | | | Pa | reel N | ło. | | _K |
| PERMIT REQUE | STED | ■ Constr. | | Ele | ctric | lumhing | σΠΕι | rosion | Cont | rol | Other: | | |
| Owner's Name | | | Mailing Addre | ess | | | | | | | Tel. | | |
| Contractor's Name: | | | N 3009 N | ' HA | Mailing Ac | Idress | | | | 21 | 414-5 | | |
| APPLEBROOK CO | | • | | | 3430 Meg | 100 Cou | u Mac | -NE 30 | RD. 92 | | Tel. 414-9 FAX# 414-9 | <u>15-1</u> 71-9 | 443 769 |
| Contractor's Name: □Co | on MElec I | HVAC DPlb | g Lic/Cert# | | Mailing Ad | | | | | | Tel. Lid- | 796- | 5585 |
| CURRENT ET | | • | - | | BREUK | FIED | | | | | FAX# 202- | 786- | 7856 |
| Contractor's Name: Co | | | | | Mailing Ad | Idress | | | | | Tel. 262- | 593 | -\$300 |
| LAKE COUNTRY | | | | 1 | OCONO | 3 tw | $r + \omega$ | 15 | 306 | 6 | FAX# 262-6 | <u> </u> | 8306 |
| Contractor's Name: □Co | | ∃HVAC ⊠ Pib | | 1 | Mailing Ad | Idress | ANE | コトノ | HE | | Tel ZEZ-T | | |
| ALPINE PLUME | ING | _ | 22698 | 52 | BRECK | FILD | | 53 | $\infty \in$ | 5 | 5262-7 | | |
| PROJECT LOCATION | Lot area 3 | 5,267 | Sq. ft. | | | | 1/4, | | | , Т | | | E (or) W |
| Building Address | | Sul | bdivision Name | | | | | Lot No | <u>, ц</u> | | Block No | | |
| 1015 E QUAR Zoning District(s) | ves pi | | FOR POINT : | | | | | | 7 | | <u></u> | <u> </u> | |
| Zoming District(s) | | Zoning Perm | 11 NO. | 0 | etbacks: | Front | ft. | Rear | ft. | Lef | t ft. | Right | ft. |
| 1. PROJECT | 3. OCCUI | | 6. ELECTRICAL | 9. | HVAC EQU | IPMENT | 12. EN | | | | | | |
| New CRepair | Single F | | Entrance Panel Amps: 200 | | Forced Air F Radiant Base | | Fuel Space H | | at Gas | LP | Oil Elec | Solid | Solar |
| □ Addition □ Move | □ Garage | | | | Heat Pump | | Water H | | \checkmark | | | | |
| □ Other: | Other: | | □ Overhead | | Boiler | | | | | | t or more in e | lectric s | pace |
| 2. AREA INVOLVED | 4. CONST | . TYPE | 7. FOUNDATION | | Central Air C Other: | Cond. | heating | equipme AT LOS | | ity. | | | |
| | Site-Bui | | | | ounci. | | 13. 116/ | | | · | | | |
| Unfin. Bsmt 2218 Sq Ft | 🗆 Mfd: 🗆 | WI UDC | □ Treated Wood | 10 | .sewer | | l | | | _ | BTU/HR | Fotal Ca | lculated |
| Living 12 il | | Ú.S. HUD | Other: | | Municipal | | - | | | | s ("Maximun | | ble |
| Area <u>4214</u> Sq Ft | 5. STORI | ES | 8. USE | | Sanitary Pern | nit No.: | - | | - | | Energy Work | | ľ |
| Garage <u>S72</u> Sq Ft | 2-Story | | Permanent | 11 | 11. WATER 14. EST. BUILD | | | ating Load" on WIScheck report) | | | | | |
| PROPOSED | □ Other: | | □ Other: | 8 | Municipal Ut | | \$800 | | | | | | |
| 1 | □ Plus Bas | | A: / / // // | _ | Private On-Si | | | | | | | | |
| I agree to comply with all app express or implied, on the sta I have read the cautionary sta authorized agent, permission | te or municip tement regar | oality; and certify ding contractor f | that all the above inf inancial responsibility | ormati y on th | ion is accurate e reverse side | e. If I am an of the last p | owner ap | plying for essly grat | or an ero nt the bu | sion co iilding | ontrol or cons inspector, or | truction | permit, ector's |
| APPLICANT'S SIG | | | | | | G Nord | | | | | | 112 | |
| | | | t is issued pursuant to | the fo | | | | - | | | | | |
| APPROVAL COND | 1 | permit or o | ther penalty. See | | hed for con | ditions of | approva | l | | | | | |
| Othe mplica | 4 | Wing A | LONE COM | 11- | f tros | <u>ر</u> م کو | -brok | syst | ŝ | [x1. | i to | Slar | fij |
| A The Araby | 4 | | | | <u>. (</u> | | نم ۱۱ | | | | | | <u></u> |
| THE THULL | - prose | | Village with | • | ne" A | 15 Buil | | vsse | | | er ionte | 7 /1 | Fler |
| The Format | <u>en 541</u> | ten 1 | complete + | | Very | × fine | | PRA | | <u>.</u> | | | |
| 3) The Applicant longlying with mi Applicantie Cone Repuinens for | | | | | | | | | | | | | |
| TOTIL | ISSUING Down of Willage of City of County of State Inspection Agency #: Municipality Number of Dwelling Location | | | | | | | | | | | | |
| ISSUING | □ Town of | 10 | | y of | □ State Inspe | ction Agenc | ;y#: M | unicipal | ity Num | berof∐ r | Dwelling Loc | ation | 1 |
| JURISDICTION | 14 | (The C | 1 | | | | | - | 4_1 | <u>-</u> | 121 | 2 | ļ |
| FEES: | | | RMIT(S) ISSUED | WI | S PERMIT S | EAL# | PERMIT | ISSUE | D BY: | | | | |
| Plan Review \$ Inspection \$ | 7,600 | | Construction HVAC | | | | Name | S.ot | 4 1 | hill | (| | |
| Wis. Permit Seal \$ | 30. | <u>c</u> | Electrical | . | ſ. | | | 1.1. | · / | _ | | 1 2- | - |
| Other Ocip. <u>\$</u> | 100. 200 | | Plumbing | ' | 12823 | 0 | Date 🖁 | | Te | al. 🤆 | 414)35 | 1-87 | <u>n</u> |
| fotal \$ | 1, 9 <u>3</u> 2. | | Erosion Control | | · · · | | Cert No. | | 702 | 29 | | | _ |
| BD-5823 (R.4/02) D | istribution: | Ply 1 - Issuing J | Iurisdiction DPly 2 - | Muni | cipality Forwa | ards to State | If New D | welling | DPly 3 | 3 - Insp | ector Piy | - Appl | icant |
| Poci | # 4541 | в 14/ | 13 | | | | | | | | | | |

•

•

| of Safety and Buildings PERMIT | | | | UNIFORM BUII T APPLICATION | | Applicat | | |
|---|--|---|--|---|--|---|--|---------------------------|
| Wisconsin Stats. 101.63, | 101.73 | | s on back of second | d ply. The information yo | ou provide may be | Parcel N | lo. | |
| DEDMIT DEOLI | OTED | | | cy programs [(Privacy La | - | | 0.1 | |
| PERMIT REQUE Owner's Name | SIED | | $\frac{1}{10000000000000000000000000000000000$ | Electric 🗆 Plumb | \square Erosion C | ontrol | Other: | |
| RICK STRATTON & | KERI | SARATIA | N 3007 N | HACKETTANE ! | MUMANUE W | 5:3211 | 414-534-4 | Ĵ.G |
| Contractor's Name: ICc | on 🗆 Elec i | | og Lic/Cert# | Mailing Address | · | | Tel. | |
| APPLEPMCOLL CI | NISMIN | CTIONJ, IN | C 1073531 | 3430 W C | ount line R. I wi 5309 | р. 7 | EAV# | |
| Contractor's Name: □Co | | • | | | | معا | Tel | |
| CURRENT EI | | | | 12625 W | BURLEICH RD | | | |
| Contractor's Name: DC | | | og Lic/Cert# | 13200XFIE | D. IN1 5300 | 70 | | |
| | | | - | Mailing Address N に 333 桁 | un F | | Tel. 762-593 | -S |
| LAKE COUNTRY | | | | 1 DIONOMOL | UOC, WI 53 | 766 | FAX# 262-593- | 22 |
| Contractor's Name: □Co | on 🗆 Elec 🛛 | HVAC QPI | 0 | Mailing Address | | | Tel. 767 - 767 - 1 | 11 |
| ALPINE PLUME | ing. | | 22698 | 2 14590 W. C | -D. (21 530 | 195. 1757 - | FAX# - 797 | |
| PROJECT | Lot area | | | | | ر پ | 101- 144- | 11. |
| LOCATION | 3 | <u>5,267</u> | Sq. ft. | 1/4, | 1/4, of Section | , ٦ | - | E (o |
| Building Address | iee Or | Ar = Su | bdivision Name | | Lot No. | 11 | Block No. | |
| $\frac{1015}{2000} = 00000000000000000000000000000000$ | NED PL | Zoning Pern | t <u>na point i</u> nit No. | SUBDIVISION | | | | |
| | | | | Berbucks. | ft. | ft. | ft. | |
| 1. BROJECT ☐ New □ Repair | 3. OCCUI | | 6. ELECTRICAL | | | | | 1 |
| □ Alteration □ Raze | Single F | | Entrance Panel Amps: <u>200</u> | ☐ Forced Air Furnace ☐ Radiant Basebd/ Pan | el Space Htg | ÷ + + | Oil Elec Solid | |
| □ Addition □ Move | 🗆 Garage | , | | □ Heat Pump | Water Htg | | | |
| □ Other: | □ Other: | | Overhead . FOUNDATION | ☐ Boiler ☐ Central Air Cond. | | | tt or more in electric s | pac |
| 2. AREA INVOLVED | 4. CONST | . ТҮРЕ | ☐ Concrete | | heating equipment 13. HEAT LOSS | capacity. | ······ | |
| Unfin. | C'Site-Bui | lt | ☐ Masonry | | | | | |
| Bsmt <u>7-2-13</u> Sq Ft | □ Mfd: □ | | | 10. SEWER | | _ | BTU/HR Total Ca | |
| Living Area <u>47.15</u> Sq Ft | 5. STORE | U.S. HUD | □ Other: \\\ 8. USE | G [*] Municipal | | | es ("Maximum Allowa | ible |
| Alea <u>- 1-1 - S</u> q Ft | | L0 | □ Seasonal | □ Sanitary Permit No.: | | - | h Energy Worksheet; on WIScheck report) | |
| Barage <u> </u> | ₽ 2-Story | | O ^P ermanent | 11. WATER | 14. EST. BUILDE | - | | |
| Pilofie 725 Sa Ft. | □ Other: □ Plus Bas | omont | □ Other: | ☐ Municipal Utility □ Private On-Site Well | \$200,000 | <u>, çç</u> | | |
| | | | | | inderstand that the issuan | e of the per | mit creates no legal li | abil |
| | nlicable code | s statutes and o | | | | le or me per | mut creates no legar n | аши |
| I agree to comply with all ap express or implied, on the sta | te or municip | pality; and certif | y that all the above in | formation is accurate. If I an | n an owner applying for a | an erosion c | ontrol or construction | рег |
| I agree to comply with all ap express or implied, on the sta I have read the cautionary sta | ate or municip atement regar | pality; and certif ding contractor | y that all the above in financial responsibilit | formation is accurate. If I an y on the reverse side of the 1 | n an owner applying for a ast ply. I expressly grant | the building | inspector, or the insp | per ecto |
| I agree to comply with all ap express or implied, on the sta I have read the cautionary sta authorized agent, permission | ate or municip atement regar to enter the p | pality; and certif ding contractor premises for whi | y that all the above in financial responsibilit ch this permit is soug | formation is accurate. If I an y on the reverse side of the 1 ht at all reasonable hours and | m an owner applying for a ast ply. I expressly grant to for any proper purpose to the second se | the building to inspect th | inspector, or the inspector, which is being | per ecto |
| I agree to comply with all ap express or implied, on the sta I have read the cautionary sta | ate or municip atement regar to enter the p | pality; and certified ing contractor premises for white \mathbf{E}_{1} | y that all the above in financial responsibilit ch this permit is soug | formation is accurate. If I at y on the reverse side of the I ht at all reasonable hours and GREG N | n an owner applying for a ast ply. I expressly grant d for any proper purpose are trong DATE | the building to inspect th SIGNEI | inspector, or the inspector which is being $\mathbf{D} = \frac{1}{2} $ | per ecto do |
| I agree to comply with all ap express or implied, on the sta I have read the cautionary sta authorized agent, permission | ate or municipatement regar to enter the p | pality; and certified $ding$ contractor $ding$ contractor $ding$ | y that all the above in financial responsibilit ch this permit is soug | formation is accurate. If I at y on the reverse side of the I ht at all reasonable hours and \underline{GREG} A o the following conditions. F | n an owner applying for a ast ply. I expressly grant d for any proper purpose (17 trank) DATE Failure to comply may res | the building to inspect th SIGNEI | inspector, or the inspector which is being $\mathbf{D} = \frac{1}{2} $ | per ecto do |
| I agree to comply with all ap express or implied, on the sta I have read the cautionary sta authorized agent, permission APPLICANT'S SIG | ate or municipatement regaries to enter the patement of the pa | bality; and certif ding contractor premises for white E | y that all the above in financial responsibilit ch this permit is soug it is fissued pursuant to other penalty. | formation is accurate. If I at y on the reverse side of the I ht at all reasonable hours and \underline{CREG} A the following conditions. F e attached for conditions | n an owner applying for a ast ply. I expressly grant d for any proper purpose $\underline{(117)}$ triangle $\underline{(117)}$ DATE Failure to comply may rest of approval. | the building to inspect th SIGNEI ult in susper | inspector, or the inspector, $\mathbf{D} = \frac{2\pi}{2} \frac{1}{2} \frac{2\pi}{2} \frac{2\pi}{2} \frac{1}{2} \frac{2\pi}{$ | per ecto do |
| I agree to comply with all ap express or implied, on the sta I have read the cautionary sta authorized agent, permission APPLICANT'S SIG APPROVAL CONI | te or municij atement regar to enter the p GNATUR DITIONS | bality; and certif ding contractor premises for white E | y that all the above in financial responsibilit ch this permit is soug it is fissued pursuant to other penalty. | formation is accurate. If I at y on the reverse side of the I ht at all reasonable hours and \underline{CREG} A the following conditions. F e attached for conditions | n an owner applying for a ast ply. I expressly grant d for any proper purpose $\underline{(117)}$ triangle $\underline{(117)}$ DATE Failure to comply may rest of approval. | the building to inspect th SIGNEI ult in susper | inspector, or the inspector, $\mathbf{D} = \frac{2\pi}{2} \frac{1}{2} \frac{2\pi}{2} \frac{2\pi}{2} \frac{1}{2} \frac{2\pi}{$ | per ecto do |
| I agree to comply with all ap express or implied, on the sta I have read the cautionary sta authorized agent, permission APPLICANT'S SIG APPROVAL CONI | Attended of the second | pality; and certif ding contractor premises for whith E | y that all the above in financial responsibilit ch this permit is soug it is issued pursuant to other penalty. See | formation is accurate. If I at y on the reverse side of the I ht at all reasonable hours and $GREG \Lambda$ the following conditions. If attached for conditions | n an owner applying for a ast ply. I expressly grant d for any proper purpose (17.17777) DATE Failure to comply may res of approval. | the building to inspect th SIGNEI ult in susper | inspector, or the insp te work which is being $D = \frac{21/3}{20} \frac{1}{20}$ nsion or revocation of | per cto do: this |
| I agree to comply with all ap express or implied, on the sta I have read the cautionary sta authorized agent, permission APPLICANT'S SIG APPROVAL CONI | Attended of the second | pality; and certif ding contractor premises for whith E | y that all the above in financial responsibilit ch this permit is soug it is issued pursuant to other penalty. See | formation is accurate. If I at y on the reverse side of the I ht at all reasonable hours and $GREG \Lambda$ the following conditions. If attached for conditions | n an owner applying for a ast ply. I expressly grant d for any proper purpose (17.17777) DATE Failure to comply may res of approval. | the building to inspect th SIGNEI ult in susper | inspector, or the insp te work which is being $D = \frac{21/3}{20} \frac{1}{20}$ nsion or revocation of | per cto do: this |
| I agree to comply with all ap express or implied, on the sta I have read the cautionary sta authorized agent, permission APPLICANT'S SIG APPROVAL CONI | Attendent regar to enter the p SNATUR SITIONS | ality; and certif ding contractor premises for white E | y that all the above in financial responsibilit ch this permit is soug it is fisued pursuant to other penalty. See finance for the finance for the financial responsibility for the finance for the finance for the finance for the finance for the finance for the finance for the finance for the finance for the finance for the finance for the finance for the finance for the finance for the finance for the finance for the finance for the finance for the finance for the finance for the fina | formation is accurate. If I and y on the reverse side of the I ht at all reasonable hours and $CREG \Lambda$ the following conditions. If a attached for conditions $M \rightarrow Economic\Lambda \rightarrow K Bb UCAFY \leq M$ | n an owner applying for a ast ply. I expressly grant d for any proper purpose (<u>arctvictu</u>) DATE ailure to comply may res of approval. | the building to inspect th SIGNEI ult in susper Transformer Transformer | inspector, or the insp te work which is being $D = \frac{21/3}{20} \frac{1}{20}$ nsion or revocation of | do this |
| I agree to comply with all ap express or implied, on the sta I have read the cautionary sta authorized agent, permission APPLICANT'S SIG APPROVAL CONI | Attendent regar to enter the p SNATUR SITIONS | ality; and certif ding contractor premises for white E | y that all the above in financial responsibilit ch this permit is soug it is fisued pursuant to other penalty. See finance for the finance for the financial responsibility for the finance for the finance for the finance for the finance for the finance for the finance for the finance for the finance for the finance for the finance for the finance for the finance for the finance for the finance for the finance for the finance for the finance for the finance for the finance for the fina | formation is accurate. If I at y on the reverse side of the I ht at all reasonable hours and \underline{CREG} A the following conditions. F e attached for conditions | n an owner applying for a ast ply. I expressly grant d for any proper purpose (<u>arctvictu</u>) DATE ailure to comply may res of approval. | the building to inspect th SIGNEI ult in susper Transformer Transformer | inspector, or the insp te work which is being $D = \frac{21/3}{20} \frac{1}{20}$ nsion or revocation of | per cto do: this |
| I agree to comply with all ap express or implied, on the sta I have read the cautionary sta authorized agent, permission APPLICANT'S SIG APPROVAL CONI D tole complete The complete D tole complete The complete D tole complete The complete D tole complete | A A A A A A A A A A A A A A A A A A A | pality; and certif ding contractor premises for white $\mathbf{E} = \frac{2}{2}$ This perm permit or of the second s | y that all the above in financial responsibilit ch this permit is soug this permit is soug this issued pursuant to other penalty. \Box See Lare Comp Lare Comp | formation is accurate. If I and y on the reverse side of the I ht at all reasonable hours and $CREG \Lambda$ the following conditions. If a attached for conditions $M \rightarrow Economic\Lambda \rightarrow K Bb UCAFY \leq M$ | n an owner applying for a ast ply. I expressly grant d for any proper purpose to (17 trian) DATE ailure to comply may res of approval. | the building to inspect th SIGNEI ult in susper Transform Transform | inspector, or the insp te work which is being $D = \frac{21/3}{20} \frac{1}{20}$ nsion or revocation of | per do |
| I agree to comply with all ap express or implied, on the sta I have read the cautionary sta authorized agent, permission APPLICANT'S SIG APPROVAL CONI D to be traph The Agents of Europe 4 | A A A A A A A A A A A A A A A A A A A | pality; and certif ding contractor premises for white E | y that all the above in financial responsibilit ch this permit is soug it is Issued pursuant to other penalty. See <u>Uillocpenet in the</u> <u>Uillocpenet in the</u> <u>Uillocpenet</u> | formation is accurate. If I at y on the reverse side of the I ht at all reasonable hours and $\underline{CREG \ N}$ o the following conditions. If a attached for conditions $\underline{M} - \underline{Fersensen}$ $\underline{M} - \underline{Fersensen}$ $\underline{M} - \underline{Fersensen}$ $\underline{M} - \underline{Fersensen}$ $\underline{M} - \underline{Fersensen}$ | n an owner applying for a ast ply. I expressly grant d for any proper purpose to (17 trian) DATE ailure to comply may res of approval. | the building to inspect th SIGNEI ult in susper Transform Transform | inspector, or the inspector, which is being $D = \frac{2}{2} \frac{1}{2} \frac{2}{2} \frac{1}{2} \frac{1}{2} \frac{2}{2}$, and the inspector of $\frac{2}{2} \frac{1}{2} \frac{1}$ | per do |
| I agree to comply with all ap express or implied, on the sta I have read the cautionary sta authorized agent, permission APPLICANT'S SIG APPROVAL CONI Date Contection Date Contection Date Contection Date Contection Date Contection Date Contection Date Contection Date Contection | A A A A A A A A A A A A A A A A A A A | pality; and certif ding contractor premises for white E | y that all the above in financial responsibilit ch this permit is soug this issued pursuant to other penalty. See Complete to the complete to the the complete to the complete to the the complete to the complete | formation is accurate. If I are y on the reverse side of the I ht at all reasonable hours and $\underline{CREG \ N}$ the following conditions. If a stached for conditions $\underline{M-4}$ Frequency $\underline{M-4}$ Frequenc | n an owner applying for a ast ply. I expressly grant d for any proper purpose I (1) | the building to inspect th SIGNEI ult in susper Transformer instruction Number of | inspector, or the inspector, which is being $D = \frac{2}{2} \frac{1}{2} \frac{2}{2} \frac{1}{2} \frac{1}{2} \frac{2}{2}$, and the inspector of $\frac{2}{2} \frac{1}{2} \frac{1}$ | per do |
| I agree to comply with all ap express or implied, on the sta I have read the cautionary sta authorized agent, permission APPLICANT'S SIG APPROVAL CONI D tole conclusion D tol | A A A A A A A A A A A A A A A A A A A | pality; and certif ding contractor premises for white E 22 This perm permit or of a diagonal of the second permit or of a diagonal of the second permit or of a diagonal of the second permit of the second permit of the s | y that all the above in financial responsibilit ch this permit is soug it is fisued pursuant to other penalty. See <i>Low Compared to the penalty</i> <i>Construction</i> | formation is accurate. If I at y on the reverse side of the I ht at all reasonable hours and $\underline{CREG \ N}$ o the following conditions. If a attached for conditions $\underline{M} - \underline{Fersensen}$ $\underline{M} - \underline{Fersensen}$ $\underline{M} - \underline{Fersensen}$ $\underline{M} - \underline{Fersensen}$ $\underline{M} - \underline{Fersensen}$ | n an owner applying for a ast ply. I expressly grant i d for any proper purpose i (17.17471) DATE ailure to comply may res of approval. | the building to inspect th SIGNEI ult in susper True True True True True True True Tr | inspector, or the inspector, which is being $D = \frac{1}{2} + \frac{1}$ | per cto do: this |
| I agree to comply with all ap express or implied, on the sta I have read the cautionary sta authorized agent, permission APPLICANT'S SIG APPROVAL CONI D tole conclusion That Presson D tole conclusion D tole conclusion | A A A A A A A A A A A A A A A A A A A | pality; and certif ding contractor premises for white E | y that all the above in financial responsibilit ch this permit is soug it is fisued pursuant to other penalty. See Construction HVAC | formation is accurate. If I are y on the reverse side of the I ht at all reasonable hours and $\underline{CREG \ N}$ the following conditions. If a stached for conditions $\underline{M-4}$ Frequency $\underline{M-4}$ Frequenc | n an owner applying for a ast ply. I expressly grant i d for any proper purpose i (17.17471) DATE ailure to comply may res of approval. | the building to inspect th SIGNEI ult in susper Transformer instruction Number of | inspector, or the inspector, which is being $D = \frac{1}{2} + \frac{1}$ | per cto do: this |
| I agree to comply with all ap express or implied, on the sta I have read the cautionary sta authorized agent, permission APPLICANT'S SIG APPROVAL CONI D tole contents Tole contents D tole co | A A A A A A A A A A A A A A A A A A A | pality; and certif ding contractor premises for white E | y that all the above in financial responsibilit ch this permit is soug it is fisued pursuant to other penalty. See <i>Low Construction</i> HVAC Electrical | formation is accurate. If I at y on the reverse side of the I ht at all reasonable hours and \underline{CRCG} A the following conditions. If attached for conditions $\underline{M} - \underline{F}_{CAC}$ $\underline{M} - \underline{F}$ | n an owner applying for a ast ply. I expressly grant i d for any proper purpose i (17.174A) DATE ailure to comply may res of approval. <u>Ante</u> Constant <u>Matter Constant</u> <u>PERMIT ISSUED</u> Name | the building to inspect th SIGNEI ult in susper Transform Transform Number of SY: | inspector, or the insp te work which is being D <u><u><u><u></u></u><u><u><u></u><u><u></u><u><u></u><u><u></u><u><u></u></u><u><u></u><u><u></u><u></u><u></u><u></u><u></u><u></u></u></u></u></u></u></u></u></u></u> | this |
| I agree to comply with all ap express or implied, on the sta I have read the cautionary sta authorized agent, permission APPLICANT'S SIG APPROVAL CONI D to be explose The explose D to be explose The explose D to be explose | te or municij atement regar to enter the p SNATUR DITIONS 4 1 1 1 1 1 1 1 1 1 1 1 1 1 | pality; and certif ding contractor premises for white E 2 This perm permit or of A = 11 A = 11 | y that all the above in financial responsibilit ch this permit is soug it is fisued pursuant to other penalty. See Construction HVAC | formation is accurate. If I are y on the reverse side of the I ht at all reasonable hours and $\underline{CREG \ N}$ the following conditions. If a stached for conditions $\underline{M-4}$ Frequency $\underline{M-4}$ Frequenc | n an owner applying for a ast ply. I expressly grant of d for any proper purpose of (17.17471) DATE ailure to comply may res of approval. | the building to inspect th SIGNEI ult in susper Transition Transitta Transitta Transition Transition Transitio | inspector, or the inspector, which is being $D = \frac{1}{2} + \frac{1}$ | this |
| I agree to comply with all ap express or implied, on the sta I have read the cautionary sta authorized agent, permission APPLICANT'S SIG APPROVAL CONI D tole Apple That Pressore D tole Apple D tole Apple D tole Apple D tole Apple S The Apple S Th | te or municipatement regarito enter the point of the poin | pality; and certif ding contractor premises for white This permit permit or of a line and permit or of a line and permit or of | y that all the above in financial responsibilit ch this permit is soug it is fissued pursuant to other penalty. See <u>Villocp</u> 30 it <u>rices 25 it</u> <u>rices 15 it <u>rices 15 it</u> <u>rices 15 it</u> <u>rices 15 it <u>rices 15 it</u> <u>rices 15 it</u> <u>rices 15 it <u>rices 15 it</u> <u>ri</u></u></u></u> | formation is accurate. If I at y on the reverse side of the I ht at all reasonable hours and \underline{CRCG} A the following conditions. If a attached for conditions $\underline{M} - \underline{F}_{CAC}$ $\underline{M} - $ | n an owner applying for a ast ply. I expressly grant d for any proper purpose f (1) CIVMAN DATE Failure to comply may res of approval. | the building to inspect th SIGNEI ult in susper Trans Trans STran | inspector, or the inspector, which is being $D = \frac{1}{2} + \frac{1}$ | this |

| Receipt No: 1.045403 | | Nov 01, 2013 |
|---|-------------------|--------------------|
| • | 1015 E QUARLES PL | |
| LICENSES & PERMITS-BU 24-44460 BUILDING PERM | | 7,600.00 |
| LICENSES & PERMITS-BU 24-44460 BUILDING PERM | | 30.00 PLICATION |
| LICENSES & PERMITS-OC 24-44420 OCCUPANCY PE | | 100.00 |
| LICENSES & PERMITS-OT 10-44540 OTHER PERMIT | HER PERMIT | 200.00 |
| Total: | | 7,930.00 |
| CHECK Chk Total Applied: | No: 2567 | 7,930.00 |
| Change Tendered: | | .00 |
| | | |

.

1

11/01/13 10:58am

r

>

VILLAGE OF FOX POINT 7200 N. SANTA MONICA BLVD FOX POINT, WI 53217

414-351-8900

SITE INFO

| SUBDIVISION | | |
|---------------------------------|-------------------|--------|
| LOT NO | BLOCK NO | |
| ZONING DISTRICT | | |
| 1/4, | 1/4, SEC, T, N, F | E or W |
| PARCEL NO SETBACKS: FRONT | ft REAR | ft |
| LEFT | ft RIGHT | ft |

Work shall not proceed until the inspector has approved the various stages of construction or the 2 business day period since notification has elapsed. This permit will expire ___24 months after the date of issuance if the building's exterior has not been completed. Keep this card posted until final inspection has been made. (WI Stats. 101.63) ______

| WISCONS | IN UNIFOR | RM | |
|---------------|-----------------|-----------|----------------------------------|
| RII | ILD | IN | WILSCONSIN UNIFORM HEILING |
| | | | |
| PRI | RM | # | |
| | | | 5547 |
| Constr | JHVAC EI | ect Plun | b Erosion |
| (Project: | | | |

| IN | SPECT | IONS | |
|------------------|---------|----------|----------|
| PHASE | ROUGH | FINAL | EROSION |
| FOOTING | | | |
| FOUNDATION | <u></u> | | <u> </u> |
| BSMT DRAIN TILES | | <u> </u> | 1 |
| CONSTRUCTION | | | |
| PLUMBING | | | |
| HEAT/VENT/AC | | | |
| ELECTRICAL | | | |
| INSULATION | | | |
| OCCUPANCY | | | |

| Issued | OWNER (AGENT) Ricic Gratic |
|--------|---|
| То | BUILDING SITE ADDRESS 1015 E QUALES PINE |
| | CITY VILLAGE TOWN For Port, WI 53217 |

| CONTRACTORS | | | | |
|-------------|---------------------------------------|-----|--|--|
| | | # | | |
| | G.C. | | | |
| | | # | | |
| | HVAC | | | |
| | | # | | |
| | ELECT. | ui. | | |
| | | # | | |
| ì | PLBG. | 41 | | |
| | · · · · · · · · · · · · · · · · · · · | # | | |
| | | | | |

| Issued | PERSONUSSUING | nilk | CERT. NO. 7-222 |
|---|--------------------|--------------------------|---------------------------------|
| by | DATE ISSUED | TELEPHONE | 351-89.00 |
| Commen | | | |
| Sec Con | ditions Permit | Noted on | Back |
| - NOTICE OF NONCO of any violations to be of | MPLIANCE: This iss | suing jurisdiction shall | notify the applicant in writing |

SBD-5824 (R. 05/00)

THIS BUILDING PERMIT IS SUBJECT TO THE FOLLOWING:

- 1. The applicant installing a code compliant erosion control system prior to starting this project.
- The applicant providing the Village with an "As-Built" survey immediately after the foundation system is completed to verify setback compliance.
 The applicant complying with all applicable code requirements.

| Wisconsin Division of Safety and Buildings | | | WISCONSIN U | | | ING | | Application No. | | | | |
|--|-----------------------------|------------------------|---|--|-------------------------|----------------------|-------------------------------|---|---|-----------------------|------------|--|
| Wisconsin Stats. 101.63, 1 | | | ns on back of second p | | on you p | | | Parcel N | 0. | 554 | <u>e</u> / | |
| DEDMITEDIAMER | | | | <u> </u> | | | | ontrol | Other | | | |
| PERMIT REQUESTED & Constr. HVAC Electric Plumbing Erosion Control Other: Owner's Name RICK STRATTON & KERI SARAJIAN 3009 N HACKETT AVE, MILWAVILEE WI 53211 414-534-6695 | | | | | | | | | | | | |
| RICK STRATTON & KERI SARAJIAN 3009 N HACKETT AVE MILWAULES W/ 53211 | | | | | | | | | | | | |
| APPLEBREUK CC | | | m | 3430 | w Cou | MAN | LINE R | D. | | 15-7 | 43 | |
| Contractor's Name: Con | | . • | | 2/Cert# Mailing Address 12625 W BURLEIGH RD | | | | | | | | |
| CURRENT EL | | | | 12625 Bleak | W Bu | RIEI | ын КD 5300 | 5 | EAV# | <u>786-5</u> 786-7 | | |
| Contractor's Name: Con | | | lbg Lic/Cert# | Mailing Add | ress | | 00 0 | <u> </u> | Tal | <u>180-1</u> 593- | | |
| LAKE COUNTRY | | , | | N6332 OCONOV | s mus | / + c, W | 1 534 | >66 | EAV4 | <u>593-8</u> | _ | |
| Contractor's Name: Con | | VAC MP | lbg Lic/Cert# | Mailing Add | | | | | Tel ZG2-7 | 9 7-4 | 130 | |
| ALPINE PLUMB | | | 22698 | - BROUKF | 400 | , | 53a | 55 | 赵雄-7 | | | |
| PROJECT LOCATION | Lot area 35 | ,267 | Sq. ft. | | 1/4, | 1/4, | of Section | , Т | N, F | E E | (or) W | |
| Building Address | ES PLA | E SI | ubdivision Name FOR POINT S | | | | Lot No. | 4 | Block No | 1 | | |
| Zoning District(s) | | Coning Peri | | | Front | | Rear | Lef | | Right | | |
| | 3. OCCUPAL | | 6. ELECTRICAL | 9. HVAC EQUI | PMENT | ft. 12. EN | ERGY SOU | ft. RCE | ft. | | ft. | |
| New □ Repair Alteration □ Raze | ☐ Single Fam □ Two Famil | | Entrance Panel Amps: 200 | Forced Air Fur | | Fuel Space I | | as LP | Oil Elec | Solid | Solar | |
| □ Addition □ Move | | 3 | Underground | □ Heat Pump | | Water 1 | Htg 🗸 | | | | | |
| □ Other: | □ Other: | | Overhead 7. FOUNDATION | □ Boiler □ Central Air Co | nd | | elling unit ha equipment o | as 3 kilowatt or more in electric space | | | | |
| 2 AREA INVOLVED | 4. CONST. T | YPE 2. | | □ Other: | | | AT LOSS | | | | 34 C.A | |
| Unfin. Bsmt_2218_Sq Ft | Site-Built | und | Masonry Treated Wood | 10.SEWER | 10.1000 Conce | | | | י סנו/ו דים | Fotol Cole | wlated | |
| Living | | S. HUD | □ Treated wood | Municipal | NA REALES | Envelo | pe and Infilt | ration Losse | BTU/HR Total Calculated ation Losses ("Maximum Allowable | | | |
| Atea 4214 Sq Ft | 5. STORIES | | | 🛛 Sanitary Permit No.: 🛛 Heating Equipmen | | | | t Output" on Energy Worksheet; | | | | |
| Garage 872 Sq Ft | □ 1-Story 2-Story | | □ Seasonal | | | | | eating Load" on WIScheck report) | | | | |
| 100 POS ED Deck 57.5 Sq Ft. | □ Other: □ Plus Basem | ent | □ Other: | Municipal Util | | | 0,000 | 00 | | | | |
| I agree to comply with all app | | | ordinances and with the c | l | | 1 | • | | mit creates no | legal lial | bility, | |
| express or implied, on the stat I have read the cautionary stat | e or municipali | ity; and certi | ify that all the above infor | mation is accurate. | If I am an | owner a | oplying for a | n erosion c | ontrol or cons | truction p | ermit, | |
| authorized agent, permission t | to enter the pre- | mises for wh | high this permit is sought | at all reasonable hou | urs and for | any prop | er purpose t | o inspect th | e work which | is being of | done. | |
| APPLICANT'S SIG | NATURE | | reg Mi- | | | |) DATE | | | 13 | | |
| APPROVAL COND | ITIONS | This perm permit or | nit is issued pursuant to the other penalty. \Box See a | e following condition ttached for condi | ons. Failu itions of | re to com approva | ply may resi 1. | ilt in suspe | nsion or revoc | ation of t | his | |
| Othe Applica | t jish | they M | + Love Comp | 14 tross | ہ کھ | -hal | syster | [MI | ; to | Slart | hij | |
| This Projec | , L | • | | | | | | | | | | |
| 3 The Apple | - prosini | | Villson with | nu" As | Bui | | wody | | erionte | 7 A7 | Fer | |
| The Formante | ~ Syle | <u>m y</u> | complete to | | <u>e pre</u> | | -mplu | | | | | |
| 3) The Applean | r Lom | ידיואית | with M A | plumeste | CONE | 44 | Unem | <u>, 17</u> | | | | |
| ISSUING | 🗆 Town of 🍾 | Willage of | f 🗆 City of 🗆 County | of State Inspect | ion Agenc | :y #: N | funicipality | Number of | Dwelling Loc | ation | { | |
| JURISDICTION | For | Por | | x | | | <u> </u> | | 12 | ¢ | | |
| FEES: | | -V-1 01 00 0 | PERMIT(S) ISSUED | WIS PERMIT SE | AL# | PERMI | I ISSUED E | Y | | | | |
| Plan Review \$ Inspection \$ | 7,000 | | Construction | | | Name | Sut | Mill | | | [| |
| Wis. Permit Seal \$ Other Occo. \$ | 30.00 | - 1 - | Electrical Plumbing | | | Date 🖁 | 10/113 | Tel (| 414 35 | 1-690 | 0 | |
| SEiver Count. | ن, ند 2 | 5 | Erosion Control | | | | | 0ZZ9 | | | - | |
| Total \$ | 1,930.00 | 2 - | | | | Cert No | | 0027 | | | | |

.....L

.

Distribution: DPly 1 - Issuing Jurisdiction DPly 2 - Municipality Forwards to State If New Dwelling DPly 3 - Inspector DPly 4 - Applicant

Wisconsin Department of Safety and Professional Services: Homepage

| Search for Individual or Company by Category here: | | | | | | | | | | |
|--|-------------------------------|--|--|--|--|--|--|--|--|--|
| Credential Type | Dwelling Contractor Qualifier | | | | | | | | | |
| Credential Status (required) | Not Expired | | | | | | | | | |
| Zip (or first three digits) | 53092 | | | | | | | | | |
| Last or Business Name | norman | | | | | | | | | |
| Search | | | | | | | | | | |

1 record(s) were returned by your search.

| ID | Name | City,State,Zip | Credential Type | Expiration |
|---------|------|----------------|-------------------------------------|------------|
| 1003500 | | | Dwelling Contractor Qualifier | 03/14/15 |

۲

| Search for Individual or Company by Credential ID here: | | | | | | | | | | |
|---|--|--|--|--|--|--|--|--|--|--|
| Specific Credential ID 831638 | | | | | | | | | | |
| Search | | | | | | | | | | |

1 record(s) were returned by your search.

| ID | Name | City,State,Zip | Credential Type | Expiration |
|--------|--------------------------|----------------------------|---------------------|------------|
| 831638 | APPLEBROOK CONSTRUCTION, | REESEVILLE WI 53579 | Dwelling Contractor | 04/08/14 |

http://apps2.commerce.wi.gov/SB_Credential/SB_CredentialApp/SearchById?cmd=Searc... 9/27/2013

VILLAGE OF FOX POINT BUILDING BOARD MINUTES JUNE 21, 2013

Christine Symchych, 7240 N. Barnett Lane, proposed patio and retaining wall. It was the consensus of the Building Board to approve this application subject to the applicant complying with the administrative requirements of Village code. More specifically, the applicant must obtain an Erosion Control Permit and provide the Building Inspector with the Village Engineer's Certification for this project as required by Section 17.4 of the Village code.

Anne Zizzo, 1526 E. Goodrich Lane, proposed window and door modifications including interior/exterior alterations. Contractor: Brookwater Construction. It was the consensus of the Building Board to approve this application subject to the following conditions:

- 1. The applicant providing the Village with a drawing of the existing building elevations.
- 2. The applicant providing the Village with a drawing of the revised (proposed) building elevations.
- 3. The applicant providing the Village with a header schedule which shows that the structural members are properly sized.

Jon & Abigail Bloom, 7125 N. Barnett Lane, proposed exterior changes to front elevation of home. Contractor: Rossi Construction. It was the consensus of the Building Board to approve this application.

Tom & Susan Parks, 1469 E. Lilac Lane, proposed interior/exterior improvements to existing detached garage. Contractor: RP Custom Homes, Inc. It was the consensus of the Building Board to approve this application subject to the following conditions:

1. The applicant providing the Village with documentation showing that the structural columns are properly sized.

Trent & Jackie Graham, 6702 N. Lake Drive, proposed retaining wall(s) as described in the application. (Tabled from June 7, 2013 Building Board meeting). It was the consensus of the Building Board to approve this application subject to the following conditions:

- 1. The applicant obtaining an Erosion Control Permit for this project required by Chapter #38 of the Village code.
- 2. The Village Inspector receiving the Village Engineer's certification for this project as required by Section 17.4 of the Village code.
- 3. The Village Attorney rendering an opinion indicating that the revised application is in compliance with the Village's Bluff Ordinance.

Rick Stratton, 1015 E. Quarles Place, proposed new single family dwelling with attached garage. It was the consensus of the Building Board to approve this application subject to the following conditions:

The applicant providing the Village with a signed and sealed survey showing that this project complies with Village code.

VILLAGE OF FOX POINT BUILDING BOARD MINUTES JUNE 21, 2013

2. The applicant providing the Village with wall bracing information as required by the Uniform Dwelling Code (UDC).

A. The applicant obtaining a fill permit.

5. The applicant submitting a revised building section to the Village which shows that this home will be constructed in accordance with the Village code.

-6. The roof system shall consist of a "Galvlume Plus" standing metal seam system as described during the meeting.

Adjourn

On motion of Stuart Rothman, seconded by David Seno, and unanimously carried the Building Board adjourned at 9:11 a.m.

Respectfully submitted,

Building Inspector



VILLAGE OF FOX POINT

MILWAUKEE COUNTY WISCONSIN

VILLAGE HALL 7200 N. SANTA MONICA BLVD. FOX POINT 53217-3505 414-351-8900 FAX 414-351-8909

September 23, 2013

Mr. Frederick Stratton Ms. Keri Sarajian 3009 North Hackett Avenue Milwaukee, WI 53211

Re: Grading and Drainage Plan for 1015 East Quarles Place

Dear Mr. Stratton and Ms. Sarajian:

I am writing with respect to the grading and drainage plan application submitted by you on or about June 24, 2013, and revised August 22, 2013, by CJ Engineering. Kapur & Associates was retained by the Village to review the grading and drainage plan and analysis and has provided me with their comments which were dated August 19 and September 4, 2013. CJ Engineering has addressed the comments and I find that the grading and drainage plan complies with the applicable portions of the Village Code. Therefore, I approve the grading and drainage plan subject to the following:

- 1. A culvert permit is required prior to commencement of construction. I have included a copy of the application with this letter.
- 2. All erosion control features must be installed prior to the start of construction.

Should you have any further questions regarding this matter, feel free to contact me at 414-351-8900.

Sincerely

Scott Brandmeier, P.E., Esq. Director of Public Works Village of Fox Point

cc: Scott Miller, Building Inspector Yuriy Amelyan, Kapur & Associates

VILLAGE OF FOX POINT

MILWAUKEE COUNTY WISCONSIN

VILLAGE HALL 7200 N. SANTA MONICA BLVD. FOX POINT 53217-3505 414-351-8900 FAX 414-351-8909

ž.

September 18, 2013

Mr. Frederick Stratton Ms. Keri Sarajian 3009 North Hackett Avenue Milwaukee, Wi 53211

Dear Mr. Stratton and Ms. Sarajian:

I am writing to inform you that, based on the recommendation from the Director of Public Works/Village Engineer, I have approved your application for a Solid Fill Permit for 1015 East Quarles Place (this letter shall serve as the permit), subject to the following conditions:

- You and your builder, currently identified as Butler Chase of Mequon, Wisconsin, and any of its subcontractors must comply with all applicable provisions of Section 18, Fox Point Village Code (FPC), entitled "Regulation of Solid Fill and Grades".
- 2. The expiration date of the permit is December 17, 2013. It may be renewed not more than two times in a calendar year per Section 18.6, FPC.
- 3. As all fill is from on-site sources, no trucking of fill to the site is permitted.
- 4. Compliance with the tree protection zone fencing plan and tree replanting plan approved by the Village Forester on August 29, 2013.
- 5. The hours of site operation/equipment operation/truck arrival and departure are limited to 7:00 a.m. to 5:00 p.m., Monday through Friday excluding holidays.
- 6. Monthly progress reports must be submitted to the Director of Public Works by the 10th calendar day of each month for the preceding month's fill activities. The progress reports must contain the following information:
 - a. Status of filling (percent complete);
 - b. Amount of fill material placed and removed from the work site in the past month and since commencement of the project; and
 - c. Updated filling project schedule.
- 7. Clean-up of dirt and debris left on Village streets as a result of excavation and filling operations must be performed at the end of each working day. Street sweeping must be done as needed but, at minimum, no less than once per week. Any exception to this must be approved by the Director of Public Works.
- 8. Erosion control measures for the fill area, such as the use of silt fencing, must remain in place until vegetation is established at the property. Vegetation must be adequately established by July 31, 2014.

Mr. Rick Stratton Ms. Keri Sarajian 1015 East Quarles Place Fill Permit September 17, 2013

- 9. Any proposed changes or amendments to the Fill Application and supplemental information that you submitted must be reviewed and approved by the Village before such changes or amendments are executed.
- 10. The Village reserves the right to request additional information and/or to impose additional requirements should the Village deem necessary.

Please contact Director of Public Works Scott Brandmeier if further assistance is needed with respect to this permit.

Sincerel

Melissa Bohse, Village Manager

cc: Director of Public Works Police Chief Village Inspector

Page 2



1015 E QUARLES A.

MiTek USA, Inc.

14515 North Outer Forty Drive Suite 300 Chesterfield, MO 63017-5746 314-434-1200

Re: r-5902-13 Stratton Residence

The truss drawing(s) referenced below have been prepared by MiTek USA, Inc. under my direct supervision based on the parameters provided by Accurate Housing Systems, Inc..

Pages or sheets covered by this seal: 121692323 thru 121692323

My license renewal date for the state of Wisconsin is July 31, 2014.

Wisconsin COA: 726-011

.


Lumber design values are in accordance with ANSI/TPI 1 section 6.3 These truss designs rely on lumber values established by others.



January 14,2014


Fox, Steve

The seal on these drawings indicate acceptance of professional engineering responsibility solely for the truss components shown. The suitability and use of this component for any particular building is the responsibility of the building designer, per ANSI/TPI 1.




ATTACH 1/2" PLYWOOD OR OSB GUSSET (15/32" APA RATED SHEATHING 32/16 EXP 1) TO EACH FACE OF TRUSS WITH 10d (3" X .131") NAILS DRIVEN THROUGH BOTH SHEETS OF PLYWOOD AND CLINCHED PER THE FOLLOWING NAIL SCHEDULE: 2 x 4's - 2 ROWS: SPACED @ 0-4-0 O.C. NAILS TO BE DRIVEN FROM BOTH FACES. STAGGER SPACING FROM FRONT TO BACK FACE FOR A NET 0-2-0 O.C. SPACING IN THE MAIN MEMBER. USE A MIN. 0-3-0 MEMBER END DISTANCE.

| | <u>⊢ 8-7-8</u> 8-7-8 | | <u> </u> | | <u>24-8-12</u> 7-9-4 | 1 | | | | | | |
|--|--|---|---|---------------------|--|---|--|--|--|--|--|--|
| Plate Offsets (X,Y): [6 | | | | | | | | | | | | |
| LOADING (psf) TCLL 30.0 TCDL 10.0 BCLL 0.0 * BCDL 10.0 | SPACING 2-0-0 Plates Increase 1.15 Lumber Increase 1.15 Rep Stress Incr YES Code IRC2006/TPI2002 | CSI TC 0.84 BC 0.80 WB 0.33 (Matrix-M) | DEFL in Vert(LL) -0.27 Vert(TL) -0.41 Horz(TL) 0.05 Wind(LL) 0.04 | 9-11 9-11 8 | l/defl L/d >999 360 >715 180 n/a n/a >999 240 | PLATES MT20 Weight: 110 lb | GRIP 197/144 FT = 10% | | | | | |
| | | | BRACING TOP CHORD BOT CHORD WEBS | Rigid ce 1 Row a | ed or 2-2-0 oc purlins eiling directly applied at midpt 5- s recommends that St | or 10-0-0 oc bracing. 9 | 10-0-0 oc bracing. | | | | | |
| WEDGE Left: 2x4 SPF Stud | | | | be ins | talled during truss eration guide. | | | | | | | |
| REACTIONS (lb/size) 2=1449/0-5-8 (min. 0-2-4), 8=1288/Mechanical Max Horz 2=267(LC 5) Max Uplift2=-75(LC 6), 8=-7(LC 7) FORCES (lb) - Max. Comp./Max. Ten All forces 250 (lb) or less except when shown. TOP CHORD 2-3=-2057/66, 3-5=-1782/83, 5-6=-987/134, 6-7=-1259/98, 7-8=-1231/70 BOT CHORD 2-11=-148/1711, 9-11=-38/1214 WEBS 3-11=-379/108, 5-11=0/574, 5-9=-777/73, 6-9=0/690, 7-9=-9/698 | | | | | | | | | | | | |
| NOTES 1) Unbalanced roof live loads have been considered for this design. 2) Wind: ASCE 7-05; 90mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; enclosed; MWFRS (low-rise) gable end zone and C-C Exterior(2) -110-8 to 11-8, Interior(1) 11-1-8 to 13-11-8, Exterior(2) 13-11-8 to 16-11-8, Interior(1) 19-11-8 to 21-7-0 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 3) Plates checked for a plus or minus 5 degree rotation about its center. 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads. 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf. 6) Refer to girder(s) for truss to truss connections. 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 8. 8) "Semi-rigid pitchbreaks including heels" Member end fixity model was used in the analysis and design of this truss. | | | | | | | | | | | | |
| L | fesion parameters and READ NOTES ON THE | S AND INCLUDED MITEK REI | | .02/26/20 | 13 BEFORE USE | | n - Hild allen stellen og stadger gegen i de de benedere de ger bezon. 1999 - Marine Arte allen de de stelle de | | | | | |
| Design valid for use only with MITek connectors. This design is based only upon parameters shown, and is for an individual building component. Applicability of design parameters and proper incorporation of component is responsibility of building designer - not truss designer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to insure stability dring construction is the responsibility of the erector. Additional permanent bracing of the overall structure is the responsibility of the building designer. For general guidance regarding fabrication, quality control, storage, delivery, erection and bracing, consult ANSI/TPII Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Pitale Institute, 781 N. Lee Street, Suite 312, Alexandria, VA 22314. If Southern Pine (SP) lumber is specified, the design values are those effective DS/01/2D13 by ALSC | | | | | | | | | | | | |



Installing & Bracing of Metal Plate Connected Wood Trusses

Numbering System



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS ICC-ES Reports:

ESR-1311, ESR-1352, ESR1988 ER-3907, ESR-2362, ESR-1397, ESR-3282

Southern Pine lumber designations are as follows:

SYP represents values as published by AWC in the 2005/2012 NDS SP represents ALSC approved/new values with effective date of June 1, 2013

© 2012 MiTek® All Rights Reserved



A General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

- Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
- Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
- Never exceed the design loading shown and never stack materials on inadequately braced trusses.
- Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
- 5. Cut members to bear tightly against each other.
- 6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TPI 1.
- 7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TPI 1.
- 8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
- Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
- 10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
- 11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
- Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
- 13. Top chords must be sheathed or purlins provided at spacing indicated on design.
- 14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
- 15. Connections not shown are the responsibility of others.
- 16. Do not cut or alter truss member or plate without prior approval of an engineer.
- 17. Install and load vertically unless indicated otherwise.
- Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
- Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
- 20. Design assumes manufacture in accordance with ANSI/TPI 1 Quality Criteria.

¥j ∙ €ĵ

| | | | | | DATE 01/09/14 PAGE 1 | | | | |
|--|-------------|--|----------------------|----------|---|--|--|--|--|
| DELIVERY SHIPLIST | | ORDER DATE | 12/02/13 | | ORDER # | | | | |
| | | REQUESTED DATE | 01/10/14 | | | | | | |
| ACCURATE HOUSING SYSTEMS | | DELIVERY DATE | 01/10/14 | | R-5902-13 | | | | |
| 2624 Corporate Circle, East Troy, WI 53120 | | DELIVERY INFO (ASSUM | ED ROLL-OFF UNLESS N | | | | | | |
| P: 262-642-3800 F: 262-642-2716 www.accuratehousing.com | المين | Roll off delivery | ć | | | | | | |
| | | | | | DESIGNER: Justin Nagl Ext. 7013 | | | | |
| Wisconsin Building Supply - | JOB NAM | E: Stratton Residence | SUBD | IVISION: | | | | | |
| SOL | MODEL: | ELEV | ATION: | RAKE | SHEATH MAT: | | | | |
| D T O | | PECIAL INSTRUCTIONS: IEW PRICE REFLECTS DELETING A1E, B1E & D1E GABLES PER FRAMER VIA BOB YURK ON 12/30/13. | | | | | | | |
| s [™] 1015 E. Quarles Pl | **** C1E ST | C1E STRUCTURAL GABLE IS NOT DELETED AND WILL STILL BE PROVIDED *** | | | | | | | |
| ັ Fox Point, WI | | | | | | | | | |
| ROO | | RS ARE BEING SHIPPE | | - | ct, AHS was not informed and charge-backs cannot ed. Contact lumber yard to correct on future projects.) | | | | |

÷.

| | | | | | | | | | | | | | | | a mus Aran |
|---------|-------|-------|------|---------------|-----------------------|----------|-------|-------|---------------------------------------|--------------|------|-------|----------|-------|---------------|
| PROFILE | QTY | | СН | TYPE | BASE | O/A | | IBER | | HANG | | LEVER | ST | | |
| | PLY | TOP | BOT | ID ROOF | SPAN | SPAN | TOP | BOT | LEFT | <u>RIGHT</u> | LEFT | RIGHT | LEFT | RIGHT | |
| | 9 | 6.49 | 0.00 | A2 · | 24-08-12 | 24-08-12 | 2 X 4 | 2 X 4 | 01-10-08 | | | | | | |
| | | | | ROOF | | | | | | | | | | • | |
| | 1 | 6.49 | 0.00 | A3 ROOF | 24-08-12 | 24-08-12 | 2 X 4 | 2 X 4 | | <u> </u> | | | | | |
| | 2 Ply | 6.49 | 0.00 | A4G | 24-10-12 | 24-10-12 | 2 X 6 | 2 X | | | | | | | |
| | | | | VALLEY | | | | | | | | | | | |
| | 1 | 6.49 | 0.00 | AV1 VALLEY | 10-00-01 | 10-00-01 | 2 X 8 | 2 X 4 | | 04-08-10 | | | | | |
| | 1 | 6.49 | 0.00 | AV2 | 08-00-01 | 08-00-01 | 2 X 8 | 2 X 4 | | 04-08-10 | | | | - | |
| | | | | VALLEY | | | | | | | | | | | j i |
| | 1 | 6.49 | 0.00 | AV3 VALLEY | 06-00-00 | 06-00-00 | 2 X 4 | 2 X 4 | | | • | | - · · · | | / |
| | i | 6.49 | 0.00 | AV4 | 03-11-15 | 03-11-15 | 2 X 4 | 2 X 4 | | | | | | ' ' | Γ |
| | | | | VALLEY | | | | | | | | | | ÷ | - |
| | 1 | 6.49 | 0.00 | AV5 | 01-11-15 | 01-11-15 | 2 X 4 | 2 X 4 | - | | | | | | · · · · · |
| | 6 | 11.00 | 0.00 | ROOF B2 | 22-02-03 | 22-02-03 | 2 X 4 | 2 X 4 | | | | | | | |
| | | | · | GABLE | | | | | | | | | | | |
| | 1 | 6.50 | 0.00 | C1E | 34-10-09 | 34-10-09 | 2 X 4 | 2 X 4 | 01-10-08 | | | | · · · · | | |
| | 4 | 6.50 | 0.00 | ROOF C2 | 34-10-09 | 34-10-09 | 2 X 4 | 2 X 4 | 01-10-08 | | | | | | |
| | | | | ROOF | 2 | | | | | | - | | | | |
| | 7 | 6.50 | 0.00 | C3 VALLEY | 34-10 _t 09 | 34-06-09 | 2 X 4 | 2 X 4 | | | | | 00-04-00 | | |
| | 1 | 4.81 | 0.00 | CV1 | 17-03-00 | 17-03-00 | 2 X 4 | 2 X 4 | | | | | | | |
| 1 | | | | VALLEY | | | | | | | - | | | | |
| | 1 | 4.81 | 0.00 | CV2 VALLEY | 12-08-02 | 12-08-02 | 2 X 4 | 2 X 4 | · · · · · · · · · · · · · · · · · · · | | | | · · · | | |
| | 1 | 4.81 | 0.00 | CV3 | 08-01-04 | 08-01-04 | 2 X 4 | 2 X 4 | -2 - | | | | | | |
| | | | | COMMON | - | | | -3, | | | | | | | |
| | 3 | 11.00 | 0.00 | D2 | 10-09-12 | 10-09-12 | 2 X 4 | 2 X 4 | | 01-07-08 | | | <u> </u> | | |
| | 9 | 11.00 | 0.00 | COMMON D3 | 10-09-12 | 10-09-12 | 2 X 4 | 2 X 4 | ÷ | | | | | | |
| | 1. | | | COMMON | | | | | | | | | | | |
| | 1 | 11.00 | 0.00 | D4 ROOF | 10-09-12 | 10-09-12 | 2 X 4 | 2X4 | | | | | | | |
| | 5 | 11.00 | 0.00 | D5 | 10-09-12 | 10-09-12 | 2 X 4 | 2 X 4 | | ë | | | | | |
| | | 11.00 | 0.00 | ROOF D6 | 10-09-12 | 10-09-12 | 286 | 2 8 4 | | | | | | | |
| | 1 | 11.00 | 0.00 | D6 | 10-09-12 | 10-09-12 | 2.76 | 2.7.4 | L | | L | I | I | | l |

· ··· .

١.

,

| DELIVERY SHIPLIST | • |
|-------------------|---|
|-------------------|---|



2624 Corporate Circle, East Troy, WI 53120 P: 262-642-3800 F: 262-642-2716 www.accuratehousing.com

| ORDER DATE | 12/02/13 | ORDER # |
|-----------------------|----------|-----------|
| REQUESTED DATE | 01/10/14 | |
| DELIVERY DATE | 01/10/14 | R-5902-13 |
| DELIVERY INFO (ASSUME | | |
| Roll off delivery | | |

DESIGNER: Justin Nagl Ext. 7013

| | Wisconsin Building Supply - | JOB NAME: Stratton Resider | ice | LOT # | SUBDIVISION: | | | | | | | |
|---------|---------------------------------------|---|---|-------|------------------|--|--|--|--|--|--|--|
| SOLD | | MODEL: | ELEVATION: | | RAKE SHEATH MAT: | | | | | | | |
| D FO | | SPECIAL INSTRUCTIONS: NEW PRICE REFLECTS DELETING A1E, B1E & D1E GABLES PER FRAMER VIA BOB YURK ON 12/30/13. | | | | | | | | | | |
| F | · · · · · · · · · · · · · · · · · · · | 4 | | | | | | | | | | |
| SHI | | **** C1E STRUCTURAL GABLE I | **** C1E STRUCTURAL GABLE IS NOT DELETED AND WILL STILL BE PROVIDED *** | | | | | | | | | |
| P | 1015 E. Quarles Pl | | | | | | | | | | | |
| Ō | Fox Point, WI | | | | | | | | | | | |

ROOF GIRDERS ARE BEING SHIPPED PRE-NAILED? YES (if incorrect, AHS was not informed and charge-backs cannor be accepted. Contact lumber yard to correct on future projects.)

(if incorrect, AHS was not informed and charge-backs cannot

| PROFI | LE | QTY | PIT | CH | TYPE | BAS | E O/A | LUM | BER | OVER | HANG | CANT | ILEVER | ST | UB | |
|-------------------------|---|------------|--------|------|-------------------|----------|--------------------|-------|-----------|------|--------|---|------------------------------|------|------------|---|
| | | PLY | ТОР | BOT | ID | SPA | N SPAN | TOP | BOT | LEFT | RIGHT | LEFT | RIGHT | LEFT | RIGHT | |
| | | 1 | | 0.00 | FLAT GIRDER | 08.00 | 00 00 00 00 | 2 2 8 | | | | | | | | |
| 4 Ply 0.00 0.00 EG 26-0 | | | | | | , . | | | | | | - | | | | |
| EG NOTE | EG NOTES: INSTALL SCREWS IN GIRDERS AT PLANTI 2 ROWS @ 2' O.C. TOP CHORD & BOTTOM CHORD. MARK UP! | | | | | | | | | | | | | | | |
| - | e e e e e e | 1 3 Ply | 0.00 | 0.00 | FLAT GIRDER FG | 39-00- | 00 | 2 X 8 | 2 X | | | | | | | |
| FG NOTE | FG NOTES: MARK UP! | | | | | | | | | | | | | | | |
| ITEM | ITEMS | | | | | | | | | | | | | | | |
| QTY | Ī | TEM | TYPE | | SIZE | | LENGTF FT-IN-16 | 1 | | PART | IUMBER | | NOTES | | | |
| 60 | SIMF | PSON I | HANGEI | RS * | INSTALLED* SD | 5 .25" X | 6" scre | | | | | | NOT Ship L alled in truss | | ws already | |
| 55 | SIMF | SON F | HANGE | RS F | 12.5T | 1 | | Ι | SHEET U-1 | | | Standard double-plate hurricane clips included. | | | | |
| [`] 10 | SIMF | SON | HANGE | RS ⊦ | ITS30C | ļ | - | T | | | | | | | | |
| 6 | SIMP | SON | HANGE | RS F | IUS28 | 1 | | | | SHE | ET R-1 | | | | | |
| 19 | SIMF | SON | HANGE | RS L | US24 | 1 | | | <u> </u> | SHE | ET R-1 | | | | | |
| 16 | SIMF | SON | ANGE | RS L | US28 | | | | | SHE | ET R-1 | | | | | L |

Total No. of Components

Total Package Weight

64

7862

TRUSS LABEL CLARIFICATION:

FORMAT: JOB #-BATCH#* TRUSS ID WEB/CHORD NUMBER (*Batch number may be found on included "BATCH LAYOUT", if included)

3/1

26-3


EX. 1: R123412-2 C4 W3 = (ROOF JOB #1234-12 - BATCH 2 TRUSS C4 WEB 3) EX. 2: F001012-8 F3 T2 = (FLOOR JOB #0010-12 - BATCH 8 TRUSS F3 TOP CHORD 2)


1-39-0718


SHIPMENT VERIFIED BY:


OFFICE: YARD: DRIVER:


DATE 01/09/14 PAGE 2



















































. د





.













6.

MiTek USA, Inc.

14515 North Outer Forty Drive Suite 300 Chesterfield, MO 63017-5746 314-434-1200

Re: r-5902-13 Stratton Residence


The truss drawing(s) referenced below have been prepared by MiTek USA, Inc. under my direct supervision based on the parameters provided by Accurate Housing Systems, Inc..

Pages or sheets covered by this seal: I21692323 thru I21692323

My license renewal date for the state of Wisconsin is July 31, 2014.

Wisconsin COA: 726-011

Lumber design values are in accordance with ANSI/TPI 1 section 6.3 These truss designs rely on lumber values established by others.




January 14,2014

Fox, Steve


The seal on these drawings indicate acceptance of professional engineering responsibility solely for the truss components shown. The suitability and use of this component for any particular building is the responsibility of the building designer, per ANSI/TPI 1.

Ŷ




ATTACH 1/2" PLYWOOD OR OSB GUSSET (15/32" APA RATED SHEATHING 32/16 EXP 1) TO EACH FACE OF TRUSS WITH 10d (3" X .131") NAILS DRIVEN THROUGH BOTH SHEETS OF PLYWOOD AND CLINCHED PER THE FOLLOWING NAIL SCHEDULE: 2 x 4's - 2 ROWS: SPACED @ 0-4-0 O.C. NAILS TO BE DRIVEN FROM BOTH FACES. STAGGER SPACING FROM FRONT TO BACK FACE FOR A NET 0-2-0 O.C. SPACING IN THE MAIN MEMBER. USE A MIN. 0-3-0 MEMBER END DISTANCE.

| | | 8-7-8 8-7-8 | <u> </u> | | <u>24-8-12</u> 7-9-4 | | · . |
|---|--|-------------------------------------|---|--|--|--|---------------------------------------|
| Plate Offsets (X,Y): [6 | 6:0-3-9,0-2-0] | | | | | | · · · · · · · · · · · · · · · · · · · |
| LOADING (psf) TCLL 30.0 TCDL 10.0 BCLL 0.0 * BCDL 10.0 | SPACING 2-0-1 Plates Increase 1.11 Lumber Increase 1.11 Rep Stress Incr YES Code IRC2006/TPI2002 | 5 TC 0.84 5 BC 0.80 5 WB 0.33 | Vert(LL) -0.27 Vert(TL) -0.41 Horz(TL) 0.05 | 9-11 8 | V/defi L/d >999 360 >715 180 n/a n/a >999 240 | PLATES MT20 Weight: 110 lb | GRIP 197/144 FT = 10% |
| | | | BRACING TOP CHORD BOT CHORD WEBS | Rigid ce 1 Row a MiTek be ins | eiling directly applied at midpt 5 recommends that S | s, except end vertica or 10-0-0 oc bracing -9 tabilizers and require ection, in accordance | d cross bracing |
| Max Ho |) 2=1449/0-5-8 (min. 0-2-4), prz 2=267(LC 5) plift2=-75(LC 6), 8=-7(LC 7) | 8=1288/Mechanical | | | | | |
| Max Uplift2=-75(LC 6), 8=-7(LC 7) FORCES (ib) - Max. Comp./Max. Ten All forces 250 (ib) or less except when shown. TOP CHORD 2-3=-2057/66, 3-5=-1782/83, 5-6=-987/134, 6-7=-1259/98, 7-8=-1231/70 BOT CHORD 2-11=-148/1711, 9-11=-38/1214 WEBS 3-11=-379/108, 5-11=0/574, 5-9=-777/73, 6-9=0/690, 7-9=-9/698 NOTES 1) Unbalanced roof live loads have been considered for this design. 2) Wind: ASCE 7-05; 90mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; enclosed; MWFRS (low-rise) gable end zone and C-C Exterior(2) -1-10-8 to 1-1-8, Interior(1) 1-1-8 to 13-11-6, Exterior(2) 13-11-8 to 16-11-6, Interior(1) 19-11-8 to 21-7-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 3) Plates checked for a plus or minus 5 degree rotation about its center. 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads. 5) * This truss has been designed for a 10.0 psf bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf. 6) Refer to girder(s) for truss to truss connections. 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 bupift at joint(s) 2, 8. 8) "Semi-rigid plichbreaks including heels" Member end fixity model was used in the analysis and design of this truss. LOAD CASE(S). Standard | | | | | | | |
| VIARVITMS -Verify design have: "A use that READ VIOLES ON THIS AND INCLUDED MITER REFERENCE PAGE MIT-7473 rev. 02/26/2013 BEFORE USE Design valid for use only with Mile connectors. This design is based only upon parameters shown, and is for an individual building component. Applicability of design parameters and proper incorporation of component is responsibility of building designer - not truss designer. Bracing shown is for lateral support of individual web members only. Additional temporary bracing to insure stability during construction is the responsibility of the erector. Additional permanent braccing of the overall structure is the responsibility of the building designer. For general guildance regarding tabrication. guality control. storage, delivery, erection and braccing. consult ANSI/TPH Quality Criteria, DSB-89 and BCSI Building Component Safety Information on Tuss Pick to hiltible 78 IN. Lee Street. Suite 312, Alexandric, VA 22314, If Southern Pine (SP) Jumbers and Tisch Charles and Extreme 06/01/2013 by ALSC | | | | | | | |
| | · . | | | | | | |



Numbering System



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS ICC-ES Reports:

ESR-1311, ESR-1352, ESR1988 ER-3907, ESR-2362, ESR-1397, ESR-3282

Southern Pine lumber designations are as follows:

SYP represents values as published by AWC in the 2005/2012 NDS SP represents ALSC approved/new values with effective date of June 1, 2013

© 2012 MiTek® All Rights Reserved




MiTek Engineering Reference Sheet: Mll-7473 rev. 02/26/2013


General Safety Notes


Failure to Follow Could Cause Property Damage or Personal Injury


- Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
- Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
- 3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
- Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
- 5. Cut members to bear tightly against each other.
- Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TPI 1.
- Design assumes trusses will be suitably protected from the environment in accord with ANSI/TPI 1.
- 8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
- Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
- 10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
- 11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
- Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
- 13. Top chords must be sheathed or purlins provided at spacing indicated on design.
- Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is Installed, unless otherwise noted.
- 15. Connections not shown are the responsibility of others.
- 16. Do not cut or alter truss member or plate without prior approval of an engineer.
- 17. Install and load vertically unless indicated otherwise.
- Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
- Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
- 20. Design assumes manufacture in accordance with ANSI/TPL1 Quality Criteria,


5




















| BCDL 10.0 | Code IRC2006/TPI2002 | (Matrix) | | Weight: 5 lb FT = 10% |
|----------------------------|----------------------|---------------------------------------|-----------------------------------|--|
| REACTIONS (Ib/siz Max H | | · · · · · · · · · · · · · · · · · · · | BRACING TOP CHORD BOT CHORD | Sheathed or 2-0-6 oc purlins, except end verticals. Rigid ceiling directly applied or 10-0-0 oc bracing. MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide. |
| | | | | |

FORCES (Ib) - Max. Comp./Max. Ten. - All forces 250 (Ib) or less except when shown,

NOTES


1) Wind: ASCE 7-05; 90mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; enclosed; MWFRS (low-rise) gable end zone and C-C Exterior(2) zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60 2) Plates checked for a plus or minus 5 degree rotation about its center.


Gable requires continuous bottom chord bearing.


4) This truss has been designed for a loup st bottom chord live load nonconcurrent with any other live loads.
 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.


6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplit at joint(s) 1, 3.
 7) This truss is designed in accordance with the 2006 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 8) "Semi-rigid pitchbreaks including heels" Member end fixity model was used in the analysis and design of this truss.


LOAD CASE(S) Standard



































| #94.00 Receipt # 48419 MILWAUKEE OF FOX POIN MILWAUKEE COUNTY, WISCONSIN | г _{No. 7999} |
|--|---|
| APPLICATION AND RECORD FOI TO THE BUILDING INSPECTION DEPARTMENT: | R HEATING PERMIT |
| The undersigned hereby applies for a permit to install, in accordar | ce with the information tabulated hereafter |
| Winter Air Conditioner D Type | ant, Baseboard, Etc. |
| | |
| Gas Oil Coal Elect. Other | |
| Gas Oil Coal Elect. Other Desc. of Heating Plant Bryout | 100,000 BTU |
| Vented to Outside | |
| Fuel Tank | Location |
| Summer Air Conditioner \Box Size 540 | (Ton, H.P.) |
| Coolant_ R410 a refrigerant. | |
| Compressor Coolant: Air ⊅; Water □; | |
| If Water Cooled: | |
| If Water Cooled: Source of Water Discharged to Location of unit on premises including distances to lot lines requ | |
| If Water Cooled: ' Source of Water Discharged to | |
| If Water Cooled: | ired for approval of exterior apparatus. |
| If Water Cooled: 'Source of Water Discharged to Location of unit on premises including distances to lot lines requ | ired for approval of exterior apparatus. |
| If Water Cooled: | ired for approval of exterior apparatusBushel |
| If Water Cooled: | ired for approval of exterior apparatusBushel |
| If Water Cooled: Source of Water | ired for approval of exterior apparatusBushel ontrol? |
| If Water Cooled: Source of Water | ired for approval of exterior apparatusBushel ontrol? |
| If Water Cooled: Source of Water | ired for approval of exterior apparatusBushel ontrol? |

ŝ



VILLAGE OF FOX POINT

MILWAUKEE COUNTY WISCONSIN

VILLAGE HALL 7200 N. SANTA MONICA BLVD. FOX POINT 53217-3505 414-351-8900 ~~ FAX 414-351-8909

January 1, 2012

Dear Heating Contractor:

I am writing to inform you that on January 1, 2012 the permit fee schedule will be as follows:

Heating

\$35.00/unit up to and including 150,000 input BTU units. Additional fee of \$12.00 each 50,000 BTU or fraction thereof.

\$2.00/100 square foot of conditioned air

Heating & Air Conditioning Distribution Systems

75724= 59

Air Conditioning

\$35.00/unit up to 3 tons or 36,000 BTUs. Additional fee of \$12.00 each ton or 12,000 BTUs or fraction thereof.

Minimum fee of all \$60.00 permits

If you have any questions please feel free to contact me.

Sincerely,

Scott Miller Inspector

| Credent Dsp s | ial/License Searc Wisconsi Services | ty and Pr | ofessional | | |
|------------------|---|--|------------------------|----------------------|--------------|
| Cred | ential/Licens | ing Search | | | |
| <u>Creder</u> | <u>itial/License Sea</u> | <u>arch</u> | | | |
| DSPS | | | le ve e | | |
| | ntial/License Se | earch DSPS I | Home | | |
| | de Search Re | | | | |
| Crec ID | lential/License | Name | City,State,Zip | Professio | n Expiration |
| 6626 | 579 | <u>LAKE</u> <u>COUNTRY</u> <u>HEATING &</u> <u>COOLING</u> <u>INC,</u> | OCONOMOWO WI 53066 | C HVAC Contractor | . 6/30/2017 |
| <u>Retu</u> | rn to Search | | | | |
| | | · | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | QA standards for prima | · | |

Consistent with The Joint Commission and NCQA standards for primary source verification. Data on this page is refreshed hourly.

https://app.wi.gov/LicenseSearch/Trade/SearchResults

10/7/2014

| IRIOIS. | | | | | | | | |
|--|--------------|---------------------------------------|------------|-------------------------------|--|----------------|--|-----------------|
| Plumber Clo | ne PI | umbing | | No\ | 3250 | Owner | Wned Cm | struction |
| Plumber (1) Address 1458 | DW. GNO | unfield av | 2 | | | _ Addres | 5 4526 N.C | at land |
| City, State, Zip B | nootfie | 12 WI530051 | Appli | catio | on and Record | White. Date | 55 4526 N.C fish Bay y- 24 | 2014 |
| Tel. No. <u>2 62-</u> | | | | Villag 200 N. Sa Fox Po | e of Fox Point anta Monica Blvd. bint, WI 53217 4) 351-8900 | | | |
| TO THE VILLACE | OF FOY P | | | • | NSPECTION DEPARTMEN | | | |
| The undersigned he | | | | | | | PERMITS I | JSED |
| laying a | | | | | inch | Kind | 1 | No. |
| builder sewer from | | | | | Main to Lot line | | er and Plumbing _ | |
| to Building | | | to Buildi | ng | | | er | |
| | | at | | | | | et | |
| 1015 E G | Jucal | Dar D. | | | Fox Point, WI | Met | er | |
| | Address at | which work is to | | | Fox Point, WI | Wate | er Usage | _ |
| | | | | | | | | |
| | Sub | division | | | Lot | | B | lock |
| and regulations pres | scribed by t | he Village Board | l for Plum | bers. | rees to bounden by and subr Building Contractor Reg# | | - | |
| | | | - | | | _ | | - |
| HVAC Contractor F | Reg# | | _Expir | | Signature Qui | 12 | lle | Applica |
| FIXTURE WIT | 'H DRAIN | OR WATER C | ONNECT | TIONS | | FE | ES | |
| - | No. | | N | No. | Water Usage | | \$ | |
| Hose Bibs | 3 | Dishwashers | · | 1 | Building Sewer | | | |
| Bath Tubs | 1 | _ Wash Basins | . | B | Water Service | | | |
| Sump Pumps | | _ Water Closer | ts | 7 3 | Building Drain | | | 50.00 |
| Laundry Trays | | _ Showers | | 3 | Fixtures | <u> </u> | 30 | 240.00 |
| Drinking Fountains | | _ Floor Drains | | _(| Water Meter | ~ | <u></u> | |
| Sinks | 0 | Food Waste | | <u>['</u> | Total | <u>\</u> | | 290.00 |
| Water Heaters | | _ Sprinkling S | | | Deposit to cover street | | | |
| Wash. Mach. Wastes Bidets Catch Basins | | _ | | | (A current certificate of in | • | e must be provided t of way (ROW)). | when doing worl |
| | | | | | | | | Permit Cler |
| | | | | | | | | |
| A | inch | | water se | rvice pipe | es laid in | / | | |
| Curb box is located | | feet | of | f | | fee | t | _of |
| | inch | | Water Met | | | | | |
| ۸ | inch | · · · · · · · · · · · · · · · · · · · | sonitory | sewer co | nnection was made in | | | |
| A | | | • | | | | | |
| | • | | ····· | | | | <u> </u> | |
| A | <u> </u> | <u> </u> | storm s | ewer coni | ection was made in | | | |
| | feet | | of manh | ole | | | | |
| Building Sewer | Report | Building Drain | Report | Rou | gh In Plumbing Inspection | Report | Final Inspection | Report |
| · | | | | | | | | |
| | | | | | | | | |
| Installation Approv | ed | | | Ar | plication Approved | | | , 20 |
| | | | | | | | | |
| As Built | | | | | | | ·· | |

_

Wisconsin Department of Safety and Professional Services: Homepage

Search for Individual or Company by Credential ID here:

1

Specific Credential ID 220705

4

Search

1 record(s) were returned by your search.

| ID | Name | City,State,Zip | Credential Type | Expiration |
|--------|--------------------------------|--------------------------------------|--------------------|------------|
| 220705 | <u>HOLLE.</u> CHRISTOPHER F | MENOMONEE FALLS WI 53051- 6327 | Master Plumber | 03/31/15 |

| Receipt No: 1.04682 | May 08, 2014 | |
|-------------------------------------|----------------|------------------|
| | 1015 E QUARLES | |
| LICENSES & PERM 24-44470 PLUMBIN | 290.00 | |
| Total: | | 290.00 |
| CHECK Total Applied: | Chk No: 027651 | 290.00 290.00 |
| Change Tendered: | | .00 |
| | 05/00/44 44:40 | |


05/08/14 11:46am

VILLAGE OF FOX POINT 7200 N. SANTA MONICA BLVD FOX POINT, WI 53217

414-351-8900

| Date CONTRACTOR USE | VILLAGE OF FOX POINT 7200 N. Santa Monica Blvd. Fox Point 53217 414-351-8900 APPLICATION FOR ELECTRICAL PERMIT PLEASE TYPE OR PRINT WITH BALL POINT PEN | | | | | | |
|--|--|--|-----------------|------------|---|--------------|--------------|
| State Master Electrician Lic. No. 170072 State Elect. Contractor Cert. No. 1098009 Village Elect. Contractor Cert. No. | | | | | Received 5/5/14 Service 9114 Rough-In Final | | |
| Builder Wired Construction | Ow | | 0 | ccupant | _ | | |
| Job Address 1015 E Quarles Pl | acc | | | | | | 1 |
| - UNU - | No. | Description | | Qty. | Rate of Fees | Dollars | Cents |
| ESTIMATED COST OF JOB \$15,000 - | 1 | Light, switch, and convenience outlets | | 100 | .70 ea | 70 | 00 |
| Buildings X Residential | 2 | Lighting Fixtures | | 45 | .70 ea | 31 | 50 |
| | 3 | Fluorescent Fixtures - per tube | | | .70 ea | | |
| □ Industrial - □ Institutional _ | 4 | Range, Electric | | 1 | 8.00 ea | 90 | 00 |
| New Construction | 5 | Garbage Grinding and Disposal Unit | | 1 | 8.00 ea | ຍ | |
| Additional Rooms | 6 | Dishwasher | | Ì | 8.00 ea | g | 00 |
| □ Remodeling | 7 | Clothes Dryer | | Î | 8.00 ea | | ΰC |
| □ New Occupancy - | | Water Heaters, Electric | | | 8.00 ea | | |
| | 9 | Gas Burner, Oil Burner, or Stoker | | | 8.00 ea | | |
| Where on Premises? | 10 | Refrigerating, Air Cooling, or similar machine25 per | Цр | | 8.00 min | <u></u> | 00 |
| Describe | | | 111 | ` | | | 00 |
| <u> </u> | 11 | Feeders - No. 6 A.W.G. or Larger | | | 10.00 ea | | |
| | 12 | Temporary Service Permit for: How Long | ? | | 30.00 ea | | - (|
| List Name of Installing Contractor | 13 | Services: Service Switches, ea. | | 1 | 5.00 ea | 5 | 00 |
| HEATING | | Service 1. 0 through 100 amps. | | | 25.00 ea | | |
| AIR CONDITIONING | | 2. 101 through 400 amps. | | 1 | 40.00 ea | -40 | .C) () |
| PLUMBING | | 3. 401 through 600 amps. | | | 40.00 ea | | |
| | | 4. 601 through 1000 amps. | | | 60.00 ea | | |
| Date of Inspection | | 5. Thereafter, ea. additional 1000 amps. | | | 5.00 ea | | |
| RoughWill Call | 14 | Motors over 1/4 HP | | | .70 per HP or frac. | | |
| Final Will Call | 15 | Fuel Dispensing Pumps | | | 6.00 ea | | |
| Service Approval Sent □ | 16 | Transformers, Rectifiers, and Generators | | | 2.00 per KW | | |
| | 17 | | | | 4.00 ea | | |
| Theled - | | Power receptacles - 120 Volts or over 1.Through 30 a | mne | | 3.00 ea | | |
| REMARKS: 7/25 4 | 10 | 19 2.0ver 30 amps. | | | 5.00 ea | | |
| REMARKS: 1/25/14 DETMOTE Both Gran Kerps E) (Anste Grante to Fill-Linne on Penahl | 19 | · · · · · · · · · · · · · · · · · · · | | | | | |
| Brasic Both Loon - | 20 | Wireways, busways, underfloor raceways, or auxiliary | - | <u> </u> | 50 per ft. | | |
| | 21 | Strip Lighting, Plug-in Strip, Trol-E Duct, or similar syst | - | | .50 per ft. | | |
| Kerps . | 22 | Signs, Electric75 ea. socket, plus 2.00 ea. add'tl tran | stormer | + | 8.00 min | | |
| | 23 | Swimming Pool Wiring: A. Inground pools | | | 40.00 | | |
| 2) (AISE CTIATE TO | 24 | B. Above ground pools | | _ | 40.00 | | <u> </u> |
| Fil- lines on Venahl | 25 | Spas, Hot-Tubs, Hydromassage Bathtubs | | _ | 6.00 | ļ | |
| ('((⁻ L ² · · | 26 | MINIMUM CHARGE FOR ANY ONE PERMIT | | _ _ | 60.00 | | |
| - | 27 | FAILURE TO CALL FOR FINAL INSPECTION | | | 15.00 | | |
| | 28 | DOUBLE FEES will be charged for any work starte obtaining permit. | d before | Ric | est # | 46 | 75 |
| | plicabl | nit for the execution of electrical installation for lig e State and Local Codes and Ordinances regulat < Point. | | | TOTAL FEES MAKE CHEC Treasurer, Vi MAIL TO: El | KS PAYAE | x Point |
| 1 / 1 | | | | | > | Date 1 | li In |
| Contractor M L El La La L | | Supervising Electrician (Sig | includin Caller | | | | |
| Contractor Current Electric Co Address 12625 W Burleigh | <u>_</u> | Supervising Electrician (Sig Sad Telephone 767 78 | Ð | 5 | 262 88 | <u> </u> | <u> 4 2</u> |

| This Permit is void if work is not started within 2 months, or if started, no work is done for 2 months. | |
|--|--|
|--|--|



1015 E QUARLES PLACE ,

May 05, 2014

| LICENSES & PERM 24-44430 ELECTRIC | 186.50 | |
|--------------------------------------|---------------|------------------|
| Total: | | 186.50 |
| CHECK Total Applied: | Chk No: 47737 | 186.50 186.50 |
| Change Tendered: | | .00 |

05/05/14 09:21am

VILLAGE OF FOX POINT 7200 N. SANTA MONICA BLVD FOX POINT, WI 53217

-

VILLAGE OF FOX POINT 7200 N. Santa Monica Blvd. Fox Point, WI 53217 Phone 414-351-8900 Fax 414-351-8909



s'

ĩ


| То: | WE ENERGIES-CENTR | ALIZED GROUP | From: | Scott Miller |
|----------|-------------------|--------------|--|-------------------------------|
| Fax: | 262-574-6401 | | Pages: | 2 |
| Phone: | | | Date: | |
| Re: | | | CC: | |
| 🗆 Urgent | t X For Review | | mment 🗆 | Please Reply 🗆 Please Recycle |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | · · · · · · · |
| | | | | |
| | | | | |
| · | | | | |
| | | | | |
| | | | <u>. </u> | |
| | ··· · · · · · · | | | |
| <u> </u> | | | | <u> </u> |
| | | | | |
| | | | | |
| | | | | |

ELECTRICAL INSPECTION APPROVED


| FAX TO (262)574-6401 | PHONE (866)423-0364 | | | | |
|--|-----------------------------------|--|--|--|--|
| COUNTY Milwavilce C T W MUNICIPALIT | y For Part INSPECTION NUMBER | | | | |
| INSPECTOR Suft Miller | | | | | |
| CUSTOMER NAME FREDERICK Stra | -How PHONE | | | | |
| ADDRESS 1015 E QUARTIES FLACE | SUBDIVISION NAMELOT | | | | |
| ELECTRICAL CONTRACTOR Current Elect | | | | | |
| NEW SERVICE | REWIRED SERVICE | | | | |
| OVERHEAD | OVERHEAD TO UNDERGROUD | | | | |
| UNDERGROUND | OVERHEAD TO OVERHEAD | | | | |
| / | UNDERGROUND TO UNDERGROUND \Box | | | | |
| PERMANENT SERVICE \Box | 4 | | | | |
| SIZE (AMPS) 200 (NUMBE | R OF METERS: CHANGE FROM TO) | | | | |
| 1 PHASE | | | | | |
| 3 PHASE | | | | | |
| VOLTAGE 10/240 OVERHEAD RESIDEN | TIAL REWIRE INFORMATION YES NO | | | | |
| TEMPORARY SERVICE D PERMANENT CON | NECTIONS HAVE BEEN MADE | | | | |
| SIZE AMPS PERMANENT CON | NECTIONS REQUIRED | | | | |
| 1 PHASE SERVICE DROP REL | LOCATION OR REPLACEMENT | | | | |
| 3 PHASE | | | | | |
| VOLTAGE | | | | | |
| RESIDENTIAL / FARM C | ommercial | | | | |
| INSTALL ONLY D NU | JMBERS OF METERS | | | | |

| | WAUSAL | . | | | | | | | | | |
|---|--|--|------------------------------|------------------------|-------------------|-------------------------|----------------|-----------------|--|-----------|----------------------------------|
| Project Name | Butier Chase stra | atton Job#: Str | atton | G | Quantity 1 (2p | cs.) | Description | | | | |
| G2-A | 2.0E WS-LA | AM LVL 1.7 | 750" X 11. | .875" | 2-Ply - | PASSED | | | 10/16/2014 Page 1 of 2 Designer: | | |
| 1 SPF | | | | ELVL | 2'4 1/8" | | Witami Vi | | 2 SPF | | |
| | | r- | | | | - | - | | | | |
| Type: Plies: | Girder 2 | Applica Design | tion: Floo Method: ASE | | | Reactions | | | | | |
| Moisture Cond | | Building | | , 2012 / IRC | ; | Brg Liv 1 410 | | Dead \$ 1372 | Snow 0 | Wind 0 | Const 0 |
| Deflection LL: | | Load Si | - | | | 2 21: | | 786 | 0 | 0 | 0 |
| Deflection TL: mportance: | 240 Normal | Deck: Vibratio | | " OSB Naile Checked | ed and Glued | | - | | - | - | - |
| Temperature: | Temp <= 100°F | | 1101 | SHOUNGU | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | Bearings | | | | | |
| Nach - 1- | | | | 1 | | Bearing Input Length | In Analysis | Cap. React | D/L lb To | tal Ld.C | ase Ld. Comb |
| Analysis Moment | Actual 12323 ft-lb | Location Allowed 7'5 3/4" 21295 ft-lb | Capacity 0.579 (58%) | | mb. Ld. Case | 1 - SPF 14.563" | | | / 4166 55 | 38 L | D+L |
| Shear | 3184 lb | 2' 9/16" 7897 lb | 0.403 (40%) | | L | 2 - SPF 5.500" | 2.000" | 98% 786 | / 2128 29 | 14 L | D+L |
| LL Defl inch | 0.168 (L/781) | 6'6 5/16" 0.364 (L/3 | 50) 0.460 (46%) | L | L | | | | | | |
| L Defl inch Design (Design 1 1 Girders a | Notes | 6'6 7/16" 0.546 (L/2 | 40) 0.420 (42%) dae only. | D+L | L | | | | | | |
| 2 Multiple p | | together as per manui | acturer's details. | | | | _ | | | | |
| ID 4 | Load Type | Location | Trib Width | Side | Dead | Live | Snow | Wind | Const. | Comme | ents |
| 1 2 | Tie-In Tie-In | 0-0-0 to 1-4-9 | (Span)0-1-12 (Span)0-1-12 | | 12 PSF | 40 PSF | 0 PSF | 0 PSF | 0 PSF | | |
| 2 3 | Part. Uniform | 0-0-0 to 1-4-9 0-0-0 to 6-0-9 | (Span)0-1-12 | Far Face | 12 PSF 112 PLF | 40 PSF 373 PLF | 0 PSF 0 PLF | 0 PSF 0 PLF | 0 PSF 0 PLF | | |
| 3 4 | Part. Uniform | 0-0-0 to 2-0-9 | | Near Face | | 502 PLF | 0 PLF | | 0 PLF 0 PLF | | |
| 5 | Tie-In | 1-4-9 to 2-8-9 | (Span)0-1-12 | | 12 PSF | 40 PSF | 0 PSF | 0 PSF | 0 PSF | | |
| 5 | Tie-In | 1-4-9 to 12-4-2 | (Span)0-1-12 | • | 12 PSF | 40 PSF | 0 PSF | 0 PSF | 0 PSF | | |
| 7 | Tie-In | 2-8-9 to 4-0-9 | (Span)0-1-12 | Тор | 12 PSF | 40 PSF | 0 PSF | 0 PSF | 0 PSF | | |
| В | Point | 2-8-9 | | Near Face | e 68 lb | 227 lb | 0 lb | 0 lb | 0 lb | J5 | |
| 9 | Tie-In | 4-0-9 to 5-4-9 | (Span)0-1-12 | Тор | 12 PSF | 40 PSF | 0 PSF | 0 PSF | 0 PSF | | |
| 10 | Tie-In | 5-4-9 to 7-9-4 | (Span)0-1-12 | | 12 PSF | 40 PSF | 0 PSF | 0 PSF | 0 PSF | | |
| 11 | Point | 6-8-9 | | Far Face | 107 lb | 355 lb | 0 lb | 0 lb | 0 lb | | |
| 12 Continued on | Point page 2 | 7-5-12 | | Far Face | 808 lb | 2194 lb | 0 ib | 0 lb | 0 lb | G7 | |
| | | | | | | - | | | <u> </u> | Aliac'- | Duildin - Orrest |
| Notes Calculated Structu | Notes consiste chemicals 6. For flat roofs provide proper drainage to prevent Calculated Structured Designs is responsible only of Handling & Installation ponding | | | | | | | | | W232 N 5 | Building Supply 700 HWY 74, W |
| Calculated structure besigns is responsible only of training of instantiation the structure adequay of this component based on 1. LVU beams must not be cut of dilled the design and leadings shown. It is the 2. Refer to manufacturer's product information responsibility of the customer and/or the contractor to regarding installation requirements, multi-ply | | | | | | | | JS 53089 | | | |
| responsibility of the | | | | | | | | | | | |
| responsibility of the ensure the comp | verify the dimensions and loads. | | strength values, and coo | ie | | | | | | | Lu Ann Price W232 N 5766 H |

| : | WAUSAU | | · <u>··</u> · | Client Butler ch | ase | | ŝ | Shipping | |
|---|--|--|--|---------------------------------------|------------------|---------------|---------------|--|---|
| | Project Name: Butler Chase strati | on Job#: Stra | atton | Quantity 1 (2pcs | | Description: | | | |
| | G2-A 2.0E WS-LA | | '50'' X 11.875' | | | second Floor | 1 | 10/16/2014 1:45 PM Page 2 of 2 Designer: | |
| | | | | 12'4 1/8" | | | | 2 SPF | 11 7/8" |
| | ł | | 12'2 | 124 1/8 | | | | ł | 3 1/2 |
| | - | | | | | | | | |
| | Continued from page 1 ID Load Type 13 Tie-In Self Weight | Location 7-9-4 to 12-4-2 | Trib Width Side (Span)1-11-8 Top | Dead 12 PSF 11 PLF | Live 40 PSF | Snow 0 PSF | Wind 0 PSF | Const. Comm 0 PSF | ents |
| | | | | | | | | | |
| | | | | | | | | | |
| | Notes Calculated Structured Designs is responsible only of | corrosive chemicals Handling & Installati | | flat roofs provide proper dra ding | inage to prevent | | | W232 N 5 | Building Supply |
| | the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads. Lumber 1. Dry service conditions, unless noted cherwise 2. LVL not to be treated with fire retardant or | LVL beams must not be c Refer to manufacture regarding installation fastening details, beams approvals Damaged Beams must n Design assumes top edge | ut or dnilled fs product information requirements, multi-ply strength values, and code of be used is laterally restrained it bearing points to avoid | | | | | | La Ann Price W221N 1996 MW774 SURSIN 328-346-441 SUPPLY CONTOCOL |



CALCULATED STRUCTURED DESIGNS



| Address P. O. Bo | x 190 | | | 110 | n and Reco | UV A d | Wired 2022 E. N | orth Ave | SU 300 MKE WE |
|--------------------|-----------------------------|--------------------|-------------|--|--|---------------|--------------------|--------------|------------------|
| Lity, State2921662 | <u>ig Bena</u> rw 2-3263 | 1 53103 | Appli | icatio | n and Reco | | ite | ber, 14in | 13 |
| el. No | | | | Village | of Fox Point | Da | <u>.</u> | | , 20 |
| | <u> </u> | | 7: | | nta Monica Blvd. | | | | |
| | | | | Fox Po | int, WI 53217 | | | | |
| | | | | (414) |) 351-8900 | | | | |
| O THE VILLAGE | 3 OF FOX | POINT, PLUMI | BING AND | WATER IN | SPECTION DEPART | MENT F | | <u> </u> | |
| he undersigned he | ereby mak | e application to e | lo the work | of plumbi | ng consisting of | - | | MITS U | |
| ying a | ir | nch | laying a | | inch | | Kind | | No. |
| ilder sewer from | Main to L | | | | Main to Lot line | 1 | | - | 12851 |
| Building | | | to Buildi | | | | Water | | |
| | • | | ARISE | | TERAL AT LOT | | | | |
| 1015 E. Quar | les Pla | се | | | Fox Point, WI | | Meter | | |
| | Address a | at which work is | | | | L | Water Usage | | |
| | Su | bdivision | | | Lot | | | | lock |
| | | | - | ······································ | | | | | |
| d regulations pre- | scribed by | the Village Boar | rd for Plum | bers. | ees to bounden by and s | | | age ordir | nances and rules |
| ate Master Lic.# | 227764 | 1 | _Expir3/ | 31/14 | Building Contractor Re | eg# | <u>N/A</u> | £ | Expir |
| AC Contractor F | ?ea# | | Evoir | | Signature | Maria | yle - | | |
| | | | | | | | FEES | - <u> </u> | Applican |
| FIXTURE WIT | | | | | 11/ | | - | _ | |
| ose Bibs | No. | Dishwasher | N | ĺ ù. | Water Usage Building Sewer <u>C</u> | | | .\$ | \$60.00 |
| ath Tubs | | Wash Basin | s | | Water Service | | ····· | - · <u></u> | φ00.00 |
| Imp Pumps | | Water Close | ;ts | | Water Service | <u> </u> | | · | |
| aundry Trays | | Showers | | | Building Drain Fixtures | | | · | |
| rinking Pountains | | Floor Drain | s | <u> </u> | Water Meter | | • | , <u> </u> | |
| nks | | | Grinders | | Total | \sim | <u> </u> | | \$60.00 |
| ater Heaters | | Sprinkling S | | | Deposit to cover she | cet repairs | Ker | rist | #453 |
| ash. Mach. Wastes | | Urinals | | | (A current certificat | | | | ben doing work |
| dets | | - | | · · · · · · · · · · · · · · · · · · · | · · · · · · · · · · · · · · · · · · · | Xn road r | ight of way (RO | W)). | |
| tch Basins | | | | | | \rightarrow | | | ermit Clerk |
| | | | | | | | | | |
| ~ | inch | | water ser | vice pipes | laid in | | | | |
| rb box is located | | feet | of | | | | feet | 0 | f |
| | | | | | | | | | |
| | | | | | ··· ·· ·· ·· ·· ·· | ······ | | | |
| | inen | | | I INO | | Dat | e installed | | · |
| | inch | | sanitary e | ewer conn | ection was made in | | | | |
| | | | | | | | | | |
| | | | | 10, | | ~ | | | |
| 1 | inch | | storm sea | yer connec | tion was made in | | | | |
| | | 1 | | | | | | | |
| | reet | | | | | | | | |
| Building Sewer | Report | Building Drain | Report | Rough | In Plumbing Inspection | Report | t Final Inspe | ction | Report |
| | | 251.04504 | 1 | | | · | 10/23 | | QE) |
| 1 | 1 | | | | | | | <u>~ / [</u> | XQ |
| | ÷~ † | | | | | | | | |
| | | | | | ······ | | | | \bigcirc |

....

Search for Individual or Company by Credential ID here:

1

Specific Credential ID 227764

Search

2 record(s) were returned by your search.

| ID | Name | City,State,Zip | Credential Type | Expiration |
|--------|-----------------------------|----------------------|---------------------------------------|------------|
| 227764 | <u>OVERLIEN,</u> WAYNE A | | Master Plumber- Restricted Service | 03/31/15 |
| 227764 | | BIG BEND WI 53103 | Utility Contractor | 03/31/16 |

| Receipt No: 1.045311 | | Oct 21, 2013 |
|---------------------------------------|-------------------------------|----------------|
| | 1015 E QUARLES PLACE | |
| LICENSES & PERMI 24-44470 PLUMBING | TS-PLUMBING PERMIT FPERMIT | 60.00 |
| Total: | | 60.00 |
| CHECK Total Applied: | Chk No: 9012 | 60.00 60.00 |
| Change Tendered: | | .00 |

٠

.

10/21/13 11:07am

VILLAGE OF FOX POINT 7200 N. SANTA MONICA BLVD FOX POINT, WI 53217

414-351-8900

3009 N. Hackett Ave Milwaukee, WI 53211

January 3, 2013

Mr. Scott Miller Fox Point Building Inspector Village of Fox Point 7200 N. Santa Monica Blvd. Fox Point, WI 53217

Dear Mr. Miller,

ļ

On January 9, 2013 we will be purchasing the home on 1015 E. Quarles Place from Lolita Friedlen.

This letter is to inform you that, upon purchase of the property and dwelling, we will not occupy the house.

Our plan is to demolish the house and build a new structure.

Thank you for your attention in this matter.

Sincerely,

Frederick Stratton III

| 2 | . ' | CP4 | ÷., | ŝ, |
|---|-----|-----|-----|----|
| | | | | |

一款 採入 化合应管 建碱化石 化合应化合应

ista u bisansi ne se isto, episosi puti interne su curente transpose estrua.

1999 A.

y en la francés de la política de la companya de l

an stra

Frank Armition Paring 8535 N. Kaul Aux Mile 53225 ph 358-1613 (Paul EIR 800 11-8994124 Job sate: Lolita Friedler 1015 Quarter Place House - 20-Road Install arched culvert 20 x 12"

| | Receipt No: 1.003168 | Jan 08, 2002 |
|----|--|--------------|
| é' | 1015 E QUARLES PLACE | |
| | LICENSES & PERMITS-PLUMBING PERMIT 10-44470 PLUMBING PERMIT | 40.00 |
| | Total: | 40.00 |

.

| CHECK | Chk No: 6589 | 40.00 |
|------------------|--------------|-------|
| Total Applied: | | 40.00 |
| Change Tendered: | | .00 |

=

01/08/02 11:20am

VILLAGE OF FOX POINT 7200 N. SANTA MONICA BLVD FOX POINT, WI 53217

414-351-8900

| | _ | - | | | \sim | | | | | | |
|---|-------------|------------------|-----------------------|---------------------|-----------------|-----------------------------|---------------------|-----------------------|----------------|--------------|--|
| Don's In | st. &ervice | e, Inc. | Fr1 | | / | | • | | | | |
| 57/0 | New Stre | | No | | | | | Цe | rBerT | FRIET | ol FN |
| Distant buse | | | olicati | ion a | and Re | ecora | Own | | | | |
| Mdre 100 C | MARE WI | \mathcal{D} | ` Ville | ide of F | ox Point | | | | 5 E.QU | | |
| (cl. No | 3-218 | 5 | | | Monica Bh | vd. | Date | 14.7 | 25 | | 1.1.2 |
| | | | Por I | 9011, v 351-8 | VI 53217 900 | | | | | | • |
| TO the VILLAGI | | | DIC AND | | | ION DEPAR | TMEN | m m | e undersig | ned he | reby |
| TO the VILLAG | e of fox i | CINT, PLUMB | | wates | C MIDEBUL | 10111 51000 JP61 | [| | ERASTE | | |
| nake application | | | | | inch | | - i | | Kind | N | 0. |
| aving a | inch | | | | | | | | | | and the second |
| builder sewer fr | rom Main | | | | | | - N - 1 | Server | nd Plumbi | Ing. 78 | 17 |
| to Building | | to | Buildi | ng | | | | Water | | | |
| • | | at | | | • | | | | | | |
| 1015 | 5'6 | QUARLE | re DI | | Fox Po | | | | | | |
| | | s at which wor | | | Fox Po | 111, W18. | | | | | |
| | ~~ | | | | | | | Water | | | |
| | | Subdivision | | | | L | ot | | B | lock | |
| | | • | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| In the per village ordinance | formance of | this work the u | indersigne | d Plum | ber hereby | agrees to be a Board for | | n by an bern | dentimitt | o all sla | Luice, |
| - | | | | | | | | | | | |
| LICENSE NO. MP. | 'RA '32' | 27 | · · · · · | | Dor | ~ Re | gn | <u></u> | | Phu | mber |
| | | | | | | | • | | | oint | |
| Application mu | st de sugne | 1 by licensed p | lumper w | no nas | cintent in | surance cen | | | | | |
| VICTURES WI | TH DRAIN | OR WATER C | ONNECTI | ONS | | | | | | | |
| | No. | | | No. | We | ter Usage | | | ••••• 👋 •••••• | | ****** |
| Hose Bibs | | . Dishwashers | | | Bu | ilding Sevier. | | | | ******** | |
| Bath Tube | | . Wesh Besins | | | W. | ter Service | • | | | | |
| Sump Pumps | | . Water Closel | | | | | | | | •••••• | |
| Laundry Trays | 0 | . Showers | | | Bu | ilding Drain | | | | ********** | |
| Drinking Fountai | | | | | Fia | | | ********** | | | |
| Sinke | 1 | | | | We | ter Meter | | | | | |
| Water Heaters | | 11 | nstem | ********* | | Total | | | ŧ | 40.6 | 20 |
| Wash. Mach. Was | | | | | | posit to cover | 9 ******** * | | Roca | + + | 3435 |
| Bidete | | - M | | | De | posit to cover | ' elsecie | t repain | | P | |
| Catch Basine | | n | 40-09-040-100-10769-2 | 2543086 4 44 | | | La - | | | • | |
| , | | | | | | , | [| , | | Permi | t Clark |
| | | | | | | | | | | | |
| A in | | | | | lotd to | | | | | | |
| A in | ch | | ngr ngraig | e hibee | | | | | feet | | ••••• |
| Curb box is loc | ated for | :tof | | | | | | | | | |
| | | | | | | | | | | | |
| inch | •••• | Water M | Actor No. | | | Date | Instal | led | | | |
| | | | | | | | | | | | |
| Ain | ch | sanitary sc | wer conne | ction w | vas made i | n | | | | | ***** |
| | - | ofman | hole | | | | | | | | |
| | 666 | | | •••• | | | | | | | |
| ********************* | | | | | | | | | | | |
| Ain | ch | etorm ecwe | r connect | ION WAL | mede in | | | | | | |
| () | | of man | hala | | | | | | | | |
| ***************** | l¢cl | | | | | | | | | | |
| ******** | | | | | | | | | | | |
| | | | | | * | ad Inspection | | leywert | Final Ineys | | Mapari |
| Building Bower | 510 500 F | Building Drain | Report | | | | | and the second second | | | |
| | | | . | | | | •••• | | | | |
| 4 | | | | | ******* | | | | | | ****** |
| ********************* | ****** | | T | | | | | | | | |
| | <u></u> | | | | Annling | tion Anorow | ed | | | | 9 |
| Installation Ar | proved | | | | | men unhi oa | | ********** | | | |
| As Built | | | | | | | | | | | , |
| | | | | | | Wa | let an | a mun | ing inspec | | |
| می از این | | | | | 1 | n vol | CIERT | ANCY | RECORD | | |
| | 3 | HEARKS | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | ,,,,,,,,,,,, | , |
| **************** | | | *********** | | | | .• | | | | |
| ** | | | ***** | ****** | | | | ••••• | | | |
| | | | | | | | | • | | | |

.

· _

VILLAGE OF FOX POINT

MILWAUKEE COUNTY, WISCONSIN

No. 775

APPLICATION FOR BUILDING PERMIT

TO THE BUILDING INSPECTION DEPARTMENT:

Story 62 Sq. Ft.

| The undersigned hereby applies for a permit to build, in accordance with the information tabulated |
|---|
| hereafter, Designation <u>Residence and garage</u> Duplex, Residence, Apartment, Store, Garage, Theatre |
| House Number 1013 6. Juarles Alsa |
| Lot 4 Block 1 |
| Subdivision Fox Point Subd |
| District |
| Does contemplated building violate the Village zoning ordinance? |
| Height of Building 1 Story (stories or feet) |
| Width (parallel to highway) 77: 11"overall (feet) |
| Depth (perpendicular to highway) 75! 2" (feet) |
| Distance: Street Line to Front Line of Porch 30 ¹ (feet) |
| ······································ |
| Type of Construction: Concrete block |
| Type of Construction: Concrete block Frame, Brick-Tile |
| Exterior finish Brick Stucco-Siding-Brick Veneer |
| Height of front yard above street sidewalk grade. 14" |
| Number of rooms |
| Estimated cost Building |
| Estimated cost Building |
| Is there a private garage?Yes |
| Does the contemplated garage violate the Village zoning ordinance?No |
| Size 16 X 27' 8" Number of stalls 1 stall |
| Where situated Attached to residence |
| General construction Concrete block and brick |
| Frame-Brick-Stucco |
| Have you applied to the Industrial Commission for a permit under the State Building Code? |
| Has the permit been granted? |
| Herewith are filed the following duplicate plansin number, which I certify I will conform to in the work hereby applied for. |
| Remarks: Plans, plot plan, survey furnished. |
| Door between garage and residence to be metal clad and also frame |
| |
| |
| |
| · |
| <u> </u> |
| Herewith are filed the specifications that describe the work in question and as shown on plans above submitted. |
| In making the application the undersigned agrees to obey the Fox Point Building Code pertaining to the erection of buildings and also agrees to obey all other ordinances of the Village of Fox Point. |
| The undersigned, owner or being duly authorized so to do, hereby gives express authorization to the Village of Fox Point, its officers, agents and employees, to enter upon the premises herein described and fill up any excavation, or tear down, remove or enclose the unfinished structure for which a permit is herein requested in the event of cessation of the building, whenever the Building Inspector shall determine that such premises in the unfinished condition of the structure are dangerous to members of the public, including children, even though trespassers. The undersigned further hereby waives all statutory notices and consents to the determination by the Village Board and the levy and placing upon the tax roll of a special assessment in the amount of the cost to the Village, including customary Village overhead charges incurred in filling up any such excavation or tearing down, removing or enclosing any such unfinished structure. |
| |
| Permit fee \$ 13.52 herewith tendered. Water Area - 2600 sq. ft. Signed |
| Dated,September 9, 19.47. |
| Architect, Owner, Builder. |

BUILDING PERMIT ISSUED 9-11-47

| | Ree # 2 9447 |
|---|-------------------|
| VILLAGE OF FOX POINT MILWAUKEE COUNTY, WISCONSIN | No. 2923 10/22/71 |

Signed

Date

7/

<u>__</u>

APPLICATION FOR HEATING PERMIT

TO THE BUILDING INSPECTION DEPARTMENT:

115

Approved:

10-22-71

The undersigned hereby applies for a permit to install, in accordance with the information tabulated hereafter,

| Win | ter Air Conditioner 🔲 | |
|--------------|--|-------------------------|
| | Fuel: Gas Oil Coal Elect. | <u> </u> |
| | Type: Forced Air, F | adiant, Baseboard, Etc. |
| | Desc. of Heating Plant 6 H-S FIRED | |
| et else | 3 | |
| | Vented to Chaim N.1. | ;, |
| | , | |
| | Fuel Tank []:Size | Location |
| <u></u> | | |
| Sum | mer Air Conditioner 🗌 | |
| | Size(Ton, H.P.) | |
| | Coolant | |
| | Compressor Coolant: Air []; Water []; If Water Cooled: Source of Water | |
| | Discharged to | |
| Rem | arks | |
| <u> </u> | | |
| ordir may | eto and that the work described herewith shall con- nances of the Village of Fox Point, and laws of the cause immediate revocation of the permit, if gra | |
| Own | er HeRB F-RIEGLEN | |
| Addı | ress of Work 1015 E QUARLE. | <u></u> |
| | Lot Block | Subdivision |
| Cont | ractor BACKMAN HEATING | |
| Addı | ress 6931 W FOND dy LAC | AVE Phone 466 5070 |
| | | Hames & Holala |

0

| | (ter # |
|--|---|
| License No. 29 SHEET 2-VILLAGE | s COPY Permit No. 7907 |
| DEPARTMENT OF ELECT | RICAL INSPECTION |
| Application for Permit for E | |
| VILLAGE OF FOX 1 | Date October 27, 19 |
| TO THE ELECTRICAL INSPECTOR: The undersigned hereby applies for a permit for the execution of | ··· ··· ··· ··· ··· ··· ··· ··· |
| prescribed: | electrical installation for light, heat, or power, as here |
| Location 1015 East Quarles Place |)o not give comer) |
| Elec. Contractor North Side Electric Co., Inc. | Address 4020 West Kiehnau Ave |
| Builder George Bachman Heating | |
| Owner Mr. H. Friedlen | |
| | ence |
| | |
| 1. Outlets | |
| 2. Fixtures 3. Fixtures — fluorescent, cold cathode, lumiline, mercury vapor | |
| 4. Audible or visual devices | |
| 5. Exhaust and ventilating fans and their control (below 1 H.P.) | |
| 6. Built-in electric heaters; bathroom, nursery, etc | |
| 7. Garbage Disposal 8. Dishwasher | |
| 9. Clothes dryer | |
| 10. Range or other receptacles over 150 volts | each |
| 11. Water heater | |
| Automatic heating equipment — <u>gas, oil</u>, coal | |
| 14. Refrigerating, air conditioning, etc., machines | |
| 15. Strip lighting, plug in strip, trol-e-duct, etc | |
| 16. Dimmers or Time Clocks | |
| Vacuum and Inert-Gas tube sign Incandescent Signs, studded lights | |
| Arc and mercury lamps, spot and floodlights (mogul base) | |
| 20. Motors, each horsepower or fraction thereof each motor | |
| 21. Generators, rectifiers, transformers, etc | |
| Feeders or subfeeders No. 3 B & S gauge or larger Raceways, wireways, busways, gutters | |
| 24. Electric heating devices (other than those listed above) | per K.W |
| 25. Service equipment - 0-100 amps. new or overhauling | per disconnect |
| Service equipment — 100 amps. to 600 amps Service equipment — over 600 amps | per disconnect 6.00 |
| 26. Temporary service, etc. (3 month period) | per disconnect |
| 27. Motion picture, stereopticon and x-ray machines, etc | each |
| 28. Re-inspection after time limit on notice | 2.00 |
| Minimum fee for any permit requiring separate inspection | |
| an application for a permit | FEES DOUBLE |
| | TOTAL FEES |
| It is hereby agreed between the understaned, as owner his agent or servant | |
| It is hereby agreed between the undersigned, as owner, his agent or servant premises and of the permit for the execution of electrical installation, for light, the Electrical Inspector, that the work thereon will be done in accordance, with t agreed to alter or install same in strict compliance with the Village of Fox Poi trical Inspector of the Village of Fox Point, the Statutes of the State of Wisconsin ston of Wisconsin under authority of the State Statutes. | leat or power as above described, to be issued and granter he description herein set forth in this statement, and it is fu |
| agreed to alter or install same in strict compliance with the Village of Fox Poi trical Inspector of the Village of Fox Point, the Statutes of the State of Wisconsir | at Elec. Code and to obey any and all lawful orders of the and the rules and regulations issued by the Industrial Com |
| | |
| REMARKS: | |
| | |
| | |
| | |
| Date for Inspection Date Approved Signar | ure 13 13 13 13 1 Scient par Sci (Supervising Electrician) |
| Roughing in Addre | |
| 100914119 III | 30 |
| ТетрСіty | Milwaukee |

.

Make check Payable to Treasurer, Village of Fox Point.



VILLAGE OF FOX POINT

MILWAUKEE COUNTY WISCONSIN

VILLAGE HALL 7200 N. SANTA MONICA BLVD. FOX POINT 53217 414-351-8900

June 19, 1991

Herbert Friedlen 1015 E. Quarles Place Fox Point, Wisconsin 53217

Dear Mr. Friedlen:

Thank you for your letter of June 07. Our Department of Public Works last week patched an "embryonic" pot hole near your residence. We will repair the cracking edges when Quarles Place is repaved. That work is <u>currently</u> scheduled for 1994.

Sincerely, Joreen Conh/

Noreen R. Cook Village Manager

HERBERT FRIEDLEN 1015 E. QUARLES PLACE MILWAUKEE, WI 53217

June 7, 1991

Village Manager Fox Point Village Hall No. Santa Monica Ave. Fox Point, WI 53217

Dear Sir:

I respectfully call to your attention that the asphalt on Quarles Pl. needs some attention. There is an embryo pot hole, and the edges are cracking off.

Very truly yours,

Hubert Friedlen

Herbert Friedlen

| Plumber E&W S Address P.O. B | ox 190 | | | No. 13.999 | Own 2022 E. | er c/o Gregg Norm North Ave, Su 300, | an of Wired Cons MKE, WI 53202 |
|---------------------------------------|---------------------------|--|----------------------------|---|----------------|---|-----------------------------------|
| Audress 'E | ig Bend, 1 | WI-53103 - | Δnnli | cation and Reco | Addr | ess July 8th | |
| Lity, State, Zip_ | | | սիիս | | Date | July 8th | . 20 |
| 'el. No <u>. (262) 66</u> | 2-3263 | <u> </u> | | Village of Fox Point | | | |
| | • | | 72 | 200 N. Santa Monica Blvd. | | | |
| | ,: | аны (1) (1) | | Fox Point, WI 53217 | | | |
| | | | | (414) 351-8900 | | | |
| O THE VILLAG | E OF FOX | POINT, PLUMB | ING AND | WATER INSPECTION DEPARTM | IENT: | PERMITS (| ISED |
| he undersigned h | ereby make | application to d | lo the work | of plumbing consisting of 1.25 inch Poly | R: | nd | No. |
| uilder sewer from | II Main ta I | ch | laying a _ | inch ory | | wer and Plumbing | |
| Building | | ot line | to Buildir | vice from Main to Lot line | 1 | ater | |
| / Dunding | | a | | ig | | | |
| | | | • | | | reet | I |
| 1015 E. Quare | | | | Fox Point, WI | | | |
| | Address a | t which work is I | o be done | | | ater Usage | |
| | | bdivision | - | Lot | | B | lock |
| Fox Point Sul | odivision | | | 4 | | ī | |
| the performance d regulations pre | of this wor scribed by | k the undersigne the Village Boar | d Plumber l d for Plumi | hereby agrees to bounden by and supers. | ubmit to all | statutes, Village ordir | ances and rules |
| ate Master Lic.# | 227764 | | _{Expir} 3/3 | 1/15 Building Contractor Reg | o# | r | Sxpir |
| | | | | | | y | мри |
| VAC Contractor | Reg# | | _Expir | Signature/h | <u>M</u> | | Applicant |
| FIXTURE WIT | 'H DRAIN | NOR WATER C | ONNECT | IONS | A | EES | |
| · · | No. | | N | o. Water Usage | | \$ | |
| lose Bibs | | Dishwasher | s | Building Sewer | 1 | | 50.00 |
| ath Tubs | _ | Wash Basin | | Water Service | 1 (2" & | under) \$ | 50.00 |
| ump Pomps | | Water Close | ts | | <u> </u> | | |
| aundry Trays | | | | | <u> </u> | | |
| rinking Pountains . inks | | Floor Drain | Grinders | Water Meter | | | 100.00 |
| Ater Heaters | · · | Sprinkling S | | | | <u> </u> | $\frac{100.00}{100.00}$ |
| Ash. Mach. Wastes | 1 | · | | Deposit to cover stre | t repairs_ | - Acer | 1 # 4 1 18 |
| idets | | | | (| | ce must be provided u | ben doing work |
| atch Basins | 1 | - | | | in roan rigi | ht of way (ROW)). | |
| | | | | |) | | Permit Clerk |
| · · · · · · · · · · · · · · · · · · · | - | | | | | | |
| | inch | <u> </u> | water ser | vice pipes laid in | | | |
| urb box is located | | feet | of | | fe | etc | f |
| | | | | | | | |
| · · · · · | inch | ······································ | | r No | Date I | nstalled | |
| | | | | ewer connection was made in | | | |
| | | | | le | | | |
| | | | | ver connection was made in | | ······································ | |
| | feet | | _of manho | le | | | |
| | | | | | <u> </u> | <u>г г г г г г г г г г г г г г г г г г г </u> | |
| | | Building Drain | Report | | Report | Final Inspection | Report |
| | Report | | | | | | |
| | Report | | | · | - | | |
| | Report | | | | | | |

i

; ;

| Search for Individual or Company by Credential ID here: | |
|---|--|
| Specific Credential ID 227764 | |
| Search | |

1

2 record(s) were returned by your search.

| ID | Name | City,State,Zip | Credential Type | Expiration |
|--------|------|----------------------|---------------------------------------|------------|
| 227764 | | 11 | Master Plumber- Restricted Service | 03/31/15 |
| 227764 | | BIG BEND WI 53103 | Utility Contractor | 03/31/16 |

| Receipt No: 1.047785 | | Jul 17, 2014 |
|--|------------------------------|------------------|
| Т. | 1015 E QUARLES PLACE | |
| LICENSES & PERMIT 24-44470 PLUMBING | rs-Plumbing Permit Permit | 100.00 |
| Total: | | 100.00 |
| CHECK Total Applied: | Chk No: 9513 | 100.00 100.00 |
| Change Tendered: | | .00 |
| | 07/17/14 00:21 am | |

,

07/17/14 09:31am

VILLAGE OF FOX POINT 7200 N. SANTA MONICA BLVD FOX POINT, WI 53217 .

| Village of Fox Point |
|----------------------------|
| 7200 N. Santa Monica Blvd. |
| Fox Point, WI 53217 |
| (414) 351-8000 |

No. 15515

APPLICATION FOR BUILDING

The undersigned hereby applies for a permit to build, in accordance with the information tabulated hereafter,

Type of Project RAZING OF RESIDENTIAL STRUCTURE Address 1015 E QUARLES PLACE

Residence, Garage, Store, Office, School, Fence, Shed, Sign, Swimming Pool, Underground Storage Tank, Etc.

Date Submittee

| Lot | Block | Subdivision | District | |
|-------------------|--|---------------------------------------|---------------------------------------|---------------------------|
| Does contemp | lated structure violate the Village : | oning ordinance? | | |
| Height of Stru | cture | | | (stories or feet) |
| Width (paralle | l to highway) | (feet) Depth (perpend | icular to highway) | (feet) |
| | | | | |
| Distance: Side | Lot Line to Structure | | | |
| Type of Const | arallel to highway)(feet) Depth (perpendicular to highway)(feet) Structure | | | |
| | Frame, Brick-t | le, etc. | Stucco, Siding, Brick | veneer, Eic. |
| Height of fron | t yard above street grade | | | |
| Number of room | ns | Baths | | |
| | Garage | | · · · · · · · · · · · · · · · · · · · | |
| Estimated cost | Building | | | |
| | Structure | | · · · · · · · · · · · · · · · · · · · | <u> </u> |
| | | | | |
| Does the conten | nplated garage violate the Village zon | ng ordinance? | ······ | |
| Size | Number | of Stalls | Where Situated | |
| Have plans be | en submitted to the Wisconsin Dep | partment of Industry, Labor and H | uman Relations for examination and | approval? |
| Have plans be | en approved as being in compliand | e with all applicable sections of the | he Wisconsin Administrative code? | |
| | | | in number, which I certify I will | conform to in the work |
| hereby applied | l for: | | | |
| Remarks: B | UILDING SIZE: MAIN | LIVING ATLEA + GATLAG | E = 18,520 WHT | |
| | 1250F | MILEA = | 10,043 cu HT | 100 |
| | TOP | T ANLEA = | 28,621 CU HT | 4.2 |
| | | | | -6 |
| Herewith are f | filed the specifications that describ | e the work in question and as show | wn on plans above submitted. | 115 |
| In making the | application the undersigned agree | s to obey the Fox Point Building a | and Zoning Codes pertaining to the e | rection of all structures |
| | | | | |

The undersigned, owner or being duly authorized so to do, hereby gives express authorization to the Village of Fox Point, its officers, agents and employees, to enter upon the premises herein described and fill up any excavation, or tear down, remove or enclose the unfinished structure for which a permit is herein requested in the event of cessation of the building, whenever the Building Inspector shall determine that such premises in the unfinished condition of the structure are dangerous to members of the public, including children, even though trespassers. The undersigned further hereby waives all statutory notices and consents to the determination by the Village Board and the levy and placing upon the tax roll of a special assessment in the amount of the cost to the Village, including customary Village overhead charges incurred in filling up any such excavation or tearing down, removing or enclosing any such unfinished structure.

We hereby agree to provide a house number plate or sign readily observable from the public highway which will be installed not less than 15 days after the structure is occupied.

| Owner of Structure RICK STRATTON & KORY SARAJIAN | Arch. or Contr. Willed CONSTRUCTION MANAGEMENT |
|---|--|
| Address 3009 N HACKETT AVE | Address 202 E NORTH AVE, SUITE 300 |
| City MILMANNE State WI Zip 5321] | City MILWAUKE State W Zip 53202 |
| Phone 414-534-6695 | Phone 414-915-7493 (GREG Norman) |
| Size of Structure(sq. ft.) F | Permit Fee_ # 11300 Receipt_ 45327 |
| Dwelling Contractor Certification No. 1269359 | Expires 9/25/14 |
| Dwelling Contractor Qualifier Certification No. 1003500 | Expires 3/14/15 |
| Building Contractor Certification No. | Applicant Signature |
| Date of Approved | |

we energies

Central Group W240 N2989 Pewaukee Rd. Pewaukee, WI 53072 Phone: 262-574-6400 Toll-free: 866-423-0364

Rick Stratton 3009 Hackett Ave Milwaukee, WI 53211

UTILITY DISCONNECTION VERIFICATION

Re: 1015 E Quarles Pl Fox Point, WI

Electric Service

I hereby certify that the electric utilities which are the responsibility of We Energies located at the above address were disconnected on: 08/13/2013

Signature:

Expediting Clerk Phone 262-574-6452; Fax 262-574-6401

<u>Note</u>: Gas utility disconnections are handled separately; contact your gas utility supplier to arrange for disconnection. For verification of We Energies gas service disconnection, please contact me at the phone number listed above.

09/26/2013

we energies.

W140 N9100 Lilly Rd. Menomonee Falls, WI 53051 www.we-energies.com

RICK STRATTON 3009 HACKETT AVE MILWAUKEE, WI 53211

UTILITY DISCONNECTION VERIFICATION

Re: 1015 E QUARLES PL FOX POINT, WI 53217

Natural Gas Service

I hereby certify that the natural gas utilities which are the responsibility of We Energies located at the above address were disconnected on: 09/18/2013

Signature:

Residential Energy Service Consultant Phone 262-502-6856; Fax 262-502-6875

<u>Note</u>: Electric utility disconnections are handled separately; contact your electric utility supplier to arrange for disconnection. For verification of We Energies electric service disconnection, please contact me at the phone number listed above.

| Ĩ | Cone Tess | umbing | Ot . | 11- | | | i i | 362-68 | 227 |
|--|---------------------------------|---------------------------------------|----------------------|----------------------------|-------------------------------|-----------------------|-------------------------|------------------|--|
| | Chertight Ph | Inc. unit 5 | No | | | ···· | | L. Frie | dien |
| PlumberN2 | Company | 15-Rd. 5318 AD | olicat | ion a | and He | ecora | Owner | 1015 5 | Quartec |
| Address | 107 W. Wie | CONST.C | Vill | lage of F | ox Point | | Address | | QUATIES PL |
| Plumber | 111d.1 (202) | •••••• | 7200 N Fox | Santa Point, V 351-8 | Monica Biv VI 53217 900 | d. | Date | | .C./. 19 PL . |
| TO the VILLAC | ie of fox | POINT, PLUMB | ing and | WATER | R INSPECT | on depar | THENT: | The undersig | ned hereby |
| make applicatio | | • | - | - | | | | PERMITS | |
| laying a | | | | | | | | Kind | No. |
| builder sewer f | rom Main | to Lot line W | | | | | Serv | er and Plumbi | ng 9966 |
| to Building | | et i | Dun | | | | | cľ | - |
| | | 6 4 | | | | | | et | 1 1 |
| | | | | | Fox Pol | nt, Wis. | Mate | K | |
| | Addres | s at which worl | c is to be | done | | `` | Wat | er Umge | |
| | | Subdivision | | | | 1 | ot | B | lock |
| | | | | | | | | | ومغيفة فالادامانين |
| | | | | | | 1 | | | |
| village ordinance | cs, and rul | | ndersign ns prese | ed Plum ribed by | ber hereby the Village | Board for | Plumbers | • | |
| License No | 202 | 395 | | | | Nene | | | Plumber |
| Application mu | ist be signe | d by licensed a | umber w | ho has | current ine | urance cert | | | |
| | TH DRAIN | OR WATER C | | IONS | | | 1 | | |
| Hose Bibs | <u> </u> | Dishwashers | | <u>No.</u> | | cr Usage | | | |
| Bath Tube | | | | | But | ding Sewer | | | |
| Sump Pumpe | | | | | Wal | er Service | | |) * * \$ * * * * * * * * * * * * * * * * |
| Laundry Trays | | | | | But | ding Drain . | | | |
| Drinking Fountai | | | | | Fud | LIFC8 | | | |
| Sinke | | | | | Wat | er Meter | • | | |
| Water Heaters | | | stem | ******** | | | .: | ŧ | 240.00 |
| Wash. Mach. Was | sics | Urinale | | | 'Den | | | - Recei | 240.00 L#3168 |
| Bidets | | · · · · · · · · · · · · · · · · · · · | | | 00 000 | | eries iche | | [7000000000000000000000000000000000000 |
| Catch Basine | •••••• | •• ••••••••••••••• | | ••••• | 400 | | | | |
| | | •• •••••• | | ******** | ידאי ^ו | | | | |
| A | | | ter servic | z pipce | laid in | | | •••• | |
| Curb box is loc | ated fe | ctof | | | | | | ícct | |
| | | | | | | | | | |
| | | Water M | | | | Date | installed | | |
| | | | | | | | | | |
| Ain | ch | sanitary sci | ver conn | ection w | ras made in | | | | |
| | leet | of manh | olc | | | | | | |
| | | | | | | | | | |
| · | | storm scwci | | | | | | | |
| | | | | | | | | | |
| ····· | fcct | of manh | oic | | | | | | ** |
| | | | | | | | | | |
| | | Building Drain | Report | | h la When he | d Inspection | Hopert | Tinal Inope | ution Report |
| Building Gewer | Report | Building Draim | | | | | | | |
| | •••••• | •••• | | † | | | | •••••••••••••••• | , |
| | ••••• | | •••••• | + | | | | ••••• | , |
| | <u> </u> | L | | 1 | | | | | 19 |
| Installation A | poroved | | | | Applicat | on Approv | 60 | | |
| As Built | | | | | | | | | |
| | | | | | | Wa | LET AND MU | mbing inspect | |
| | | UNBEARKS | | | | DIN | CHEPANC | YRECORD | · · |
| and the second sec | n a trainigh a Tairtí | | · | | | · · · · · · · · · · · | | | |
| | | | | | | | | | • • • • • |
| | •••• | | | | | | •••• ••• ••••••• | | |
| | | | | | l | | ***** | | |
| **************** | | • | | | | | | | |

STRUCTURAL CALCULATIONS

FEB. 27, 2013 PROJECT NO. 13-129

PROJECT:

ŗ 1.1.80


a 1977

The Stratton Resdience A CUSTOM DESIGNED HOME 1015 EAST QUARLES PLACE FOX POINT, WI

ARCHITECT:

JOY PEOT-SHIELDS


ENGINEER:




TDI ASSOCIATES, INC.

ARCHITECTS, ENGINEERS, PLANNERS NB W22350 JOHNSON DRIVE SUITE B4 WAUKESHA, WISCONSIN 53186 (262) 409-2530 OFFICE (262) 409-2531 FAX

1





Job: Stratton Residence-Fox Point

Architects • Engineers • Planners Project No.: 13-159

Date: May 4, 2013 Sheet_____of____

Concrete Foundation Wall- Resist Soil Pressure If Unreinforced Wall works for Loading, Reinforcement may be added without satisfying Temperature & Shrinkage Thickness of Foundation Wall (Width) W (in) 10 Mal of Wal Grade **Height of Wall** L (ft) 9.0 Top of Wall to Grade l (inches) 8 Thickness of Basement Slab t_{slab} (inches) з 69 **Equivalent Lateral Fluid Pressure** 3 Horizontal Pressure from Soil psf 60 Hvdrostatic Pressure 15 psf Wall Width Total Equiv. Pressure (unfactored) 75 psf Unbraced Length ft 8.21 Horizontal Force and Moment Produced from Equiv. Pressure Compounded Press. At Wall Bot. psf 615.625 Horizontal Force (1/3) from Bot. Pound-force 2526.6 Distance Unfactored Moment M (#-ft) 11/2" 2654.64 Vert. Reinf. tο Factored Moment (1.2DL+1.6LL) M., (#-ft) 3397.94 Wall Horiz, Reinf. **Check Wall Design- Unreinforced** Ъ See note below Section Modulus of Wall Section S (in³) 200 Height **Concrete Compressive Strength** Fc (psi) 3,000 φ Mn = φ 5 (F_c)^{1/2} S (1'/12") φMn (#*ft) 4107.9 Check ØMn > M. **Unreinforced Wall Works** Vertical Reinforcement Required (for Bending) Factored Moment (1.2DL+1.6LL) М́., (#-ft) 3397.94 Depth to Comp. Line (minus cover) d (in) 8.19 **Bar Designation** /8 = inches 5 Keyway Allowed Steel Stress f_v (psi) 60.000 or Dowel # bar vs. 1/3L Bar Development at Critical Bending О.К. As- required (bending vs. Asmin, if Reg'd) in² 0.0933 Spacing of Bars- Maximum inches 39.89 Spacing of Bars- Chosen (less than Max) inches 36 φ Mn = φ Asfy/12 * [d- (Asfy/(1.7*b*f'_c)] φMn (#*ft) 3760.08 Check $\wp Mn > M_{II}$ **O.K. Check Beam Shear at Bottom Support** Horizontal Reinforcement Force at Bottom of wall (at support) P (lbs) 1684.4 Reinforcing Per ACI 7.12.2 is Not Reg'd V_u =[(1.2DL+1.6LL)/DL+LL]*P V_u (lbs) 2156.1 Use # 5 bar at Top, Middle, & Bottom $\varphi V_c = \varphi^* 2^* (f_c)^{\prime\prime 2} |^* d$ φV_{c} (lbs) 9148.3 Check $\varphi V_{c} > V_{u}$ 0.K. Design width of Keyway or Dowel required Keyway width (minimum) = $(V_u * d)/\varphi V_c$ w (inches) 1.930 20 **Dowel Lengths** Bar Designation /8 = inches 5 Spacing of Bars- Chosen inches 36 Depth of Footing h (inches) 12.0 Strength of Rebar (see lengths, right) φV_n (lbs) 2241.3 12 Check $\varphi V_n > V_u$ **O.K.**


Designer reserves all copyrights to these calculations which are not to be reproduced, copied, or assigned to any third party in any form or manner without first obtaining the expressed written permission of TDI Associates, Inc.




TDI Associates, Inc. Job: Stratton Residence-Fox Point

Architects • Engineers • Planners Project No.: 13-159

Date: May 4, 2013 Sheet_____ of





Architects • Engineers • Planners


Job: Stratton Residence-Fox Point Project No.: 13-159

Date: May 4, 2013 Sheet____of___

| F-1 Footing Design- Point Load & Moment | | | | | |
|---|-----------------------------------|--------|----------|--------|--|
| Knowns | worst case | | | | |
| Vertical Load- combined | P (k) | 30 | _ | - | |
| Moment (x-x) dead | M _{xd} (k-ft) | 0 | | | |
| Moment (x-x) live | M _{xl} (k-ft) | 0 | | | |
| Moment (y-y) dead | M _{yd} (k-ft) | 0 | | | |
| Moment (y-y) live | M _{vl} (k-ft) | 0 | | - | |
| Column dim- I | c1 (in) | 4 | | | |
| Column dim- b | c2 (in) | 4 | | | |
| Conc.C stress | f' _c (ksi) | 3 | | - | |
| Allowed Steel stress | f _y (ksi) | 60 | | | |
| Soil Pressure | q _a (ksf) | 3 | | | |
| Factors (1.2DL + 1.6LL), | use P*1 49 | | | • | |
| Vertical Load- Ult. | P _u (k) | 44.7 | | | |
| Moment (x-x) -Ult. | M _{ux} (k-ft) | 0 | | 1 | |
| Moment (y-y) -Ult. | M _{uy} (k-ft) | õ | | Ţ | |
| | | Ū | | | |
| Dimensions | | | | , | |
| Estimate A | ~A (tt⁻) | 12.00 | | | |
| (1.2* P/q _a) | | | | | |
| Length | l (ft) | 4.5 | | | |
| Width | b (ft) | 2.5 | | I | |
| Area | A (ft ²) | 11.25 | | ī | |
| Section Mod. (x-x) | S _x (ft ³) | 8.44 | | 1 | |
| Section Mod. (y-y) | S_y (ft ³) | 4.69 | | I | |
| Soil P (max) | q _{max} (ksi) | 2.67 | | | |
| Soil P (min) | q _{min} (ksi) | 2.67 | О.К. | - | |
| Factored Soil P (max) | q _{umax} (ksi) | 3.97 | | 7 | |
| Factored Soil P (min) | qu _{min} (ksi) | 3.97 | | | |
| Depth | h (in) | 12 | | | |
| Comp. Line | d (in) | 8.0625 | | | |
| Conc. Volume | tt ³ | 11.25 | | , | |
| | 1 | 11.20 | | ÷ | |
| | Y | | | | |
| | | | | _ | |
| | | | | E | |
| | | | | ŧ | |
| My- | ч I | | | [| |
| ¥ | \uparrow | | | ŧ | |
| | | | | ٦ | |
| ~ ~ | | -x | ~ | ξ | |
| × | - +)- | · | <u>×</u> | \$ | |
| ÷ l | | | | | |
| LENGTH (1) | | | | C | |
| | | | | Ē | |
| " | | 1 | | # | |
| | | | | Г | |
| | , | | | ŧ | |
| ШОТН (Ь | 2 | | | ד ר | |
| | | | | ļ | |
| | ' | | | Ì | |
| | | | | 9 | |

| Loads applied at center of foo | ting- Using | g ACI-318-02 | |
|--|-------------------------|--------------|-------------------------------|
| Beam Shear- length | | | |
| b (base) = width | inches | 30 | _ |
| Edge Dist = 1/2I5c1-d | inches | 16.94 | |
| $V_u = qu^*$ (area to edge) | kips | 14.02 | |
| $V_{n} = V_{u} / .85$ | kips | 16.49 | _ |
| $V_c = 2^* (f_c)^{1/2} b^* d$ | kips | 26.50 | 0.к. |
| Design Observes 1 HI | | | |
| Beam Shear- width | inches | | - |
| b (base) = length | inches | 54 | |
| Edge Dist = 1/2b5c1-d | inches | 4.94 | |
| $V_u = qu^*$ (area to edge) $V_n = V_u/.85$ | kips | 7.36 | |
| $\frac{V_n - V_0' \cdot 0.5}{V_c - 2^* (f_c)^{1/2} \cdot 1^* d}$ | kips | 8.66 | |
| $v_c = 2 (1_c) + 1_c$ | kips | 47.69 | О.К. |
| Punching Shear | | | |
| b _o | inches | 48.25 | - |
| A _o | sq. in. | 145.50 | |
| $V_u = qu^*((l^*b)-A_o)$ | kips | 40.69 | |
| $V_{n} = V_{u}/.85$ | kips | 47.86 | |
| $V_c = 4^* (f_c)^{1/2} b_o^* d$ | kips | 85.23 | О.К. |
| Pending A Deg d | | | |
| Bending- As Req-d | f | | - 1 |
| Edge Dist Length= 1/2I5c1 | feet | 2.08 | |
| Edge Dist Width= 1/2b5c2 | feet | 1.08 | |
| M _{ux} =qu*area*1/2 dist.* 1.33 | k-ft in [∠] | 28.67 | |
| As- Long direction (bending) | יוי יוי | 0.82 | |
| Min As (temp. & shrinkage) | in² | 0.65 | - |
| As Required- long direction | 111 | 0.82 | |
| M _{uy} =qu*area*1/2 dist.* 1.33 | k-ft | 13.95 | |
| As -short direction (bending) | in ² | 0.39 | |
| Min As (temp. & shrinkage) | in² | 1.17 | _ |
| As Required- short direction | in ² | 1.17 | |
| Choose Bars and Spacing- Lo | na Directio | n | |
| Bar designation | | 5 | – о.к. |
| # of bar layers (top & bottom?) | | 1 | |
| Development Length (inches) | in | 27.39 | <edge dist.<="" td=""></edge> |
| # of bars required | | 3.0 | |
| Total area of bars | in ² | 0.93 | |
| Spacing Distance (inches) | in | 13.50 | о.к. |
| φ Mn of the design (φ = .9) | k-ft | 32.22 | - |
| | | | |
| Choose Bars and Spacing- Sho | ort Directio | | _ |
| Bar designation | | 5 | О.К. |
| # of bar layers (top & bottom?) | | 1 | |
| Development Length | in. | 27.39 | <edge dist.<="" td=""></edge> |
| # of bars required | . 2 | 4.0 | |
| Total area of bars | in² | 1.24 | |
| Spacing Distance | in | 17.00 | - ^{О.К.} |
| φ Mn of the design (φ = .9) | k-ft | 43.48 | |

V



Architects • Engineers • Planners

Job: Stratton Residence-Fox Point Project No.: 13-159


Date: May 4, 2013 Sheet____of__

| Loads applied at center of for | oting- Usin | g ACI-318-02 | 2 |
|---|------------------------|------------------------------|-------------------------------|
| Beam Shear- length | | | |
| b (base) = width | inches | 36 | - |
| Edge Dist = $1/2I$ 5c1-d | inches | 7.94 | |
| $V_u = qu^*$ (area to edge) | kips | 8.21 | |
| $V_n = V_u / .85$ | kips | 9.66 | _ |
| $V_c = 2^* (f_c)^{1/2} b^* d$ | kips | 31.80 | О.К. |
| Deem Observed III | | | |
| Beam Shear- width b (base) = length | inches | 36 | |
| Edge Dist = 1/2b5c1-d | inches | 7.94 | |
| $V_u = qu^*$ (area to edge) | | | |
| $V_{\rm u} = V_{\rm u}/.85$ | kips | 8.21 | |
| $V_c = 2^* (f_c)^{1/2} * I^* d$ | kips | 9.66 | |
| $v_c = 2 (r_c) + \alpha$ | kips | 31.80 | 0.K. |
| Punching Shear | | | |
| b _o | inches | 48.25 | |
| A _o | sq. in. | 145.50 | |
| $V_u = qu^*((l^*b)-A_o)$ | kips | 33.07 | |
| $V_n = V_u / .85$ | kips | 38.90 | |
| $V_c = 4^* (f_c)^{1/2} b_o^* d$ | kips | 85.23 | О.К. |
| Bonding A Bog d | | | |
| Bending- As Req-d | | | _ |
| Edge Dist Length= 1/2I5c1 | feet | 1.33 | |
| Edge Dist Width= 1/2b5c2 | feet | 1.33 | |
| M _{ux} =qu*area*1/2 dist.* 1.33 | k-ft in≤ | 14.68 | |
| As- Long direction (bending) | ווז וח ^ב | 0.41 | |
| Min As (temp. & shrinkage) | | 0.78 | _ |
| As Required- long direction | 111 | 0.78 | |
| M _{uy} =qu*area*1/2 dist.* 1.33 | k-ft | 14.68 | |
| As -short direction (bending) | in ² | 0.41 | |
| Min As (temp. & shrinkage) | in² | 0.78 | |
| As Required- short direction | in ² | 0.78 | - |
| Chappe Pers and Chaping La | | _ | |
| Choose Bars and Spacing- Log Bar designation | ng pirectio | | - or |
| # of bar layers (top & bottom?) | | 5 | О.К. |
| | in | 1 | |
| Development Length (inches) # of bars required | in | 27.39 | <edge dist.<="" td=""></edge> |
| Total area of bars | in ² | 3.0 | |
| Spacing Distance (inches) | | 0.93 | 0.1 |
| φ Mn of the design ($\varphi = .9$) | k-ft | <u>16.50</u> <u>32.47</u> | О.К. |
| | | | |
| Choose Bars and Spacing- Sho | ort Direction | n | _ |
| Bar designation | | 5 | о.к. |
| # of bar layers (top & bottom?) | | 1 | |
| Development Length | in. | 27.39 | <edge dist.<="" td=""></edge> |
| # of bars required | _ | 3.0 | |
| Total area of bars | in ² | 0.93 | |
| Spacing Distance | in | 16.50 | О.К. |
| φ Mn of the design (φ = .9) | k-ft | 32.47 | |
| | | | |

F-2 Footing Design- Point Load & Moment

| Knowns | worst case | | |
|---|---|--------------|-----|
| Vertical Load- combined | P (k) | 25 | |
| Moment (x-x) dead | M _{xd} (k-ft) | 0 | |
| Moment (x-x) live | M _{xl} (k-ft) | 0 | |
| Moment (y-y) dead | M _{yd} (k-ft) | 0 | |
| Moment (y-y) live | M _{yl} (k-ft) | 0 | |
| Column dim- I | c1 (in) | 4 | |
| Column dim- b | c2 (in) | 4 | |
| Conc.C stress | f' _c (ksi) | 3 | |
| Allowed Steel stress | f _y (ksi) | 60 | |
| Soil Pressure | q _a (ksf) | 3 | |
| Factors (1.2DL + 1.6LL), | use P*1.49 | | |
| Vertical Load- Ult. | P _u (k) | 37.25 | |
| Moment (x-x) -Ult. | M _{ux} (k-ft) | 0 | |
| Moment (y-y) -Ult. | M _{uy} (k-ft) | 0 | |
| | | | |
| Dimensions Estimate A | ~A (ft ⁻) | 10.00 | |
| | / (it) | 10.00 | |
| (1.2* P/q _a) | | | |
| Length Width | (ft) ト (ft) | 3 | |
| | b (ft) | .3 | |
| Area Section Mod. (x-x) | A (ft ²) S _x (ft ³) | 9 4.50 | |
| Section Mod. (y-y) | S_{y} (ft ³) | 4.50 4.50 | |
| Soil P (max) | q _{max} (ksi) | 2.78 | |
| Soil P (min) | q _{max} (ksi) q _{min} (ksi) | 2.78 | О.К |
| Factored Soil P (max) | q _{umax} (ksi) | 4.14 | • |
| Factored Soil P (min) | qu _{min} (ksi) | 4.14 | |
| Depth | h (in) | 12 | |
| Comp. Line | d (in) | 8.0625 | |
| Conc. Volume | ft ³ | 9 | |
| | | | |
| | Y | | |
| | · · · · · · · · · · · · · · · · · · · | | |
| | | | |
| My- | 9 | | |
| × | | | |
| | | | |
| × CI | T M× | -x | × |
| ~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~ | ΨŢ | | |
| | 22 ₁ | | |
| L S N | | | |
| <u><u> </u></u> | 1 | | |
| | l | | |
| ШОТН (Ь) | | J | |
| | l | | |
| ٢ | r | | |
| | I | | |

Designer reserves all copyrights to these calculations which are not to be reproduced, copied, or assigned to any third party in any form or manner without first obtaining the expressed written permission of TDI Associated, Inc.



Architects • Engineers • Planners

Job: Stratton Residence-Fox Point Project No.: 13-159

Date: May 4, 2013 Sheet____of___

| Loads applied at center of foo | oting- Usin | g ACI-318-02 | |
|---|-----------------|--------------------|------------------------------|
| Beam Shear- length | | | |
| b (base) = width | inches | 42 | _ |
| Edge Dist = 1/2I5c1-d | inches | 10.94 | |
| V _u = qu*(area to edge) | kips | 12.03 | |
| $V_n = V_u/.85$ | kips | 14.15 | |
| $V_c = 2^* (f_c)^{1/2*} b^* d$ | kips | 37.09 | о.к. |
| Beam Shear- width | | | |
| b (base) = length | inches | 42 | _ |
| Edge Dist = 1/2b5c1-d | inches | 10.94 | |
| V _u = qu*(area to edge) | kips | 12.03 | |
| $V_n = V_u / .85$ | kips | 14.15 | |
| $V_c = 2^* (f_c)^{1/2*} l^* d$ | kips | 37.09 | о.к. |
| Punching Shear | | | |
| bo | inches | 48.25 | - |
| A _o | sq. in. | 145.50 | |
| $V_u = qu^*((I^*b) - A_o)$ | kips | 42.38 | |
| $V_n = V_u / .85$ | kips | 49.86 ⁻ | |
| $V_{c} = 4^{*}(f_{c})^{1/2}b_{o}^{*}d$ | kips | 85.23 | о.к. |
| Bending- A _s Req-d | | | |
| Edge Dist Length= 1/2I5c1 | feet | 1.58 | - |
| Edge Dist Width= 1/2b5c2 | feet | 1.58 | |
| M _{ux} =qu*area*1/2 dist.*1.33 | k-ft | 22.00 | |
| As- Long direction (bending) | in⁴ | 0.62 | |
| Min As (temp. & shrinkage) | in- | 0.91 | |
| As Required- long direction | în ' | 0.91 | • |
| M _{uy} =qu*area*1/2 dist.* 1.33 | k-ft | 22.00 | |
| As -short direction (bending) | in ² | 0.62 | |
| Min As (temp. & shrinkage) | in ² | 0.91 | |
| As Required- short direction | in ² | 0.91 | - |
| Choose Bars and Spacing- Lor | na Direction | 1 | |
| Bar designation | × | 5 | О.К. |
| # of bar layers (top & bottom?) | | 1 | |
| Development Length (inches) | in | 27.39 | <edge dis<="" td=""></edge> |
| # of bars required | | 3.0 | |
| Total area of bars | in² | 0.93 | |
| Spacing Distance (inches) | in | 18.00 | О.К. |
| φ Mn of the design (φ = .9) | k-ft | 32.65 | • |
| Choose Bars and Spacing- Sho | ort Direction | า | |
| Bar designation | | 5 | О.К. |
| # of bar layers (top & bottom?) | | 1 | |
| Development Length | in. | 27.39 | <edge dist<="" td=""></edge> |
| of bars required | - | 3.0 | |
| Fotal area of bars | in ² | 0.93 | |
| Spacing Distance | in | 18.00 | 0.K. |
| ρ Mn of the design (φ = .9) | k-ft | 32.65 | 2.14 |

| F-3 Footing Design- | Point Load | & Moment |
|---------------------|--------------------------------|----------|
|---------------------|--------------------------------|----------|

| Knowns | worst case | | |
|----------------------------|-----------------------------------|-----------------|------|
| Vertical Load- combined | P (k) | 31 | _ |
| Moment (x-x) dead | M _{xd} (k-ft) | 0 | |
| Moment (x-x) live | M _{xi} (k-ft) | 0 | |
| Moment (y-y) dead | M _{yd} (k-ft) | 0 | |
| Moment (y-y) live | M _{yi} (k-ft) | Ó | |
| Column dim- I | c1 (in) | .4 | |
| Column dim- b | c2 (in) | 4 | |
| Conc.C stress | f' _c (ksi) | .3 | |
| Allowed Steel stress | f _v (ksi) | 60 | |
| Soil Pressure | q _a (ksf) | 3 | |
| Factors (1.2DL + 1.6LL), | use P*1.49 | | |
| Vertical Load- Ult. | P _u (k) | 46.19 | - |
| Moment (x-x) -Ult. | M _{ux} (k-ft) | 0 | |
| Moment (y-y) -Ult. | M _{uy} (k-ft) | 0 | |
| Dimensions | | | |
| Estimate A | ~A (ft ⁻) | 12.40 | |
| (1.2* P/q _a) | | | |
| Length | l (ft) | 3.5 | |
| Width | b (ft) | 3.5 | |
| Area | A (ft ²) | 12.25 | |
| Section Mod. (x-x) | S _x (ft ³) | 7.15 | |
| Section Mod. (y-y) | $\hat{S_y}$ (ft ³) | 7.15 | |
| Soil P (max) | q _{max} (ksi) | 2.53 | |
| Soil P (min) | q _{min} (ksi) | 2.53 | О.К. |
| Factored Soil P (max) | q _{umax} (ksi) | 3.77 | |
| Factored Soil P (min) | qu _{min} (ksi) | 3.77 | |
| Depth | h (in) | 12 | |
| | | | |
| Comp. Line Conc. Volume | d (in) ft ³ | 8.0625 12,25 | |
| conc. volume | 1 | 12,20 | |
| | | -x | × |
| | - <u> </u> | | |

WIDTH (b)

ן ר

Designer reserves all copyrights to these calculations which are not to be reproduced, copied, or assigned to any third party in any form or manner without first obtaining the expressed written permission of TDI Associated, Inc.



Architects • Engineers • Planners

Job: Stratton Residence-Fox Point

Project No.: 13-159

Date: May 4, 2013 Sheet_____of____

| C. Spread Footings at house | |
|---|--|
| 1. Worse case exterior wall load | P _{max} = 2000.0 #, Wall, Floor & Roof Loads P _{wall} = 1125 #, wall weight |
| Wall Properties | P _{total} = 3125.0 # on Footing |
| Height: 9.00 ft., Concrete Wall | 5 |
| Width: 10 in., Concrete Wall | pf _{allow} = 3000 psf, Allowable Soil Pressure F'c = 3000 psi, Conc. Compr. Strength |
| Footing Properties | As _{reg} = 0.346 in2, (0.0018*b*h) for T& s |
| Width _{reg} : 12.5 in., Concrete Footing | |
| Width _{chosen} : 24 in. O.K. | (2) #5 bar =.62 in2 > Asreq O.K. |
| Height _{req} : 4.0 in., Concrete Footing | |
| Height _{chosen} : 8 in. O.K. | <u>Bars at bottom have 3" of Cover Reg</u> 'd |

Use 24'' wide x 8'' tall footing, with (2) #5 bar continuous

ŝ



Architects • Engineers • Planners

Job: Stratton Residence-Fox Point Project No.: 13-159

Date: May 4, 2013 Sheet_____of_____

| C. Spread Footings at garage | |
|--|--|
| Worse case exterior wall load | P _{max} = 1400.0 #, Wall, Floor & Roof Load |
| | P _{wall} = 400 <i>#,</i> wall weight |
| Wall Properties | P _{total} = 1800.0 # on Footing |
| Height: 4.00 ft., Concrete Wa | II |
| Width: 8 in., Concrete Wal | |
| | F'c = 3000 psi, Conc. Compr. Strength |
| Footing Properties | As _{reg} = 0.288 in2, (0.0018*b*h) for T & |
| Width _{reg} : 7.2 in., Concrete Foo | · · · · |
| Width _{chosen} : 20 in. O.K. | (2) #5 bar =.62 in2 > Asreg O.K. |
| Height _{reg} : 3.4 in., Concrete Foo [.] | |
| Height _{chosen} : 8 in. O.K. | Bars at bottom have <u>3" of Cover</u> Reg'd |

Designer reserves all copyrights to these calculations which are not to be reproduced, copied, or assigned to any third party in any form or manner without first obtaining the expressed written permission of TDI Associates, Inc.

đ



Architects • Engineers • Planners

Job: Stratton Residence-Fox Point Project No.: 13-159 Date: May 4, 2013 Sheet____of____

| Support Structure | | | | | | | | | | |
|--|-----------------------|-------|------------|------|--------|--------|----|----------|------|-----|
| Steel Pipe Columns | | | | | | | | | | |
| 1. Column C-1 | | | Try: | 3.00 | " Dia. | std | S† | eel Pipe | : | |
| Column Height (kL): | <u>9.00</u> | feet | - | Fy : | 35 | ksi | | | - | |
| Unfactored Load P: | 13.40 | kips | | r: | 1.16 | inches | 5 | | | |
| Factored Load Pu: 13.00 kip | kips | | Ag: | 2.23 | in⁴ | | | | | |
| λ c = kL/r*(F _y / π ² *E | | | λ c | = | 1.03 | | | | | |
| If λ c<1.5, Fcr = (0.6 | 658 ^{λc^2}) | *Fy | Fcr | = | 22.46 | | | | | |
| $_{\sim}$ If λ c>1.5, Fcr = (0.8 | 877/λc²) |) *Fy | | | | | | | | |
| φ Pcr = 0.85*Fcr*A | S | - | φPcr | = | 42.57 | kips | < | 13.00 | kips | 0.k |
| At Column C-1 | | | , Use | 3 | " Dia. | 7.58 | | s/ft Pip | | 1 |

3



¥

Architects • Engineers • Planners

Job: Stratton Residence-Fox Point Project No.: 13-159

Date: May 4, 2013 Sheet____of____

| III. Support Structure B. Steel Pipe Columns 1. Column C-2 | | Try | : 3 | " Dia. | std | Steel Pij | De | |
|--|-------|------|-----|--------|-----------------|-----------|---------|------|
| Column Height (kL): <u>9.00</u> | feet | , | | 35 | ksi | | | |
| Unfactored Load P: 12.50 | kips | | r: | 1.16 | inches | 5 | | |
| Factored Load Pu: 26.00 | kips | | Ag: | 2.23 | in [∠] | | | |
| λ c = kL/r*(F _y / π ² *E) ^(1/2) | | λc | = | 1.03 | | | | |
| If λ c<1.5, Fcr = (0.658 $^{\lambda$ c^2}) | *Fy | Fcr | = | 22.46 | | | | |
| If λ c>1.5, Fcr = (0.877/ λ c ²) |) *Fy | | | | | | | |
| arphiPcr = 0.85*Fcr*As | | φPcr | = | 42.57 | kips | < 26.00 |) kips | 0.K. |
| At Column C-2 | , | Use | 3 | " Dia. | 7.58 | Lbs/ft P | ipe |] |

Designer reserves all copyrights to these calculations which are not to be reproduced, copied, or assigned to any third party in any form or manner without first obtaining the expressed written permission of TDI Associates, Inc.



Job: Stratton Residence-Fox Point Project No.: 13-159

Date: May 4, 2013 Sheet____of____

| | teel Pipe Columns . Column C-3 | | | Trv | : 3 | " Dia | std | St | eel Pipe | , | |
|---|---|-----------------------|------|------|-----|-------|--------|----|----------|------|----|
| | Column Height (kL): | <u>9.00</u> | feet | , | | 35 | | | | _ | |
| | Unfactored Load P: | 24.60 | kips | | r: | 1.16 | inches | | | | |
| | Factored Load Pu: | 36.65 | kips | | Ag: | 2.23 | in² | | | | |
| | λ c = kL/r*(F _y / π^{2*} | E) ^(1/2) | | λc | = | 1.03 | | | | | |
| | If λ c<1.5, Fcr = (0. | 658 ^{\c^2}) | *Fy | Fcr | = | 22.46 | | | | | |
| i | If λ c>1.5, Fcr = (0. | 877/λc ²) |)*Fy | | | | | | | | |
| | φ Pcr = 0.85*Fcr*A | ls | • | φPcr | ' = | 42.57 | kips | < | 36.65 | kips | 0. |

Designer reserves all copyrights to these calculations which are not to be reproduced, copied, or assigned to any third party in any form or manner without first obtaining the expressed written permission of TDI Associates, Inc.


7



Job: Stratton Residence-Fox Point Project No.: 13-159 Date: May 4, 2013 Sheet____of____

| III. Support Structure | | | | | | | | |
|---|------|------|--------|--------|-----|----------|------|------|
| B. Steel Pipe Columns | | | | | | | | |
| 1. Basement Beam C-4 | Try: | 3.50 | " Dia. | std | St | eel Pipe | 2 | |
| Column Height (kL): <u>9.00</u> feet | | Fy : | 35 | ksi | | | - | |
| Unfactored Load P: 30.22 kips | | r: | 1.34 | inches | ; | | | |
| Factored Load Pu: 45.03 kips | | Ag: | 2.68 | in⁴ | | | | |
| λ c = kL/r*(F _y / π^{2} *E) ^(1/2) | λc | = | 0.891 | | | | | |
| If λ c<1.5, Fcr = (0.658 $^{\lambda$ c ²) *Fy | Fcr | = | 25.1 | | | | | |
| If λ c>1.5, Fcr = (0.877/ λ c ²) *Fy | | | | | | | | |
| arphiPcr = 0.85*Fcr*As | φPcr | = | 57.18 | kips | < | 45.03 | kips | 0.K. |
| At Basement Beam C-4 , | Use | 3.50 | " Dia. | 9.12 | Lbs | s/ft Pip | e | 1 |

:




Architects • Engineers • Planners

Job: Stratton Residence-Fox Point Project No.: 13-159 Date: May 4, 2013 Sheet_____of_

W 8 x 21 -Wide Flange Section Designation B-1 50,000 psi, E

50,000 psi, Elastic Yield Stress LRFD, 3rd Edition

| Beam/Column Length (strong) | 12'6" | | Properties from Section Designated, include LTB | _ |
|--|-------------------------|--------------------------------|--|-----|
| (k) _x length factor adjustment | 1.0 | | $\lambda \mathbf{c}_{\mathbf{x}} = \mathbf{k} \mathbf{L}_{\mathbf{x}} / \mathbf{r}_{\mathbf{x}}^{*} (\mathbf{F}_{\mathbf{y}} / \pi^{2*} \mathbf{E}) \qquad \lambda \mathbf{c}_{\mathbf{x}} \qquad 0.568$ | - |
| Unbraced Length of Comp. Flange | 1.34 | feet | If $\lambda c_x < 1.5$, Fcr _x = (0.658 ^{$\wedge c^{n_x}$}) *Fy Fcr _x 43.68 | |
| Beam/Column Length (weak) | 12'6" | •* | If $\lambda c_x > 1.5$, Fcr _x = (0.877/ λc^2) *Fy Fcr _x 0.00 | |
| (k) _y length factor adjustment | 1.0 | | | |
| - | | | $\lambda c_y = kL_y/r_y^*(F_y/\pi^{-*}E)$ λc_y 1.573 | |
| Axial Load 1, and type (kips) | 0.1 | DL | If $\lambda c_v < 1.5$, Fcr _v = (0.658 $^{\wedge \sigma' 2}$) *Fy Fcr _v 0.00 | |
| Axial Load 2, and type (kips) | 0.1 | LL | If $\lambda c_y > 1.5$, Fcr _y = (0.877/ λc^2) *Fy Fcr _y 17.71 | |
| Transverse Load 1, strong (#/LF) | 720 | DL | | |
| Transverse Load 2, strong (#/LF) | 1440 | LL | Capacity for Axial Compression φ Pn (kips) 92.74 | О.К |
| Transverse Load 1, weak (#/LF) | 0 | WL | Capacity for Moment (strong axis) φMn_x (k-ft) 76.50 | О.К |
| Transverse Load 2, weak (#/LF) | 0 | - | Capacity for Moment (weak axis) φMn_v (k-ft) 21.34 | О.К |
| Torsion Load 1, and type (#/LF) | 500 | DL | Capacity for Shear φ Vn (k-ft) 55.89 | О.К |
| Torsion Load 2, and type (#/LF) | 500 | LL | Capacity for Torsion φ Tn (k-ft) 342.00 | О.К |
| | | | • · · · • · · · • • · · · · · · · · · · | _ |
| Calculate Factored Load Case 1: 1.: Factored Axial Load | P _u (kips) | + 0.8WL 0.28 | Calculate Factored Load Case 2: 1.2DL + 1.0LL + 1.6W Factored Axial Load P _u (kips) 0.22 | Ļ |
| Factored Transverse Load (strong) | w _u (k/ft) | 3.168 | Factored Transverse Load (strong) $w_{\rm u}$ (k/ft) 2.304 | |
| Factored Transverse Load (weak) | w _u (k/ft) | 0 | Factored Transverse Load (weak) w _u (k/ft) 0 | |
| Factored Torsion Load | T _u (k/ft) | 1.4 | Factored Torsion Load T_u (k/ft) 1.1 | |
| Factored Shear (strong axis) | Vu _x (kips) | 19.80 | Factored Shear (strong axis) Vu_x (kips) 14.40 | |
| Factored Shear (weak axis) | Vu _v (kips) | 0.00 | Factored Shear (weak axis) Vuv (kips) 0.00 | |
| Factored Moment (strong axis) | Mu _x (k-ft) | 61.88 | Factored Moment (strong axis) Mu _x (k-ft) 45.00 | |
| Additional Moment (strong axis) | +Mu _x (k-ft) | 0.00 | Additional Moment (strong axis) +Mu _x (k-ft) 0.00 | |
| Factored Moment (weak axis) | Mu _y (k-ft) | 0.00 | Factored Moment (weak axis) Mu _y (k-ft) 0.00 | |
| Additional Moment (weak axis) | +Mu _y (k-ft) | 0.00 | Additional Moment (weak axis) +Muy (k-ft) 0.00 | |
| Pe _x (max. Euler value for P-delta) | Pe _x (kips) | 957.88 | Pe _x (max. Euler value for P-delta) Pe _x (kips) 957.88 | |
| Pe _y (max. Euler value for P-delta) | Pe _y (kips) | 124.28 | Pe _y (max. Euler value for P-delta) Pe _y (kips) 124.28 | |
| Moment Magnification (strong) | B1 _x | 1.000 | Moment Magnification (strong) B1 _x 1.000 | |
| Moment Magnification (weak) | B1 _y | 1.002 | Moment Magnification (weak) B1y 1.002 | |
| %Axial+%Moment+(%Shear+%Torsio | n) ² ≤ 1.0 | 0.939 | O.K. %Axial+%Moment+(%Shear+%Torsion) ² < 1.0 0.718 | 0.к |
| Interaction If $Pu/\varphi Pn \ge 0.2$, then P | u/φPn + 8/9(| Mu _v / φ Mn | $+ Mu_v / \varphi Mn_v) \le 1.0$ * If Torsion is >0, then add: | ī |
| Equations: If $Pu/\varphi Pn < 0.2$, then P | | | | |
| i weak | | <u>x</u> +x | | |
| y axis | | | Deflection | |
| | | | Deflection Bending L/240 L/240 0.625 | • |
| strong | Wide Flang | e Member | - | 0.К |
| | designed fo | | Deflection Bending L/360 L/360 0.417 | |
| x x | and Inelasti | | vs. calculated Defl. (live load) 5wL ⁴ /384El 0.362 | о.к |
| | | | ** If wind is causing bending, mult. w by 0.7, IBC 1604.3 | |
| | | | | |
| <u> </u> | | | | |



c

TDI Associates, Inc.

Architects • Engineers • Planners


Job: Stratton Residence-Fox Point Project No.: 13-159 Date: May 4, 2013 Sheet_____of_

W 8 x 21 -Wide Flange Section Designation B-2 50,000 psi, Elastic Yield Stress

LRFD, 3rd Edition

| Beam/Column Length (strong) | 11'9" | | Properties from Section Designa | ted, include | LTB | |
|--|-------------------------|-----------------------------------|---|--|-----------|------------|
| (k) _x length factor adjustment | 1.0 | | $\lambda c_{x} = kL_{x}/r_{x}^{*}(F_{y}/\pi^{2}E)$ | \C _X | 0.534 | - |
| Unbraced Length of Comp. Flange | 1.34 | feet | lf ∖c _x <1.5, Fcr _x = (0.658 ^{∧cv2}) *Fy | Fcr _x | 44.38 | |
| Beam/Column Length (weak) | 11'9" | .i | lf ∧c _x >1.5, Fcr _x = (0.877/∧c ⁻) *Fy | Fcrx | 0.00 | |
| (k) _v length factor adjustment | 1.0 | | | | | |
| | | | $\lambda c_y = kL_y/r_y^*(F_y/\pi^{-*}E)$ | λc _v | 1.479 | |
| Axial Load 1, and type (kips) | 0.1 | DL | If $\lambda c_{y} < 1.5$, Fcr _y = (0.658 $^{\wedge c^{*2}}$) *Fy | , Fcr _v | 20.01 | |
| Axial Load 2, and type (kips) | 0.1 | LL | lf ∧c _v >1.5, Fcr _v = (0.877/∧c ²) *Fy | Fcrv | 0.00 | |
| Transverse Load 1, strong (#/LF) | 720 | DL | y , , , , , , , | y | 0.00 | |
| Transverse Load 2, strong (#/LF) | 1440 | | Capacity for Axial Compression | arphiPn (kips) | 104.79 | 0.К |
| Transverse Load 1, weak (#/LF) | 0 | WL | Capacity for Moment (strong axis) | φMn_x (k-ft) | 76.50 | 0.K |
| Transverse Load 2, weak (#/LF) | 0 | - | Capacity for Moment (weak axis) | φMn_v (k-ft) | 21.34 | 0.K |
| Torsion Load 1, and type (#/LF) | 500 | DL | Capacity for Shear | φ Vn (k-ft) | 55.89 | 0.K |
| Torsion Load 2, and type (#/LF) | 500 | | Capacity for Torsion | φ Tn (k-ft) φ Tn (k-ft) | 342.00 | 0.K |
| | 000 | | objectly for Torsion | φm(khy | 342.00 | 0.6 |
| Calculate Factored Load Case 1: 1.2 | | + 0.8WL | Calculate Factored Load Case 2: | 1.2DL + 1.0L | _L + 1.6W | /L |
| Factored Axial Load | P _u (kips) | 0.28 | Factored Axial Load | P _u (kips) | 0.22 | - |
| Factored Transverse Load (strong) | w _u (k/ft) | 3.168 | Factored Transverse Load (strong) | w _u (k/ft) | 2.304 | |
| Factored Transverse Load (weak) | w _u (k/ft) | 0 | Factored Transverse Load (weak) | w _u (k/ft) | 0 | |
| Factored Torsion Load | T _u (k/ft) | 1.4 | Factored Torsion Load | T _u (k/ft) | 1.1 | |
| Factored Shear (strong axis) | Vu _x (kips) | 18.61 | Factored Shear (strong axis) | Vu _x (kips) | 13.54 | |
| Factored Shear (weak axis) | Vu _y (kips) | 0.00 | Factored Shear (weak axis) | Vu _y (kips) | 0.00 | |
| Factored Moment (strong axis) | Mu _x (k-ft) | 54.67 | Factored Moment (strong axis) | Mu _x (k-ft) | 39.76 | |
| Additional Moment (strong axis) | +Mu _x (k-ft) | 0.00 | Additional Moment (strong axis) | +Mu _x (k-ft) | 0.00 | |
| Factored Moment (weak axis) | Mu _y (k-ft) | 0.00 | Factored Moment (weak axis) | Mu _y (k-ft) | 0.00 | |
| Additional Moment (weak axis) | +Mu _y (k-ft) | 0.00 | Additional Moment (weak axis) | +Mu _y (k-ft) | 0.00 | |
| Pe _x (max. Euler value for P-delta) | Pe _x (kips) | 1084.06 | Pe_x (max. Euler value for P-delta) | Pe _x (kips) | 1084.06 | |
| Pe _y (max. Euler value for P-delta) | Pe _y (kips) | 140.65 | Pey (max. Euler value for P-delta) | Pe _y (kips) | 140.65 | |
| Moment Magnification (strong) | B1 _x | 1.000 | Moment Magnification (strong) | B1 _x | 1.000 | |
| Moment Magnification (weak) | B1 _y | 1.002 | Moment Magnification (weak) | B1 _y | 1.002 | |
| %Axial+%Moment+(%Shear+%Torsio | n) ² ≤ 1.0 | 0.830 | O.K. %Axial+%Moment+(%Shear+%Tors | sion) ² <u><</u> 1.0 | 0.635 | О.К. |
| Interaction If $Pu/\rho Pn \ge 0.2$, then P | u/φPn + 8/9(| Mu _x /φMn _y | $(+ Mu_y/\varphi Mn_y) \le 1.0$ * If Torsion is | >0, then add: | | 1 |
| Equations: If $Pu/\varphi Pn < 0.2$, then Pr | u/(2φPn) + N | lu _x /φMn _x | | | | |
| y weak y axis | | | Deflection | | - | |
| | | | Deflection Deflection Bending L/240 | | 0 500 | - |
| strong | Wide Flang | a Mambar | | L/240 5wL ⁴ /384EI | 0.588 | <u>م</u> ۲ |
| | - | | | | 0.424 | О.К. |
| $\overline{\mathbf{x}}$ | designed fo | | Deflection Bending L/360 | L/360 5wL ⁴ /384EI | 0.392 | <u>ہ</u> |
| | and Inelasti | | vs. calculated Defl. (live load) ** If wind is causing bending, mult. | | 0.283 | 0.К. |
| | | | ii wind is causing bending, mult. | w dy 0.7, IBC | 1604.3 | |
| y | | | | | | |

Designer reserves all copyrights to these calculations which are not to be reproduced, copied, or assigned to any third party in any form or manner without first obtaining the expressed written permission of TDI Associates, Inc



Architects • Engineers • Planners


Job: Stratton Residence-Fox Point Project No.: 13-159 Date: May 4, 2013 Sheet____of_

W 8 x 21 -Wide Flange Section Designation B-3 50,000

50,000 psi, Elastic Yield Stress LRFD, 3rd Edition

| 1.0 1.34 12'0" 1.0 0.1 0.1 | feet | $\frac{1}{2} \frac{1}{2} \frac{1}$ | ∖c _x Fcr _x Fcr _x | 0.545 44.15 0.00 | - |
|---|---|--|---|--|--|
| 12'0" 1.0 0.1 | .i | If λc_x >1.5, Fcr _x = (0.877/ λc^c) *Fy | | | |
| 1.0 0.1 | DL | | Fcr _x | 0.00 | |
| 0.1 | DL | $\wedge \mathbf{c_v} = kL_v/r_v^*(F_v/\pi^{-*}E)$ | | | |
| | DL | $\lambda c_v = kL_v/r_v^*(F_v/\pi^{-*}E)$ | | | |
| | DL | | λ c_y | 1.511 | |
| 0.1 | | If $\lambda c_{\gamma} < 1.5$, Fcr _y = (0.658 ^{$\wedge c^{-2}$}) *Fy | Fcrv | 0.00 | |
| | LL | If $\lambda c_y > 1.5$, Fcr _y = (0.877/ λc^2) *Fy | Fcr _v | 19.22 | |
| 720 | DL | , , , , , , , , | y | | |
| | | Capacity for Axial Compression | φPn (kips) | 100.63 | 0.К |
| 0 | WL | | | | 0.К |
| 0 | - | · · · · · | | | 0.K |
| | DL | · · · · · | , | | 0.K |
| | | | | | 0.K |
| | | Suparity for Foreign | ý m (n nj | 042.00 | 0.1 |
| | | Calculate Factored Load Case 2: | | L + 1.6W | 'L |
| | 0.28 | Factored Axial Load | P _u (kips) | 0.22 | - |
| | | | - | 2.304 | |
| | | | | 0 | |
| T _u (k/ft) | 1.4 | Factored Torsion Load | T _u (k/ft) | 1.1 | |
| Vu _x (kips) | 19.01 | Factored Shear (strong axis) | Vu _x (kips) | 13.82 | |
| Vu _y (kips) | 0.00 | Factored Shear (weak axis) | Vu _v (kips) | 0.00 | |
| Mu _x (k-ft) | 57.02 | Factored Moment (strong axis) | Mu _x (k-ft) | 41.47 | |
| +Mu _x (k-ft) | 0.00 | Additional Moment (strong axis) | +Mu _x (k-ft) | 0.00 | |
| Mu _y (k-ft) | 0.00 | Factored Moment (weak axis) | Mu _y (k-ft) | 0.00 | |
| +Mu _y (k-ft) | 0.00 | Additional Moment (weak axis) | +Mu _y (k-ft) | 0.00 | |
| Pe _x (kips) | 1039.36 | Pe _x (max. Euler value for P-delta) | Pe _x (kips) | 1039.36 | |
| Pe _v (kips) | 134.86 | Pev (max. Euler value for P-delta) | | 134.86 | |
| Β1 _x | 1.000 | Moment Magnification (strong) | | 1.000 | |
| B1 _y | 1.002 | Moment Magnification (weak) | B1 _y | 1.002 | |
| ר) ² <u><</u> 1.0 | 0.865 | O.K. %Axial+%Moment+(%Shear+%Tors | sion) ² <_1.0 | 0.662 | 0.К. |
| ı/φPn + 8/9(i | Mu _x /∉Mn _x | $+ Mu_v/\varphi Mn_v) \le 1.0$ * If Torsion is | >0, then add: | | 1 |
| $1/(2\varphi Pn) + N$ | luÿMn _v - | | | | |
| | <u> </u> | <u> </u> | | <u>-</u> | J |
| | | Deflection | | | |
| | | | L/240 | 0.600 | - |
| Wide Flange | e Member | _ | - | 0.461 | 0.К. |
| - | | Deflection Bending L/360 | L/360 | 0.400 | |
| | | | | | о.к. |
| | | | | | |
| | | | | - | |
| | 0 500 500 2DL + 1.6LL P _u (kips) w _u (k/ft) T _u (k/ft) Vu _x (kips) Vu _y (kips) Mu _x (k-ft) +Mu _y (k-ft) +Mu _y (k-ft) Pe _x (kips) Pe _y (kips) B1 _x B1 _y n) ² ≤ 1.0 $1/\varphi$ Pn + 8/9(int) /(2\varphi Pn) + N | 0 WL 0 - 500 DL 500 LL 20L + 1.6LL + 0.8WL P _u (kips) 0.28 w _u (k/ft) 3.168 w _u (k/ft) 0 T _u (k/ft) 1.4 Vu _x (kips) 19.01 Vu _y (kips) 0.00 Mu _x (k-ft) 57.02 +Mu _x (k-ft) 0.00 Mu _y (k-ft) 0.00 Mu _y (k-ft) 0.00 Pe _x (kips) 1039.36 Pe _y (kips) 134.86 B1 _x 1.000 B1 _y 1.002 m) ² ≤ 1.0 0.865 1/φPn + 8/9(Mu _x /φMn _x + | 0WLCapacity for Moment (strong axis)0-Capacity for Moment (weak axis)500DLCapacity for Shear500LLCapacity for TorsionCDL + 1.6LL + 0.8WLPu (kips)0.28Pu (kips)0.28Wu (k/ft)3.168Factored Axial LoadWu (k/ft)1.4Factored Transverse Load (strong)Wu (k/ft)1.4Factored Shear (strong axis)Vuy (kips)0.00Factored Shear (weak axis)Mux (k-ft)57.02Factored Moment (strong axis)Mux (k-ft)0.00Factored Moment (strong axis)Muy (k-ft)0.00Factored Moment (strong axis)Muy (k-ft)0.00Factored Moment (weak axis)Muy (k-ft)0.00Factored Moment (weak axis)Muy (k-ft)0.00Additional Moment (weak axis)Muy (k-ft)0.00Additional Moment (weak axis)Pex (kips)1039.36Pex (kips)1039.36Pex (kips)1039.36Pex (kips)0.865O.K.%Axial+%Moment+(%Shear+%Tors)U/2 Pn + 8/9(Mux/φMnx + Muy/φMny) ≤ 1.0* If Torsion isU/2 Pn + 8/9(Mux/φMnx + Muy/φMny ≤ 1.0* If Torsion isU/2 pPn) + Mux/φMnx + Muy/φMny ≤ 1.0* If Torsion isDeflectionBending L/240vs. calculated Defl. (total load)Deflection Bending L/260vs. calculated Defl. (live load) | 0WLCapacity for Moment (strong axis) φ Mn _x (k-ft)0-Capacity for Moment (weak axis) φ Mn _y (k-ft)500DLCapacity for Shear φ Vn (k-ft)500LLCapacity for Torsion φ Tn (k-ft)Pu(kips)0.28Calculate Factored Load Case 2: 1.2DL + 1.0LPu(kips)0.28Factored Axial LoadPuWu (k/ft)3.168Factored Transverse Load (strong)wu (k/ft)Tu(k/ft)1.4Factored Torsion LoadTuVux (kips)19.01Factored Shear (strong axis)Vux (kips)Vuy (kips)0.00Factored Moment (strong axis)Vuu (kips)Mux (k-ft)57.02Factored Moment (strong axis)Mux (k-ft)Muy (k-ft)0.00Factored Moment (strong axis)Mux (k-ft)Muy (k-ft)0.00Factored Moment (weak axis)Muy (k-ft)Muy (k-ft)0.00Factored Moment (weak axis)Muy (k-ft)Muy (k-ft)0.00Factored Moment (weak axis)Muy (k-ft)Pex (kips)1039.36Pex (max. Euler value for P-delta)Pex (kips)B1x1.000Moment Magnification (strong)B1xB1y1.002Moment Magnification (weak)B1yn)²≤ 1.00.865O.K.%Axial+%Moment+(%Shear+%Torsion)²≤1.0Wide Flange MemberDeflection Bending L/240L/240wide Flange MemberDeflection Bending L/240L/240wide Flange MemberDeflection Bending L/260L/360 | 0WLCapacity for Moment (strong axis) $φ$ Mn _x (k-ft)76.500-Capacity for Moment (weak axis) $φ$ Mn _y (k-ft)21.34500DLCapacity for Shear $φ$ Vn (k-ft)55.89500LLCapacity for Torsion $φ$ Tn (k-ft)342.002DL + 1.6LL + 0.8WLCapacity for Torsion $φ$ Tn (k-ft)342.00 P_u (kips)0.28Capacity for Torsion $φ$ Tn (k-ft)342.00 w_u (k/ft)3.168Factored Load Case 2: 1.2DL + 1.0LL + 1.6W w_u (k/ft)0Factored Transverse Load (strong) w_u (k/ft)0.22 w_u (k/ft)1.4Factored Torsion LoadTu (k/ft)1.1Vu _x (kips)19.01Factored Shear (strong axis)Vu _x (kips)13.82Vu _y (kips)0.00Factored Moment (strong axis)Vu _x (k/ft)0.00Mu _x (k-ft)0.00Factored Moment (strong axis)Mu _x (k-ft)0.00Mu _y (k-ft)0.00Factored Moment (weak axis)Mu _y (k-ft)0.00Mu _y (k-ft)0.00Factored Moment (weak axis)Mu _y (k-ft)0.00Mu _y (k-ft)0.00Additional Moment (weak axis)Mu _y (k-ft)0.00Mu _y (k-ft)0.00Additional Moment (weak axis)Mu _y (k-ft)0.00Mu _y (k-ft)0.00Additional Moment (weak axis)Mu _y (k-ft)0.00Pe _x (kips)134.86Pe _y (max. Euler value for P-delta)Pe _x (kips)134.86B1 _x 1.000Moment Magnification (str |

Designer reserves all copyrights to these calculations which are not to be reproduced, copied, or assigned to any third party in any form or manner without first obtaining the expressed written permission of TDI Associates, Inc




Architects • Engineers • Planners

Job: Stratton Residence-Fox Point Project No.: 13-159 Date: May 4, 2013 Sheet____of_

W 8 x 24 - Wide Flange Section Designation B-4 5

50,000 psi, Elastic Yield Stress LRFD, 3rd Edition

| Beam/Column Length (strong) | 16'4" | | Properties from Section Designa | | | _ |
|--|---------------------------------|------------------------------------|---|----------------------------------|----------|----------|
| (k) _x length factor adjustment | 1.0 | | $\mathbf{A}\mathbf{c}_{\mathbf{x}} = \mathbf{k}\mathbf{L}_{\mathbf{x}}/\mathbf{r}_{\mathbf{x}}^{*}(\mathbf{F}_{\mathbf{y}}/\pi^{**}\mathbf{E})$ | ∧c _x | 0.757 | |
| Unbraced Length of Comp. Flange | 1.34 | feet | If $\lambda c_x < 1.5$, Fcr _x = (0.658 $^{\circ \circ \circ}$) *Fy | Fcr _x | 39.33 | |
| Beam/Column Length (weak) | 16'4" | | If λc_x >1.5, Fcr _x = (0.877/ λc^c) *Fy | Fcr _x | 0.00 | |
| (k) _y length factor adjustment | 1.0 | | | | | |
| | | | $\lambda c_y = kL_y/r_y^*(F_y/\pi^{-*}E)$ | λ c_y | 1.609 | |
| Axial Load 1, and type (kips) | 0.1 | DL | lf λc_y <1.5, Fcr _y = (0.658 $^{\wedge \sigma' 2}$) *Fy | Fcry | 0.00 | |
| Axial Load 2, and type (kips) | 0.1 | LL | If λc_y >1.5, Fcr _y = (0.877/ λc^2) *Fy | Fcry | 16.94 | |
| Transverse Load 1, strong (#/LF) Transverse Load 2, strong (#/LF) | 200 400 | DL LL | Capacity for Axial Compression | arphiPn (kips) | 101.93 | 0.K. |
| Transverse Load 1, weak (#/LF) | 0 | WL | Capacity for Moment (strong axis) | φ Mn _x (k-ft) | 86.63 | О.К. |
| Transverse Load 2, weak (#/LF) | 0 | - | Capacity for Moment (weak axis) | φMn _v (k-ft) | 32.14 | О.К. |
| Torsion Load 1, and type (#/LF) | 250 | DL | Capacity for Shear | φ Vn (k-ft) | 52.46 | 0.K. |
| Torsion Load 2, and type (#/LF) | 250 | LL | Capacity for Torsion | arphiTn (k-ft) | 582.75 | 0.К. |
| Calculate Factored Load Case 1: 1. | 2DI + 16I I | ± 0.8WI | Calculate Factored Load Case 2: | 1 201 + 1 01 | 1 ± 1 6M | /1 |
| Factored Axial Load | P _u (kips) | 0.28 | Factored Axial Load | P _u (kips) | 0.22 | <u>_</u> |
| Factored Transverse Load (strong) | w _u (k/ft) | 0.88 | Factored Transverse Load (strong) | w _u (k/ft) | 0.64 | |
| Factored Transverse Load (weak) | w _u (k/ft) | 0 | Factored Transverse Load (weak) | w _u (k/ft) | 0 | |
| Factored Torsion Load | T _u (k/ft) | 0.7 | Factored Torsion Load | T _u (k/ft) | 0.55 | |
| Factored Shear (strong axis) | Vu _x (kips) | 7.19 | Factored Shear (strong axis) | Vu _x (kips) | 5.23 | |
| Factored Shear (weak axis) | Vu _v (kips) | 0.00 | Factored Shear (weak axis) | Vu _v (kips) | 0.00 | |
| Factored Moment (strong axis) | Mu _x (k-ft) | 29.35 | Factored Moment (strong axis) | M⊔ _x (k-ft) | 21.34 | |
| Additional Moment (strong axis) | +Mu _x (k-ft) | 0.00 | Additional Moment (strong axis) | +Mu _x (k-ft) | 0.00 | |
| Factored Moment (weak axis) | Mu _v (k-ft) | 0.00 | Factored Moment (weak axis) | Mu _v (k-ft) | 0.00 | |
| Additional Moment (weak axis) | +Mu _y (k-ft) | 0.00 | Additional Moment (weak axis) | +Mu _y (k-ft) | 0.00 | |
| Pe _x (max. Euler value for P-delta) | Pe _x (kips) | 616.16 | Pe _x (max. Euler value for P-delta) | Pe _x (kips) | 616.16 | |
| Pe _y (max. Euler value for P-delta) | Pe _y (kips) | 136.34 | Pe _y (max. Euler value for P-delta) | Pe _v (kips) | 136.34 | |
| Moment Magnification (strong) | B1 _x | 1.000 | Moment Magnification (strong) | Β1 _x | 1.000 | |
| Moment Magnification (weak) | B1 _y | 1.002 | Moment Magnification (weak) | B1 _y | 1.002 | |
| %Axial+%Moment+(%Shear+%Torsio | n) ² <u><</u> 1.0 | 0.359 | O.K. %Axial+%Moment+(%Shear+%Tor | sion) ² <1.0 | 0.267 | о.к. |
| Interaction If $Pu/\varphi Pn \ge 0.2$, then P | u/ $arphi$ Pn + 8/9(| Mu _x /∉Mn, | $_{\rm x}$ + Mu _y / φ Mn _y) \leq 1.0 * If Torsion is | >0, then add: | | 1 |
| Equations: If $Pu/\varphi Pn < 0.2$, then P | u/(2 φ Pn) + N | ∕lu _x /∉Mn _x | + $Mu_y/\varphi Mn_y \le 1.0$ (Vu/ φ Vn + T | u/ $arphi$ Tn) ² | | |
| y weak y axis | | | . | | · | - |
| | | | Deflection | | | - |
| | | | Deflection Bending L/240 | L/240 | 0.817 | |
| axis | Wide Flang | | . , | 5wL ⁴ /384EI | 0.401 | 0.K. |
| $\frac{1}{x}$ | designed fo | | Deflection Bending L/360 | L/360 | 0.544 | . |
| | and Inelasti | CLIB | vs. calculated Defl. (live load) | 5wL ⁴ /384El | 0.267 | 0.К. |
| | | | ** If wind is causing bending, mult. | w by 0.7, IBC | ; 1604.3 | |
| y | | | | | | |



Architects • Engineers • Planners

Job: Stratton Residence-Fox Point Project No.: 13-159

Date: May 4, 2013 Sheet____of____

| | ent Factors for Analysis | r Environmental Lo | bads | | | | | | |
|--|---|--|---|---|--|--|--|--|--|
| Exposure | | Vind Speed of 90 reduction or magit 250 | | | 39.00 | | | | |
| | | | utilities Description | | | | | | |
| <u>Main For</u> | | <u>ystem:</u> Low Rise B tal Loada | ullaing Provisio | | ـــ | | | | |
| Horizontal Loads Vertical Loads End Zone Interior Zone End Zone Interior Zone | | | | | | | | | |
| Wall | 14,4 | 11.5 | Leeward | -8.8 | | | | | |
| Roof | 9.9 | 7.9 | Windward | -0.0 -5.6 | -7.5 4.8 | | | | |
| | 1 2.2 | 1 7.2 | Overhang | -5.6 -5.1 | -5.8 | | | | |
| Height a | nd Exposure A | djustment Coffici | e <u>1.00</u> | | | | | | |
| | Horizontal | Loads * Coeff. | | Vertical Loads * | Coeff. | | | | |
| End Zone Interior Zone End Zone Interior Zor | | | | | | | | | |
| Wall | 14.4 | 11.5 | Leeward | -8.8 | -7.5 | | | | |
| Roof | 9.9 | 7.9 | Windward | -5.6 | 4.8 | | | | |
| | - | - | Overhang | -5.1 | -5.8 | | | | |
| • <u>Components and Cladding</u> : Low Rise Building Provisions | | | | | | | | | |
| <u>Componer</u> | | - | ng Provisions | | | | | | |
| | Wa | ĂĨ. | ng Provisions | Roof | | | | | |
| Area | Wa Dir. Pres. | ll Uplift | Area | Dir. Pres. | Uplift | | | | |
| Area 10 | Wa Dir. Pres. 14.6 | ll Uplift -15.8 | Area 10 | Dir. Pres. 13.3 | -14.6 | | | | |
| <u>Area</u> 10 20 | Wa Dir. Pres. 14.6 13.9 | Uplift -15.8 -15.2 | Area 10 20 | Dir. Pres. 13.3 13.0 | -14.6 -13.8 | | | | |
| <u>Area</u> 10 20 50 | Wa Dir. Pres. 14.6 13.9 13.0 | Uplift -15.8 -15.2 -14.3 | Area 10 20 50 | Dir. Pres. 13.3 13.0 12.5 | -14.6 -13.8 -12.8 | | | | |
| <u>Area</u> 10 20 | Wa Dir. Pres. 14.6 13.9 | Uplift -15.8 -15.2 | Area 10 20 | Dir. Pres. 13.3 13.0 | -14.6 -13.8 | | | | |
| Area 10 20 50 100 | Wa Dir. Pres. 14.6 13.9 13.0 12.4 | Uplift -15.8 -15.2 -14.3 | Area 10 20 50 100 | Dir. Pres. 13.3 13.0 12.5 | -14.6 -13.8 -12.8 | | | | |
| Area 10 20 50 100 | Wa Dir. Pres. 14.6 13.9 13.0 12.4 nd Exposure Ac | Uplift -15.8 -15.2 -14.3 -13.5 | Area 10 20 50 100 | Dir. Pres. 13.3 13.0 12.5 | -14.6 -13.8 -12.8 -12.1 | | | | |
| Area 10 20 50 100 | Wa Dir. Pres. 14.6 13.9 13.0 12.4 nd Exposure Ac | Uplift -15.8 -15.2 -14.3 -13.5 djustment Coffici | Area 10 20 50 100 | Dir. Pres. 13.3 13.0 12.5 12.1 | -14.6 -13.8 -12.8 -12.1 | | | | |
| <u>Area</u> 10 20 50 100 Height ar | Wa Dir. Pres. 14.6 13.9 13.0 12.4 nd Exposure Ac | Uplift -15.8 -15.2 -14.3 -13.5 djustment Coffici * Coeff. | Area 10 20 50 100 | Dir. Pres. 13.3 13.0 12.5 12.1 Roof * Coet | -14.6 -13.8 -12.8 -12.1 | | | | |
| Area 10 20 50 100 Height ar Area | Wa Dir. Pres. 14.6 13.9 13.0 12.4 nd Exposure Ac Wall ³ Dir. Pres. | Uplift -15.8 -15.2 -14.3 -13.5 djustment Coffici * Coeff. Uplift | Area 10 20 50 100 1.00 Area | Dir. Pres. 13.3 13.0 12.5 12.1 Roof * Coet Dir. Pres. | -14.6 -13.8 -12.8 -12.1 ff. Uplift | | | | |
| Area 10 20 50 100 Height ar <u>Area</u> 10 | Wa Dir. Pres. 14.6 13.9 13.0 12.4 nd Exposure Ac Wall ³ Dir. Pres. 14.6 | Uplift -15.8 -15.2 -14.3 -13.5 djustment Coffici * Coeff. Uplift -15.8 | Area 10 20 50 100 1.00 Area 10 | Dir. Pres. 13.3 13.0 12.5 12.1 Roof * Coet Dir. Pres. 13.3 | -14.6 -13.8 -12.8 -12.1 ff. Uplift -14.6 | | | | |



:


2

TDI Associates, Inc.

Architects • Engineers • Planners

Job: Stratton Residence-Fox Point Project No.: 13-159 Date: May 4, 2013 Sheet____of___


| hear wall | floor | grid | wind | trib. | height | no, of | shear force | shear force | total shear force |
|-----------|-------|----------|-------|-------|--------|---------|-------------|-------------|-------------------|
| ype | | - | force | span | _ | stories | | on wall | on wall |
| | | | | | | | | | |
| A | 1ST | END | 14.4 | 19.25 | 9.50 | 1 | 2,633.40 | | |
| Α | 1ST | END | 11.9 | 19.25 | 0.00 | 1 | 0.00 | 2,633.40 | 6,209.96 |
| В | 1ST | INTERIOR | 11.5 | 19.25 | 9.50 | 1 | 2,103.06 | | - |
| В | 1ST | INTERIOR | 7.9 | 19.25 | 0.00 | 1 | 0.00 | 2,103.06 | 4,626.83 |
| С | 1ST | END | 14.4 | | | | 2,633.40 | , | ., |
| С | 1ST | END | 11.9 | | | | 0.00 | 2,633.40 | 6,209.96 |
| D | 1ST | END | 14.4 | | | | 2,701.80 | _, | -, |
| D | 1ST | END | 11.9 | | | | 0.00 | 2,701.80 | 6,307.16 |
| Ē | 1ST | INTERIOR | 11.5 | | | | 2,157.69 | 2,701.00 | 0,007.10 |
| Ē | 1ST | INTERIOR | 7.9 | | | | 0.00 | 2,157.69 | 4,704.45 |
| F | 1ST | END | 14.4 | | | | 2,701.80 | 2,107.00 | 07.70 |
| , F | 1ST | END | 11.9 | | | | 0.00 | 2,701.80 | 6,307.16 |
| • | | | | 10.00 | 0.00 | • | 0.00 | 2,701.00 | 0,007.10 |
| | | | | | | | | | |
| G | 2ND | END | 14.4 | | | | 1,108.80 | | } |
| G | 2ND | END | 11.9 | 19.25 | 10.50 | 1 | 2,467.76 | 3,576.56 | } |
| н | 2ND | INTERIOR | 11.5 | 19.25 | 4.00 | 1 · | 885.50 | | |
| н | 2ND | INTERIOR | 7.9 | 19.25 | 10.50 | 1 | 1,638.26 | 2,523.76 | |
| I | 2ND | END | 14.4 | 19.25 | 4.00 | 1 | 1,108.80 | | |
| Ι | 2ND | END | 11.9 | 19.25 | 10.50 | 1 | 2,467.76 | 3,576.56 | |
| J | 2ND | END | 14.4 | 19.75 | | 1 | 1,137.60 | , | |
| J | 2ND | END | 11.9 | 19.75 | 10.50 | 1 | 2,467.76 | 3,605.36 | |
| к | 2ND | INTERIOR | 11.5 | 19.75 | | | 908.50 | , . | |
| к | 2ND | INTERIOR | 7.9 | 19.75 | | | 1,638.26 | 2,546.76 | |
| L | 2ND | END | 14.4 | 19.75 | | | 1,137.60 | _, | |
| Ĺ | 2ND | END | 11.9 | 19.75 | | | 2,467.76 | 3,605.36 | |
| - | | | | | 10.00 | • | | 0,000.00 | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | I | | I | | . 1 | | I I | I | 1 |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |



Architects • Engineers • Planners

Job: Stratton Residence-Fox Point Project No.: 13-159 Date: May 4, 2013 Sheet_____of_

Perforated Shear Wall Worksheet SW-#A 1ST Floor



 $b_0 = b1 + b2 + b3$

 $b_{fh} = b - b_o$

ho = height, maximum, for openings

V = Shear applied to Wall

- v = Unit Shear (from Piers * Perforation Factor)
- T = Tension Force for Holddown to System Below
- C = Compression Force to System Below

** Diagram is for illustrative purposes only. See Elevation Sheets for shear wall being examined.

| | h _o / h | | | | | | | | | |
|---------------------|--------------------|----------------------|----------------|-------|---------------|----------------|---------------------------------------|----------------|----------------|-----------|
| b _{th} / b | 0.1 | 0.2 | 0.3 | 0.4 | 0.5 | 0.6 | 0.7 | 0.8 | 0.9 | 1.0 |
| 0.0 | 1.000 | 1.000 | 1.000 | 0.802 | 0.670 | 0.602 | 0.480 | 0.420 | 0.358 | 0.330 |
| 0.1 | 1.000 | 1.000 | 1.000 | 0.814 | 0.690 | 0.626 | 0.510 | 0.450 | 0.388 | 0.360 |
| 0.2 | 1.000 | 1.000 | 1.000 | 0.826 | 0.710 | 0.650 | 0.538 | 0.472 | 0.408 | 0.380 |
| 0.3 | 1.000 | 1.000 | 1.000 | 0.844 | 0.740 | 0.680 | 0.570 | 0.510 | 0.448 | 0.420 |
| 0.4 | 1.000 | 1.000 | 1.000 | 0.862 | 0.770 | 0.714 | 0.610 | 0.550 | 0.482 | 0.450 |
| 0.5 | 1.000 | 1.000 | 1.000 | 0.880 | 0.800 | 0.748 | 0.650 | 0.590 | 0.528 | 0.500 |
| 0.6 | 1.000 | 1.000 | 1.000 | 0.898 | 0.830 | 0.782 | 0.694 | 0.646 | 0.588 | 0.560 |
| 0.7 | 1.000 | 1.000 | 1.000 | 0.922 | 0.870 | 0.830 | 0.754 | 0.706 | 0.654 | 0.630 |
| 0.8 | 1.000 | 1.000 | 1.000 | 0.946 | 0.910 | 0.878 | 0.818 | 0.782 | 0.734 | 0.710 |
| 0.9 | 1.000 | 1.000 | 1.000 | 0.970 | 0.950 | 0.934 | 0.902 | 0.878 | 0.846 | 0.830 |
| 1.0 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 |
| Wall Input Valu | les | _ | | | Force Input V | alue | | | | |
| Height of Wall | | h (ft) | 9 | | Shear Force a | pplied to Wall | V (lbs) | 6210 | _ | |
| Maximum Open | ning Height | h _o (ft) | 7 | | | | | | | |
| Width of Wall (te | otal) | b (ft) | 59.25 | | | | | | | |
| Sum of Wall Op | ening Width | b _o (ft) | AAA | | Unit Shear Ca | alculation | | | _ | |
| | | | | | Remaining Pie | er Length * Co | b _{fh} ⁺ C _o (ft) | #VALUE! | _ | |
| | | | | 75 | Unit Shear, V | / Pier length | v (lb/ft) | #VALUE! | | |
| Calculate Perfo | pration Reduct | tion | | | | | | | | |
| Max Opening H | gt / Wall Hgt | h/h₀ | 0.78 | | Side 1: Sheat | hing: 1/2" OS | В | | _ | |
| Shear Wall Ren | naining (piers) | b _{íh} (ft) | #VALUE! | | Length | | L (ft) | #VALUE! | - | |
| Pier length / wal | ll length | b _{fh} / b | #VALUE! | | Unit Shear Ca | pacity | v (lb/ft) | 260 | 8d Nail @ 6/1: | 2 Pattern |
| Perforation facto | or | C ₀ (ft) | #VALUE! | | | | | | | |

Side 2: Sheating 1/2" GYP

Unit Shear Capacity

Total Force Capacity

Equivalent Unit Shear

Length

C₋ Table

*Perforation Factor is from Double Intertoplation of $\boldsymbol{C_o}$ Table

| Hold-down Force Required | | |
|---------------------------|---------|--------|
| Length between Hold-downs | L (ft) | 59 |
| Tension Force | T (lbs) | 947.29 |

IBC Code: Can sum the sheathing values per side, but the summation of the two must be less that twice the lowest unit shear of the two materials.

Gypsum is screwed at 16" OC at edge joint along horizontal butt joints

#VALUE!

80

#VALUE!

#VALUE!

#6Screw @ 8/12 pattern

#VALUE! #VALUE!

#VALUE!


#VALUE!

L (ft)

v (ib/ft)

V (lbs)


v (lb/ft)



Architects • Engineers • Planners

Job: Stratton Residence-Fox Point Project No.: 13-159 Date: May 4, 2013 Sheet_____of__

Perforated Shear Wall Worksheet SW-#B-1ST FLR



 $b_0 = b1 + b2 + b3$

 $b_{fh} = b - b_o$

ho = height, maximum, for openings


V = Shear applied to Wall

- v = Unit Shear (from Piers * Perforation Factor)
- T = Tension Force for Holddown to System Below C = Compression Force to System Below

** Diagram is for illustrative purposes only. See Elevation Sheets for shear wall being examined.

| | | | | | C _o Tal | ble | | | | |
|---------------------------------|-------------------|----------------------|------------------------------|-------|--------------------------------|----------------|---------------------------------------|---------------|---------------------|--------------|
| | | | | | h _o /h | | | | | |
| b _{íh} / b | 0.1 | 0.2 | 0.3 | 0.4 | 0.5 | 0.6 | 0.7 | 0.8 | 0.9 | 1.0 |
| 0.0 | 1.000 | 1.000 | 1.000 | 0.802 | 0.670 | 0.602 | 0.480 | 0.420 | 0.358 | 0.330 |
| 0.1 | 1.000 | 1.000 | 1.000 | 0.814 | 0.690 | 0.626 | 0.510 | 0.450 | 0.388 | 0.360 |
| 0.2 | 1.000 | 1.000 | 1.000 | 0.826 | 0.710 | 0.650 | 0.538 | 0.472 | 0.408 | 0.380 |
| 0.3 | 1.000 | 1.000 | 1.000 | 0.844 | 0.740 | 0.680 | 0.570 | 0.510 | 0.448 | 0.420 |
| 0.4 | 1.000 | 1.000 | 1.000 | 0.862 | 0.770 | 0.714 | 0.610 | 0.550 | 0.482 | 0.450 |
| 0.5 | 1.000 | 1.000 | 1.000 | 0.880 | 0.800 | 0.748 | 0.650 | 0.590 | 0.528 | 0.500 |
| 0.6 | 1.000 | 1.000 | 1.000 | 0.898 | 0.830 | 0.782 | 0.694 | 0.646 | 0.588 | 0.560 |
| 0.7 | 1.000 | 1.000 | 1.000 | 0.922 | 0.870 | 0.830 | 0.754 | 0.706 | 0.654 | 0.630 |
| 0.8 | 1.000 | 1.000 | 1.000 | 0.946 | 0.910 | 0.878 | 0.818 | 0.782 | 0.734 | 0.710 |
| 0.9 | 1.000 | 1.000 | 1.000 | 0.970 | 0.950 | 0.934 | 0.902 | 0.878 | 0.846 | 0.830 |
| 1.0 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 |
| Wali input Valı | lies | | | | Force Input V | alue | | | | |
| Height of Wall | | h (ft) | 9 | | Shear Force a | | V (lbs) | 4627 | _ | |
| Maximum Oper | ning Height | h _o (ft) | 7 | | | pp | • (100) | -OLI | | |
| Width of Wall (t | | b (ft) | 59 | | | | | | | |
| Sum of Wall Op | ' | b _o (ft) | 12 | | Unit Shear Ca | alculation | | | | |
| | | | | | Remaining Pie | er Length * Co | b _{fh} * C _o (ft) | 38.34 | _ | |
| | | | | | Unit Shear, V | / Pier length | v (lb/ft) | 120.67 | | |
| Calculate Perfe | oration Reducti | on | | | 8 | - | . , | | | |
| Max Opening H | lgt / Wall Hgt | h / h _o | 0.78 | | Side 1: Sheat | hing: 1/2" Gyp | . Board | | | |
| Shear Wall Ren | maining (piers) | b _{fh} (ft) | 47 | | Length | | L (ft) | 38.34 | | |
| Pier length / wa | li length | b _{th} / b | 0.797 | | Unit Shear Ca | pacity | v (lb/ft) | 80 | #6 Screw @ | 8/12 Pattern |
| Perforation factor | or | C ₀ (ft) | 0.816 | | | | | | | |
| | | | | | - | hing: 1/2" Gyp | . Board | | _ | |
| *Perforation Fac | ctor is from Doul | ble Intertopla | tion of C _o Table | | Length | | L (ft) | 38.34 | | |
| | | | | | Unit Shear Ca | pacity | v (lb/ft) | 80 | #6 Screw @ | 8/12 Pattern |
| Hold-down For | | | | | | | | | | |
| Length between Tension Force | i nolu-uowiis | L (ft) T (lbs) | 58.75 708.82 | | Total Force C Equivalent Ur | | V (lbs) v (lb/ft) | 6135.0 160 | > 4627 > 120.672 | О.К. О.К. |
| | | 1 (103) | 100.02 | | | in onear | | 100 | > 120.072 | U.K. |
| IBC Code: Can | sum the sheath | ing values pe | er side, but | | | | | | | |
| the summation | | | | | Gypsum is s | crewed at 16 | 5" OC at edge | e joint alor | ng horizontal | butt joints |
| lowest unit shea | ar of the two mat | erials. | | | | | | - | - | |
| | | | * | | | | | | | |


Table



Architects • Engineers • Planners

Job: Stratton Residence-Fox Point Project No.: 13-159 Date: May 4, 2013 Sheet_____of____

Perforated Shear Wall Worksheet SW-#C 1ST Floor



 $b_0 = b1 + b2 + b3$

 $b_{fh} = b - b_{o}$

ho = height, maximum, for openings

- V = Shear applied to Wall
- v = Unit Shear (from Piers * Perforation Factor)
- T = Tension Force for Holddown to System Below
- C = Compression Force to System Below

** Diagram is for illustrative purposes only. See Elevation Sheets for shear wall being examined.

IBC Code: Can sum the sheathing values per side, but the summation of the two must be less that twice the


lowest unit shear of the two materials.

| | | | | | h _o /h | | | | | |
|---------------------|------------------|----------------------|-----------------------------------|-------|--|----------------|---------------------------------------|---------------|---------------------|--------------|
| b _{fh} / b | 0.1 | 0.2 | 0.3 | 0.4 | 0.5 | 0.6 | 0.7 | 0.8 | 0.9 | 1.0 |
| 0.0 | 1.000 | 1.000 | 1.000 | 0.802 | 0.670 | 0.602 | 0.480 | 0.420 | 0.358 | 0.330 |
| 0.1 | 1.000 | 1.000 | 1.000 | 0.814 | 0.690 | 0.626 | 0.510 | 0.450 | 0.388 | 0.360 |
| 0.2 | 1.000 | 1.000 | 1.000 | 0.826 | 0.710 | 0.650 | 0.538 | 0.472 | 0.408 | 0.380 |
| 0.3 | 1.000 | 1.000 | 1.000 | 0.844 | 0.740 | 0.680 | 0.570 | 0.510 | 0.448 | 0.420 |
| 0.4 | 1.000 | 1.000 | 1.000 | 0.862 | 0.770 | 0.714 | 0.610 | 0.550 | 0.482 | 0.450 |
| 0.5 | 1.000 | 1.000 | 1.000 | 0.880 | 0.800 | 0.748 | 0.650 | 0.590 | 0.528 | 0.500 |
| 0.6 | 1.000 | 1.000 | 1.000 | 0.898 | 0.830 | 0.782 | 0.694 | 0.646 | 0.588 | 0.560 |
| 0.7 | 1.000 | 1.000 | 1.000 | 0.922 | 0.870 | 0.830 | 0.754 | 0.706 | 0.654 | 0.630 |
| 0.8 | 1.000 | 1.000 | 1.000 | 0.946 | 0.910 | 0.878 | 0.818 | 0.782 | 0.734 | 0.710 |
| 0.9 | 1.000 | 1.000 | 1.000 | 0.970 | 0.950 | 0.934 | 0.902 | 0.878 | 0.846 | 0.830 |
| 1.0 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 |
| Wall Input Valu | IPS | | | | Force Input V | alue | | | | |
| Height of Wall | | h (ft) | 9 | | Shear Force applied to Wall V (lbs) 6210 | | | | _ | |
| Maximum Open | ina Heiaht | h _o (ft) | 7 | | 0.000 | | (100) | GETO | | |
| Width of Wall (t | | b (ft) | 59.25 | | | | | | | |
| Sum of Wall Op | , | b _o (ft) | 33 | | Unit Shear Ca | lculation | | | | |
| | | | | | Remaining Pie | r Length * Co | b _{fh} * C _o (ft) | 16.46 | | |
| | | | | | Unit Shear, V | Pier length | v (lb/ft) | 377.18 | | |
| Calculate Perfo | pration Reducti | on | | | | | | | | |
| Max Opening H | gt / Wall Hgt | h / h _o | 0.78 | | Side 1: Sheat | hing: 1/2" OSI | 3 | | | |
| Shear Wall Ren | naining (piers) | b _{íh} (ft) | 26.25 | | Length | | L (ft) | 16.46 | _ | |
| Pier length / wal | ll length | b _{fh} / b | 0.443 | | Unit Shear Ca | pacity | v (lb/ft) | 380 | 8d Nail @ 4 | /12 Pattern |
| Perforation factor | or | C ₀ (ft) | 0.627 | | | | | | | |
| | | | | | Side 2: Sheat | hing: 1/2" Gyp | - | | _ | |
| *Perforation Fac | tor is from Doul | ble Intertoplat | ion of C_o Table | ! | Length | | L (ft) | 16.46 | | |
| | | | | | Unit Shear Ca | pacity | v (lb/ft) | 80 | #6Screw @ | 8/12 pattern |
| Hold-down For | | | | | T | | | | | |
| i endin netween | Hold-downs | ∟(ft) T (lbs) | 59 947.29 | | Total Force Ca Equivalent Un | | V (lbs) v (lb/ft) | 7573.6 460 | > 6210 < 377.179 | 0.K. 0.K. |

Gypsum is screwed at 16" OC at edge joint along horizontal butt joints

Designer reserves all copyrights to these calculations which are not to be reproduced, copied, or assigned to any third party in any form or manner without first obtaining the expressed written permission of TDI Associated, Inc

C_o Table




. . . .

TDI Associates, Inc.

Architects • Engineers • Planners

Job: Stratton Residence-Fox Point Project No.: 13-159 Date: May 4, 2013 Sheet_____of__

Perforated Shear Wall Worksheet SW-#D-1ST FLR



 $b_0 = b1 + b2 + b3$

 $b_{fh} = b - b_o$

ho = height, maximum, for openings


- V = Shear applied to Wall
- v = Unit Shear (from Piers * Perforation Factor)
- T = Tension Force for Holddown to System Below
- C = Compression Force to System Below

** Diagram is for illustrative purposes only. See Elevation Sheets for shear wall being examined.

| | | | | | 0 0 . a. | 510 | | | | |
|--------------------|-------|-------|-------|-------|--------------------|-------|-------|-------|-------|-------|
| | | | | | h ₀ / h | | | | | |
| b _{th} /b | 0.1 | 65.5 | 0.3 | 0.4 | 0.5 | 0.6 | 0.7 | 0.8 | 0.9 | 1.0 |
| 0.0 | 1.000 | 1.000 | 1.000 | 0.802 | 0.670 | 0.602 | 0.480 | 0.420 | 0.358 | 0.330 |
| 0.1 | 1.000 | 1.000 | 1.000 | 0.814 | 0.690 | 0.626 | 0.510 | 0.450 | 0.388 | 0.360 |
| 0.2 | 1.000 | 1.000 | 1.000 | 0.826 | 0.710 | 0.650 | 0.538 | 0.472 | 0.408 | 0.380 |
| 0.3 | 1.000 | 1.000 | 1.000 | 0.844 | 0.740 | 0.680 | 0.570 | 0.510 | 0.448 | 0.420 |
| 0.4 | 1.000 | 1.000 | 1.000 | 0.862 | 0.770 | 0.714 | 0.610 | 0.550 | 0.482 | 0.450 |
| 0.5 | 1.000 | 1.000 | 1.000 | 0.880 | 0.800 | 0.748 | 0.650 | 0.590 | 0.528 | 0.500 |
| 0.6 | 1.000 | 1.000 | 1.000 | 0.898 | 0.830 | 0.782 | 0.694 | 0.646 | 0.588 | 0.560 |
| 0.7 | 1.000 | 1.000 | 1.000 | 0.922 | 0.870 | 0.830 | 0.754 | 0.706 | 0.654 | 0.630 |
| 0.8 | 1.000 | 1.000 | 1.000 | 0.946 | 0.910 | 0.878 | 0.818 | 0.782 | 0.734 | 0.710 |
| 0.9 | 1.000 | 1.000 | 1.000 | 0.970 | 0.950 | 0.934 | 0.902 | 0.878 | 0.846 | 0.830 |
| 1.0 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 |

C_o Table


| Wall Input Values | | | Force Input Value | | | | | |
|---------------------------------|----------------------|-----------------------------------|--------------------------|------------------|---------------------------------------|--------------|----------------|--------------|
| Height of Wall | h (ft) | 9 | Shear Force applied to | Wail | V (lbs) | 6308 | _ | |
| Maximum Opening Height | h _o (ft) | 7 | Force applied | d by wi | nd | | | |
| Width of Wall (total) | b (ft) | 57.75 | | | | | | |
| Sum of Wall Opening Width | b _o (ft) | 29 | Unit Shear Calculation | า | | | | |
| | | | Remaining Pier Length | * C ₀ | b _{fh} * C _o (ft) | 18.66 | _ | |
| | | | Unit Shear, V / Pier len | gth | v (lb/ft) | 338.00 | | |
| Calculate Perforation Reduct | ion | | | | | | | |
| Max Opening Hgt / Wall Hgt | h / h _o | 0.78 | Side 1: Sheathing: 1/2 | " OSE | 3 | | | |
| Shear Wall Remaining (piers) | b _{fh} (ft) | 28.75 | Length | - | L (ft) | 18.66 | _ | |
| Pier length / wall length | b _{th} / b | 0.498 | Unit Shear Ca 5 | 50.42 | v (ib/ft) | 640 | 8d Nail @ 2 | /12 Pattern |
| Perforation factor | C ₀ (ft) | 0.649 | | | | | | |
| | | | Side 2: Sheathing: 1/2 | " Gyp | Board | | | |
| *Perforation Factor is from Dou | ble Intertoplat | ion of C_o Table | Length | | L (ft) | 18.66 | _ | |
| | | | Unit Shear Capacity | | v (lb/ft) | 80 | #6Screw @ | 8/12 pattern |
| Hold-down Force Required | | | | | | | | |
| Length between Hold-downs | L (ft) | 57.5 | Total Force Capacity | | V (lbs) | 13437.0 | > 6308 | O.K. |
| Tension Force | T (ibs) | 987.34 | Equivalent Unit Shear | | v (lb/ft) | 720 | > 338.005 | О.К. |
| | | | | | | | | |
| IBC Code: Can sum the sheath | ing values pe | er side, but | | | | | | |
| the summation of the two must | be less that t | wice the | Gypsum is screwed a | at 16" | OC at edge j | oint along I | norizontal but | tt joints |
| lowest unit shear of the two ma | terials. | | | | | - | | |



Architects • Engineers • Planners

Job: Stratton Residence-Fox Point Project No.: 13-159 Date: May 4, 2013 Sheet_____of____

Perforated Shear Wall Worksheet SW-#E-1ST FLR



b_o = b1 + b2 +b3

b_{fh} = b - b_o

ho = height, maximum, for openings

V = Shear applied to Wall

- v = Unit Shear (from Piers * Perforation Factor)
- T = Tension Force for Holddown to System Below
- C = Compression Force to System Below

** Diagram is for illustrative purposes only. See Elevation Sheets for shear wall being examined.

| | h_0 / h | | | | | | | | | |
|---------------------|-----------|-------|-------|-------|-------|-------|-------|-------|-------|-------|
| b _{fh} / b | 0.1 | 0.2 | 0.3 | 0.4 | 0.5 | 0.6 | 0.7 | 0.8 | 0.9 | 1.0 |
| 0.0 | 1.000 | 1.000 | 1.000 | 0.802 | 0.670 | 0.602 | 0.480 | 0.420 | 0.358 | 0.330 |
| 0.1 | 1.000 | 1.000 | 1.000 | 0.814 | 0.690 | 0.626 | 0.510 | 0.450 | 0.388 | 0.360 |
| 0.2 | 1.000 | 1.000 | 1.000 | 0.826 | 0.710 | 0.650 | 0.538 | 0.472 | 0.408 | 0.380 |
| 0.3 | 1.000 | 1.000 | 1.000 | 0.844 | 0.740 | 0.680 | 0.570 | 0.510 | 0.448 | 0.420 |
| 0.4 | 1.000 | 1.000 | 1.000 | 0.862 | 0.770 | 0.714 | 0.610 | 0.550 | 0.482 | 0.450 |
| 0.5 | 1.000 | 1.000 | 1.000 | 0.880 | 0.800 | 0.748 | 0.650 | 0.590 | 0.528 | 0.500 |
| 0.6 | 1.000 | 1.000 | 1.000 | 0.898 | 0.830 | 0.782 | 0.694 | 0.646 | 0.588 | 0.560 |
| 0.7 | 1.000 | 1.000 | 1.000 | 0.922 | 0.870 | 0.830 | 0.754 | 0.706 | 0.654 | 0.630 |
| 0.8 | 1.000 | 1.000 | 1.000 | 0.946 | 0.910 | 0.878 | 0.818 | 0.782 | 0.734 | 0.710 |
| 0.9 | 1.000 | 1.000 | 1.000 | 0.970 | 0.950 | 0.934 | 0.902 | 0.878 | 0.846 | 0.830 |
| 1.0 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 |

C_o Table

| Wall Input Values | | |
|---------------------------|---------------------|-------|
| Height of Wall | h (ft) | 9 |
| Maximum Opening Height | h _o (ft) | 7 |
| Width of Wall (total) | b (ft) | 89.75 |
| Sum of Wall Opening Width | b _o (ft) | 33 |

Calculate Perforation Reduction


| Max Opening Hgt / Wall Hgt | h/h _o | 0.78 |
|------------------------------|----------------------|-------|
| Shear Wall Remaining (piers) | b _{fh} (ft) | 56.75 |
| Pier length / wall length | b _{th} / b | 0.632 |
| Perforation factor | C ₀ (ft) | 0.713 |

*Perforation Factor is from Double Intertoplation of Co Table

| Length between Hold-downs | L (ft) | 89.5 |
|---------------------------|---------|--------|
| Tension Force | T (lbs) | 473.13 |

IBC Code: Can sum the sheathing values per side, but the summation of the two must be less that twice the lowest unit shear of the two materials.


| Force Input Value | | | | |
|--|---------------------------------------|--------------|--------------|---------------|
| Shear Force applied to Wall | V (lbs) | 4705 | | |
| Force applied by w | vind | | | |
| Unit Shear Calculation | | | | |
| Remaining Pier Length * C ₀ | b _{fh} * C _o (ft) | 40.48 | | |
| Unit Shear, V / Pier length | v (ib/ft) | 116.22 | | |
| 8 | | | | |
| Side 1: Sheathing: 1/2" Gyp | . Board | | | |
| Length | L (ft) | 40.48 | | |
| Unit Shear Capacity | v (lb/ft) | 80 | #6 Screw @ | 8/12 Pattern |
| | | | | |
| Side 2: Sheathing: 1/2" Gyp | . Board | | | |
| Length | L (ft) | 40.48 | _ | |
| Unit Shear Capacity | v (ib/ft) | 80 | #6 Screw @ | 8/12 Pattern |
| Total Force Capacity | V (Ibs) | 6477.5 | > 4705 | О.К. |
| Equivalent Unit Shear | v (lb/ft) | 160 | > 116.217 | О.К. |
| | | | | |
| | | | | |
| Gypsum is screwed at 16 | 6" OC at edge | e joint aloi | ng horizonta | l butt ioints |



Architects • Engineers • Planners

Job: Stratton Residence-Fox Point Project No.: 13-159 Date: May 4, 2013 Sheet_____of____

Perforated Shear Wall Worksheet SW-#F-1ST FLR




 $b_0 = b1 + b2 + b3$

- b_{fh} = b b_o ho = height, maximum, for openings
- V = Shear applied to Wall
- v = Unit Shear (from Piers * Perforation Factor)
- T = Tension Force for Holddown to System Below
- C = Compression Force to System Below

** Diagram is for illustrative purposes only. See Elevation Sheets for shear wall being examined.


| | | | | | C _o Tab | ole | | | | |
|---------------------|-----------------------------------|----------------------|--------|---------------------|--------------------|-------------------|---------------------------------------|-------------|----------------|--------------|
| | | | | | h ₀ / h | | | | | |
| b _{ih} / b | 0.1 | 0.2 | 0.3 | 0.4 | 0.5 | 0.6 | 0.7 | 0.8 | 0.9 | 1.0 |
| 0.0 | 1.000 | 1.000 | 1.000 | 0.802 | 0.670 | 0.602 | 0.480 | 0.420 | 0.358 | 0.330 |
| 0.1 | 1.000 | 1.000 | 1.000 | 0.814 | 0.690 | 0.626 | 0.510 | 0.450 | 0.388 | 0.360 |
| 0.2 | 1.000 | 1.000 | 1.000 | 0.826 | 0.710 | 0.650 | 0.538 | 0.472 | 0.408 | 0.380 |
| 0.3 | 1.000 | 1.000 | 1.000 | 0.844 | 0.740 | 0.680 | 0.570 | 0.510 | 0.448 | 0.420 |
| 0.4 | 1.000 | 1.000 | 1.000 | 0.862 | 0.770 | 0.714 | 0.610 | 0.550 | 0.482 | 0.450 |
| 0.5 | 1.000 | 1.000 | 1.000 | 0.880 | 0.800 | 0.748 | 0.650 | 0.590 | 0.528 | 0.500 |
| 0.6 | 1.000 | 1.000 | 1.000 | 0.898 | 0.830 | 0.782 | 0.694 | 0.646 | 0.588 | 0.560 |
| 0.7 | 1.000 | 1.000 | 1.000 | 0.922 | 0.870 | 0.830 | 0.754 | 0.706 | 0.654 | 0.630 |
| 0.8 | 1.000 | 1.000 | 1.000 | AAAA | 0.910 | 0.878 | 0.818 | 0.782 | 0.734 | 0.710 |
| 0.9 | 1.000 | 1.000 | 1.000 | 0.970 | 0.950 | 0.934 | 0.902 | 0.878 | 0.846 | 0.830 |
| 1.0 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 |] 1.000 | 1.000 | 1.000 | 1.000 | 1.000 |
| Wall Input Val | ues | | | | Force Input V | /alue | | | | |
| Height of Wall | | h (ft) | 9 | | Shear Force a | | V (lbs) | 6308 | _ | |
| Maximum Oper | ning Height | h _o (ft) | 7 | | | | · · · · · · · · · · · · · · · · · · · | | | |
| Width of Wall (| | b (ft) | 57.75 | | | | | | | |
| Sum of Wall O | | b _o (ft) | 40 | | Unit Shear Ca | alculation | | | | |
| | | | | | Remaining Pie | er Length * Co | b _{th} * C _o (ft) | 10.17 | | |
| | | | | | Unit Shear, V | / Pier length | v (ib/ft) | 620.27 | | |
| Calculate Perf | oration Reduct | ion | | | | | - \ | | | |
| Max Opening H | lgt / Wall Hgt | h / h ₀ | 0.78 | | Side 1: Sheat | hing: 1/2" OSB | | | | |
| Shear Wall Rer | maining (piers) | b _{ih} (ft) | 17.75 | | Length | | L (ft) | 10.17 | | |
| Pier length / wa | all length | b _{íh} / b | 0.307 | | Unit Shear Ca | pacity | v (lb/ft) | 640 | 8d Nail @ 2/ | 12 Pattern |
| Perforation fact | tor | C _o (ft) | 0.573 | | | | | | | |
| *Dorforation Ea | star is from Dou | the Intertented | | | | hing: 1/2" Gyp. B | | | _ | |
| Penoration Fa | ctor is from Dou | ble intertopiat | | | Length | | L (ft) | 10.17 | | |
| Hold-down Fo | rce Required | | | Unit Shear Capacity | | pacity | v (lb/ft) | 80 | #6 Screw @ | 8/12 Pattern |
| Length betweer | n Hold-downs | L (ft) | 57.5 | | Total Force C | apacity | V (Ibs) | 7322.2 | > 6308 | О.К. |
| Tension Force | | T (lbs) | 987.34 | | Equivalent Un | nit Shear | v (lb/ft) | 720 | > 620.272 | О.К. |
| | sum the sheath of the two must | | | | Gypsum is s | crewed at 16" C | DC at edge join | t along hor | izontal butt j | oints |
| lowest unit shea | ar of the two mat | terials. | | | | | | Ū | • | |



Architects • Engineers • Planners

Job: Stratton Residence-Fox Point Project No.: 13-159 Date: May 4, 2013 Sheet____of_

Perforated Shear Wall Worksheet SW-#G-2ND FLR



 $b_0 = b1 + b2 + b3$

 $b_{fh} = b - b_o$

ho = height, maximum, for openings

V = Shear applied to Wall

v = Unit Shear (from Piers * Perforation Factor)

T = Tension Force for Holddown to System Below C = Compression Force to System Below

** Diagram is for illustrative purposes only. See Elevation Sheets for shear wall being examined.

| | | | | | C _o Tal | ole | | | | |
|--------------------|-------|-------|-------|-------|--------------------|-------|-------|-------|-------|-------|
| h _o / h | | | | | | | | | | |
| b _{fh} /b | 0.1 | 0.2 | 0.3 | 0.4 | 0.5 | 0.6 | 0.7 | 0.8 | 0.9 | 1.0 |
| 0.0 | 1.000 | 1.000 | 1.000 | 0.802 | 0.670 | 0.602 | 0.480 | 0.420 | 0.358 | 0.330 |
| 0.1 | 1.000 | 1.000 | 1.000 | 0.814 | 0.690 | 0.626 | 0.510 | 0.450 | 0.388 | 0.360 |
| 0.2 | 1.000 | 1.000 | 1.000 | 0.826 | 0.710 | 0.650 | 0.538 | 0.472 | 0.408 | 0.380 |
| 0.3 | 1.000 | 1.000 | 1.000 | 0.844 | 0.740 | 0.680 | 0.570 | 0.510 | 0.448 | 0.420 |
| 0.4 | 1.000 | 1.000 | 1.000 | 0.862 | 0.770 | 0.714 | 0.610 | 0.550 | 0.482 | 0.450 |
| 0.5 | 1.000 | 1.000 | 1.000 | 0.880 | 0.800 | 0.748 | 0.650 | 0.590 | 0.528 | 0.500 |
| 0.6 | 1.000 | 1.000 | 1.000 | 0.898 | 0.830 | 0.782 | 0.694 | 0.646 | 0.588 | 0.560 |
| 0.7 | 1.000 | 1.000 | 1.000 | 0.922 | 0.870 | 0.830 | 0.754 | 0.706 | 0.654 | 0.630 |
| 0.8 | 1.000 | 1.000 | 1.000 | 0.946 | 0.910 | 0.878 | 0.818 | 0.782 | 0.734 | 0.710 |
| 0.9 | 1.000 | 1.000 | 1.000 | 0.970 | 0.950 | 0.934 | 0.902 | 0.878 | 0.846 | 0.830 |
| 1.0 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 |

| Wall Input Values | | |
|---------------------------|---------------------|-------|
| Height of Wall | h (ft) | 8 |
| Maximum Opening Height | h _o (ft) | 5 |
| Width of Wall (total) | b (ft) | 59.25 |
| Sum of Wall Opening Width | b _o (ft) | 22 |

Calculate Perforation Reduction Max Opening Hot / Wall Hot h/ho

| Max Opening Hgt / Wall Hgt | h / h ₀ | 0.63 |
|------------------------------|----------------------|-------|
| Shear Wall Remaining (piers) | b _{íh} (ft) | 37.25 |
| Pier length / wall length | b _{fh} / b | 0.629 |
| Perforation factor | C ₀ (ft) | 0.775 |


*Perforation Factor is from Double Intertoplation of Co Table

| Hold-down | Force | Required | |
|-----------|-------|----------|--|
| | | | |

| Length between Hold-downs | L (ft) | 59 |
|---------------------------|---------|--------|
| Tension Force | T (lbs) | 485.29 |

IBC Code: Can sum the sheathing values per side, but the summation of the two must be less that twice the lowest unit shear of the two materials.


| Force Input Value | | | | |
|--|---------------------------------------|--------------|----------------------------------|-------------|
| Shear Force applied to Wall | V (lbs) | 3579 | | |
| Unit Shear Calculation | | | | |
| Remaining Pier Length * Co | b _{fb} * C _o (ft) | 28.86 | | |
| 5 Unit Shear, V / Pier length | v (lb/ft) | 124.03 | | |
| Side 1: Sheathing: 1/2" OSI | 3 | | | |
| Side I. Sheathing. I/2 USI | - | | | |
| Length | L (ft) | 28.86 | _ | |
| | | 28.86 260 | 8d Nail @ 6 | /12 Pattern |
| Length | L (ft) | | | /12 Pattern |
| Length Unit Shear Capacity | L (ft) | | 8d Nail @ 6 | /12 Pattern |
| Length Unit Shear Capacity Side 2: Sheating 1/2" GYP | L (ft) v (lb/ft) | 260 | 8d Nail @ 6 #6Screw @ | |
| Length Unit Shear Capacity Side 2: Sheating 1/2" GYP Length | L (ft) v (lb/ft) L (ft) | 260 28.86 | _ | |



Architects • Engineers • Planners

Job: Stratton Residence-Fox Point Project No.: 13-159 Date: May 4, 2013 Sheet____of_

Perforated Shear Wall Worksheet SW-#H-2ND FLR



 $b_0 = b1 + b2 + b3$

 $b_{fh} = b - b_o$

ho = height, maximum, for openings

V = Shear applied to Wall

v = Unit Shear (from Piers * Perforation Factor)

T = Tension Force for Holddown to System Below C = Compression Force to System Below

** Diagram is for illustrative purposes only. See Elevation Sheets for shear wall being examined.

| | | | | | C _o Tab _{h₀} /h | | | | | |
|---------------------|-----------------|----------------------|-------|-------|--|----------------|---------------------------------------|-------|--------------|-------------|
| b _{fh} / b | 0.1 | 0.2 | 0.3 | 0.4 | 0.5 | 0.6 | 0.7 | 0.8 | 0.9 | 1.0 |
| 0.0 | 1.000 | 1.000 | 1.000 | 0.802 | 0.670 | 0.602 | 0.480 | 0.420 | 0.358 | 0.330 |
| 0.1 | 1.000 | 1.000 | 1.000 | 0.814 | 0.690 | 0.626 | 0.510 | 0.450 | 0.388 | 0.360 |
| 0.2 | 1.000 | 1.000 | 1.000 | 0.826 | 0.710 | 0.650 | 0.538 | 0.472 | 0.408 | 0.380 |
| 0.3 | 1.000 | 1.000 | 1.000 | 0.844 | 0.740 | 0.680 | 0.570 | 0.510 | 0.448 | 0.420 |
| 0.4 | 1.000 | 1.000 | 1.000 | 0.862 | 0.770 | 0.714 | 0.610 | 0.550 | 0.482 | 0.450 |
| 0.5 | 1.000 | 1.000 | 1.000 | 0.880 | 0.800 | 0.748 | 0.650 | 0.590 | 0.528 | 0.500 |
| 0.6 | 1.000 | 1.000 | 1.000 | 0.898 | 0.830 | 0.782 | 0.694 | 0.646 | 0.588 | 0.560 |
| 0.7 | 1.000 | 1.000 | 1.000 | 0.922 | 0.870 | 0.830 | 0.754 | 0.706 | 0.654 | 0.630 |
| 0.8 | 1.000 | 1.000 | 1.000 | 0.946 | 0.910 | 0.878 | 0.818 | 0.782 | 0.734 | 0.710 |
| 0.9 | 1.000 | 1.000 | 1.000 | 0.970 | 0.950 | 0.934 | 0.902 | 0.878 | 0.846 | 0.830 |
| 1.0 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 |
| Wall Input Val | ues | | | | Force Input V | alue | | | | |
| Height of Wall | | h (ft) | 8 | • | Shear Force a | pplied to Wall | V (lbs) | 2524 | _ | |
| Maximum Oper | ning Height | h _o (ft) | 7 | | | | | | | |
| Width of Wall (1 | total) | b (ft) | 72.75 | | | | | | | |
| Sum of Wall Op | pening Width | b _o (ft) | 15 | | Unit Shear Ca | alculation | | | | |
| | | | | | Remaining Pie | er Length * Co | b _{fh} * C _o (ft) | 42.80 | _ | |
| | | | | | Unit Shear, V | / Pier length | v (lb/ft) | 58.97 | | |
| | oration Reduct | | | | | | | | | |
| Max Opening H | lgt / Wali Hgt | h / h ₀ | 0.88 | | Side 1: Sheat | hing: 1/2" Gyp | . Board | | | |
| Shear Wall Rer | naining (piers) | b _{fh} (ft) | 57.75 | | Length | | · L (ft) | 42.80 | _ | |
| Pier length / wa | ll length | b _{th} / b | 0.794 | | Unit Shear Ca | pacity | v (lb/ft) | 80 | #6 Screw @ 8 | /12 Pattern |
| Perforation fact | or | C ₀ (ft) | 0.741 | | | | | | | |

Side 2: sheating 1/2" gyp board

*Perforation Factor is from Double Intertoplation of Co Table

| Hold-down Force Required | | |
|---------------------------|---------|--------|
| Length between Hold-downs | L (ft) | 72.5 |
| Tension Force | T (ibs) | 278.51 |

IBC Code: Can sum the sheathing values per side, but the summation of the two must be less that twice the lowest unit shear of the two materials.

Gypsum is screwed at 16" OC at edge joint along horizontal butt joints

42.80

80

6847.8

160

#6 Screw @ 8/12 Pattern

0.К.

О.К.

> 2524

> 58.974

L (ft)

v (lb/ft)

V (lbs)


v (lb/ft)

Length

Unit Shear Capacity

Total Force Capacity


Equivalent Unit Shear



Architects • Engineers • Planners

Job: Stratton Residence-Fox Point Project No.: 13-159 Date: May 4, 2013 Sheet____of____

Perforated Shear Wall Worksheet SW-#I-2ND FLR



 $b_0 = b1 + b2 + b3$

b_{fh} = b - b_o


ho = height, maximum, for openings

V = Shear applied to Wall

- v = Unit Shear (from Piers * Perforation Factor)
- T = Tension Force for Holddown to System Below C = Compression Force to System Below

** Diagram is for illustrative purposes only. See Elevation Sheets for shear wall being examined.


| $ \begin{array}{ c c c c c c c c c c c c c c c c c c c$ | | | | | le | C _o Tab _{b₀} /h | | | | | |
|--|-------------|-------------------|---------------|---------------------------------------|------------------|--|-------|----------------------------|----------------------|------------------|---------------------------------|
| $ \begin{array}{c c c c c c c c c c c c c c c c c c c $ | 1.0 | 0.9 | 0.8 | 0.7 | 0.6 | | 0.4 | 0.3 | 0.2 | 0.1 | b _{fh} / b |
| $ \begin{array}{c c c c c c c c c c c c c c c c c c c $ | 0.330 | 0.358 | 0.420 | 0.480 | 0.602 | 0.670 | 0.802 | 1.000 | 1.000 | 1.000 | 0.0 |
| 0.3 1.000 1.000 1.000 1.000 0.844 0.740 0.680 0.570 0.511 0.448 0.4 1.000 1.000 1.000 0.862 0.770 0.714 0.610 0.550 0.482 0.5 1.000 1.000 1.000 0.880 0.800 0.748 0.650 0.590 0.528 0.6 1.000 1.000 1.000 0.898 0.830 0.754 0.694 0.646 0.588 0.7 1.000 1.000 1.000 0.922 0.870 0.830 0.754 0.706 0.654 0.8 1.000 1.000 1.000 0.970 0.9550 0.934 0.902 0.878 0.846 0.9 1.000 1. | 0.360 | 0.388 | 0.450 | 0.510 | 0.626 | 0.690 | 0.814 | 1.000 | 1.000 | 1.000 | |
| $ \begin{array}{c c c c c c c c c c c c c c c c c c c $ | 0.380 | 0.408 | 0.472 | 0.538 | 0.650 | 0.710 | 0.826 | 1.000 | 1.000 | 1.000 | 0.2 |
| $ \begin{array}{c c c c c c c c c c c c c c c c c c c $ | 0.420 | 0.448 | 0.510 | 0.570 | 0.680 | 0.740 | 0.844 | 1.000 | 1.000 | 1.000 | 0.3 |
| $ \begin{array}{c c c c c c c c c c c c c c c c c c c $ | 0.450 | 0.482 | 0.550 | 0.610 | 0.714 | 0.770 | | | | | - |
| $\begin{array}{c c c c c c c c c c c c c c c c c c c $ | 0.500 | 0.528 | 0.590 | 0.650 | | 4 1 | | | | | |
| 0.8 1.000 1.000 1.000 1.000 0.946 0.910 0.878 0.818 0.782 0.734 0.9 1.000 1.000 1.000 1.000 0.970 0.950 0.934 0.902 0.878 0.846 1.0 1.000 <td>0.560</td> <td>0.588</td> <td></td> <td>0.694</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> | 0.560 | 0.588 | | 0.694 | | | | | | | |
| 0.9 1.000 | 0.630 | 0.654 | 0.706 | 0.754 | | | | | | | |
| 1.01.001.0001. | 0.710 | | | | | | | | | | |
| Wall Input ValuesForce Input ValueHeight of Wallh (ft)8Maximum Opening Heighth_o (ft)5Width of Wall (total)b (ft)59.25Sum of Wall Opening Width31Unit Shear CalculationCalculate Perforation ReductionRemaining Pier Length * C_o b_{th} * C_o (ft)20.21Max Opening Hgt / Wall Hgth / h_o0.63Shear Wall Remaining (piers) b_{th} (ft)28.25Pier length / wall length b_{th} / b0.477Perforation factorC_o (ft)0.715Side 2: Sheathing: 1/2" Gyp. Board*Perforation Factor is from Double Intertoplation of Co TableHold-down Force RequiredLengthL (ft)20.21Unit Shear Capacityv (lb/ft)80#6Screw @ 8Total Force CapacityV (lbs)6870.1 | 0.830 | | | | | | | | | | |
| Height of Wallh (ft)8Maximum Opening Height h_o (ft)5Width of Wall (total)b (ft)59.25Sum of Wall Opening Width31Unit Shear Calculation Remaining Pier Length * Co b_{th} * Co (ft)20.21 Unit Shear, V / Pier lengthCalculate Perforation ReductionMax Opening Hgt / Wall Hgth / h_0 0.63Shear Wall Remaining (piers) b_{in} (ft)28.25Pier length / wall length b_{in} / b0.477Perforation factorCo (ft)0.715Side 1: Sheathing: 1/2" OSBSide 2: Sheathing: 1/2" Gyp. BoardLengthLengthL (ft)20.21Unit Shear Capacityv (lb/ft)20.21Unit Shear Capacityv (lb/ft | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 [| 1.000 | 1.000 | 1.000 J | 1.000 | 1.000 | 1.0 |
| Height of Wallh (ft)8Shear Force applied to WallV (lbs) 3579 Maximum Opening Heighth_0 (ft)55 3579 Width of Wall (total)b (ft) 59.25 31 Unit Shear CalculationSum of Wall Opening Width31Unit Shear CalculationRemaining Pier Length * C ₀ b_{th} * C ₀ (ft) 20.21 Unit Shear, V / Pier lengthv (lb/ft) 177.13 Side 1: Sheathing: $1/2"$ OSBShear Wall Remaining (piers) b_{th} (ft) 28.25 Pier length / wall length b_{th} / b 0.477 Unit Shear Capacityv (lb/ft) 20.21 Perforation factorC ₀ (ft) 0.715 Side 2: Sheathing: $1/2"$ Gyp. Board* Perforation Factor is from Double Intertoplation of C ₀ TableHold-down Force RequiredLengthL (ft) 20.21 Unit Shear Capacityv (lb/ft) 80 #6Screw @ 8Hold-down Force RequiredTotal Force CapacityV (lbs) 6870.1 | | | | | alue | Force Input V | | | | les | Wall Input Valu |
| Width of Wall (total)b (ft)59.25Sum of Wall Opening Width31Unit Shear Calculation Remaining Pier Length $*C_0$ $b_{fh} * C_o$ (ft)20.21 Unit Shear, V / Pier lengthCalculate Perforation ReductionMax Opening Hgt / Wall Hgth / h_00.63 0.63Side 1: Sheathing: 1/2" OSBShear Wall Remaining (piers) b_{fh} (ft)28.25 0.477Pier length / wall length b_{fh} / b0.477 0.715Unit Shear Capacityv (lb/ft)2608d Nail @ 6/1*Perforation factor C_0 (ft)0.715Side 2: Sheathing: 1/2" Gyp. Board LengthLengthL (ft)20.21 20.21*Perforation Factor is from Double Intertoplation of C_0 TableSide 2: Sheathing: 1/2" Gyp. Board LengthLengthL (ft)20.21 400 #6Screw @ 8Hold-down Force RequiredTotal Force CapacityV (lbs)6870.1> | | - - | 3579 | V (lbs) | | | | 8 | h (ft) | | |
| Width of Wall (total)b (ft)59.25Sum of Wall Opening Width31Unit Shear Calculation Remaining Pier Length $^{\circ}C_{o}$ (ft)20.21 Unit Shear, V / Pier lengthV (Ib/ft)177.13Calculate Perforation ReductionMax Opening Hgt / Wall Hgth / h_{0}0.63Shear Wall Remaining (piers)b _{in} (ft)28.25Pier length / wall lengthb _{in} / b0.477Perforation factorC_0 (ft)0.715Side 2: Sheathing: 1/2" Gyp. Board*Perforation Factor is from Double Intertoplation of Co TableHold-down Force RequiredLengthL (ft)20.21 Unit Shear CapacityV (Ib/ft)80#6Screw @ 8Total Force CapacityV (lbs)6870.1 | | | | . , | | | | 5 | h _o (ft) | ning Height | Maximum Open |
| Sum of Wall Opening Width31Unit Shear Calculation Remaining Pier Length $*C_0$ b _{th} $*C_0$ (ft)20.21 20.21 Unit Shear, V / Pier lengthCalculate Perforation ReductionSide 1: Sheathing: 1/2" OSBMax Opening Hgt / Wall Hgth / h_00.63 0.63Shear Wall Remaining (piers)b _{in} (ft)28.25 0.477Pier length / wall lengthb _{in} / b0.477 0.715Unit Shear Capacityv (lb/ft)20.21 20.21Perforation factorC ₀ (ft)0.715Side 2: Sheathing: 1/2" Gyp. Board LengthEngthL (ft)20.21 20.21*Perforation Factor is from Double Intertoplation of C ₀ TableSide 2: Sheathing: 1/2" Gyp. Board LengthEngthL (ft)20.21 20.21 Unit Shear CapacityV (lb/ft)80#6Screw @ 8Hold-down Force RequiredEngthL (ft)59Total Force CapacityV (lbs)6870.1> | | | | | | | | | | otal) | Width of Wall (to |
| Unit Shear, V / Pier lengthv (lb/ft)177.13Calculate Perforation ReductionMax Opening Hgt / Wall Hgth / h_00.63Shear Wall Remaining (piers)b _{ih} (ft)28.25Pier length / wall lengthb _{ih} / b0.477Perforation factor C_0 (ft)0.715Side 1: Sheathing: 1/2" OSBLengthLengthL (ft)20.21Unit Shear Capacityv (lb/ft)2608d Nail @ 6/1Perforation factorCo (ft)0.715Side 2: Sheathing: 1/2" Gyp. BoardLengthLengthL (ft)20.21Unit Shear Capacityv (lb/ft)80#Old-down Force RequiredLengthL (ft)20.21Length between Hold-downsL (ft)59Total Force CapacityV (lbs)6870.1 | | | | | lculation | Unit Shear Ca | | | ., | ening Width | Sum of Wall Op |
| Unit Shear, V / Pier lengthv (lb/ft)177.13Calculate Perforation ReductionMax Opening Hgt / Wall Hgth / h_00.63Shear Wall Remaining (piers)b _{ih} (ft)28.25Pier length / wall lengthb _{ih} / b0.477Perforation factor C_0 (ft)0.715Side 1: Sheathing: 1/2" OSBLengthLengthL (ft)20.21Unit Shear Capacityv (lb/ft)2608d Nail @ 6/1Perforation factorCo (ft)0.715Side 2: Sheathing: 1/2" Gyp. BoardLengthLengthL (ft)20.21Unit Shear Capacityv (lb/ft)80#Old-down Force RequiredLengthL (ft)20.21Length between Hold-downsL (ft)59Total Force CapacityV (lbs)6870.1 | | - | 20.21 | b _{fh} * C _o (ft) | r Length * C₀ | Remaining Pie | | | | | |
| Calculate Perforation Reduction Max Opening Hgt / Wall Hgt h / h_0 0.63 Side 1: Sheathing: 1/2" OSB Shear Wall Remaining (piers) b_{ln} (ft) 28.25 Length L (ft) 20.21 Pier length / wall length b_{ln} / b 0.477 Unit Shear Capacity v (lb/ft) 260 8d Nail @ 6/1 Perforation factor C_0 (ft) 0.715 Side 2: Sheathing: 1/2" Gyp. Board Ength L (ft) 20.21 *Perforation Factor is from Double Intertoplation of C_0 Table Side 2: Sheathing: 1/2" Gyp. Board Ength L (ft) 20.21 Hold-down Force Required Unit Shear Capacity v (lb/ft) 80 #6Screw @ 8 Length between Hold-downs L (ft) 59 Total Force Capacity V (lbs) 6870.1 | | | | | Pier length | Unit Shear. V / | | | | | |
| Shear Wall Remaining (piers) b_{th} (ft) 28.25 Length L (ft) 20.21 Pier length / wall length b_{th} / b 0.477 Unit Shear Capacity v (lb/ft) 260 8d Nail @ 6/1 Perforation factor C_0 (ft) 0.715 Side 2: Sheathing: 1/2" Gyp. Board 1000000000000000000000000000000000000 | | | | (| | | | | ion | pration Reduct | Calculate Perfo |
| Pier length / wall length b _{th} / b 0.477 Unit Shear Capacity v (lb/ft) 260 8d Nail @ 6/1 Perforation factor C ₀ (ft) 0.715 Side 2: Sheathing: 1/2" Gyp. Board *Perforation Factor is from Double Intertoplation of C ₀ Table Hold-down Force Required Length L (ft) 20.21 Unit Shear Capacity v (lb/ft) 80 #6Screw @ 8 Hold-down S L (ft) 59 Total Force Capacity V (lbs) 6870.1 | | | | 3 | ning: 1/2" OSE | Side 1: Sheat | | 0.63 | h/h _o | gt / Wall Hgt | Max Opening H |
| Perforation factor C ₀ (ft) 0.715 *Perforation factor is from Double Intertoplation of C ₀ Table Side 2: Sheathing: 1/2" Gyp. Board *Perforation Factor is from Double Intertoplation of C ₀ Table Length L (ft) 20.21 Hold-down Force Required Unit Shear Capacity v (lb/ft) 80 #6Screw @ 8 Length L (ft) 59 Total Force Capacity V (lbs) 6870.1 | | - | 20.21 | L (ft) | | Length | | 28.25 | b _{íh} (ft) | naining (piers) | Shear Wall Rem |
| Perforation factor C ₀ (ft) 0.715 *Perforation factor is from Double Intertoplation of C ₀ Table Side 2: Sheathing: 1/2" Gyp. Board *Perforation Factor is from Double Intertoplation of C ₀ Table Length L (ft) 20.21 Hold-down Force Required Unit Shear Capacity v (lb/ft) 80 #6Screw @ 8 Length L (ft) 59 Total Force Capacity V (lbs) 6870.1 | 2 Pattern | 8d Nail @ 6/12 | 260 | v (lb/ft) | acity | Unit Shear Car | | 0.477 | b _{fh} / b | ll length | Pier length / wal |
| *Perforation Factor is from Double Intertoplation of Co Table Length L (ft) 20.21 Unit Shear Capacity v (lb/ft) 80 #6Screw @ 8 Hold-down Force Required Ength the force Capacity v (lbs) 6870.1 | | | | . , | • | | | 0.715 | C ₀ (ft) | or | Perforation facto |
| Hold-down Force Required Unit Shear Capacity v (lb/ft) 80 #6Screw @ 8 Length between Hold-downs L (ft) 59 Total Force Capacity V (lbs) 6870.1 > | | _ | _ | | ning: 1/2" Gyp | | | | | | |
| Hold-down Force Required Total Force Capacity V (lbs) 6870.1 > | | | - | • • | | 0 | | on of C _o Table | ble Intertoplat | ctor is from Dou | *Perforation Fac |
| Length between Hold-downs L (ft) 59 Total Force Capacity V (lbs) 6870.1 > | /12 pattern | #6Screw @ 8/1 | 80 | v (lb/ft) | acity | Unit Shear Cap | | | | | |
| | | | | | | | | | 1 (4) | | |
| Topping Fores T (lbs) 0.00 Equivalent (lait Observer 1) (lt (tt) 0.00 (lt (tt)) | O.K. | | | • • | • • | | | 59 0.00 | | Hold-downs | Length between Tension Force |
| Tension Force T (lbs) 0.00 Equivalent Unit Shear v (lb/ft) 340 > 177.126 | O.K. | > 177.126 C | 340 | ν (ib/π) | it Snear | Equivalent Un | | 0.00 | i (ibs) | | Tension Force |
| IBC Code: Can sum the sheathing values per side, but | | | | | | | | | | | |
| the summation of the two must be less that twice the Gypsum is screwed at 16" OC at edge joint along horizontal butt lowest unit shear of the two materials. | oints | orizontal butt jo | oint along ho | OC at edge j | rewed at 16" | Gypsum is so | | vice the | | | |



Architects • Engineers • Planners

Job: Stratton Residence-Fox Point Project No.: 13-159 Date: May 4, 2013 Sheet_____of__

Perforated Shear Wall Worksheet SW-#J-2ND FLR



 $b_0 = b1 + b2 + b3$

b_{fh} = b - b_o

ho = height, maximum, for openings

V = Shear applied to Wall

v = Unit Shear (from Piers * Perforation Factor)

T = Tension Force for Holddown to System Below

C = Compression Force to System Below

** Diagram is for illustrative purposes only. See Elevation Sheets for shear wall being examined.

| | | | | | C _o Tal | ble | | | | |
|---------------------|-------|-------|-------|-------|--------------------|-------|-------|-------|-------|-------|
| | | | | | h _o / h | | | | | |
| b _{fh} / b | 0.1 | 65.5 | 0.3 | 0.4 | 0.5 | 0.6 | 0.7 | 0.8 | 0.9 | 1.0 |
| 0.0 | 1.000 | 1.000 | 1.000 | 0.802 | 0.670 | 0.602 | 0.480 | 0.420 | 0.358 | 0.330 |
| 0.1 | 1.000 | 1.000 | 1.000 | 0.814 | 0.690 | 0.626 | 0.510 | 0.450 | 0.388 | 0.360 |
| 0.2 | 1.000 | 1.000 | 1.000 | 0.826 | 0.710 | 0.650 | 0.538 | 0.472 | 0.408 | 0.380 |
| 0.3 | 1.000 | 1.000 | 1.000 | 0.844 | 0.740 | 0.680 | 0.570 | 0.510 | 0.448 | 0.420 |
| 0.4 | 1.000 | 1.000 | 1.000 | 0.862 | 0.770 | 0.714 | 0.610 | 0.550 | 0.482 | 0.450 |
| 0.5 | 1.000 | 1.000 | 1.000 | 0.880 | 0.800 | 0.748 | 0.650 | 0.590 | 0.528 | 0.500 |
| 0.6 | 1.000 | 1.000 | 1.000 | 0.898 | 0.830 | 0.782 | 0.694 | 0.646 | 0.588 | 0.560 |
| 0.7 | 1.000 | 1.000 | 1.000 | 0.922 | 0.870 | 0.830 | 0.754 | 0.706 | 0.654 | 0.630 |
| 0.8 | 1.000 | 1.000 | 1.000 | 0.946 | 0.910 | 0.878 | 0.818 | 0.782 | 0.734 | 0.710 |
| 0.9 | 1.000 | 1.000 | 1.000 | 0.970 | 0.950 | 0.934 | 0.902 | 0.878 | 0.846 | 0.830 |
| 1.0 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 |
| | | | | | | | | - | | • |
| Wall input Val | ues | | | | Force Input V | 'alue | | | | |

_ . .

| Wall Input Values | | | Force In |
|---------------------------|---------------------|-------|----------|
| Height of Wall | h (ft) | 8 | Shear F |
| Maximum Opening Height | h _o (ft) | 5 | |
| Width of Wall (total) | b (ft) | 57.75 | |
| Sum of Wall Opening Width | b _o (ft) | 5 | Unit Sh |
| | | | Bemaini |

Calculate Perforation Reduction

| Max Opening Hgt / Wall Hgt | h/h ₀ | 0.63 |
|------------------------------|----------------------|-------|
| Shear Wall Remaining (piers) | b _{fh} (ft) | 52.75 |
| Pier length / wall length | b _{íh} / b | 0.913 |
| Perforation factor | C ₀ (ft) | 0.936 |


*Perforation Factor is from Double Intertoplation of \mathbf{C}_{o} Table

| Hold-down Force Required | |
|---------------------------|-----|
| Length between Hold-downs | 1.1 |

| Length between Hold-downs | L (ff) | 57.5 |
|---------------------------|---------|--------|
| Tension Force | T (lbs) | 501.70 |
| | | |

IBC Code: Can sum the sheathing values per side, but the summation of the two must be less that twice the lowest unit shear of the two materials.


| Shear Force applied to Wall | V (lbs) | 3606 | _ | |
|-----------------------------|---------------------------------------|---------|-----------|--------------|
| Unit Shear Calculation | | | | |
| Remaining Pier Length * Co | b _{fh} * C _o (ft) | 49.37 | _ | |
| Unit Shear, V / Pier length | v (lb/ft) | 73.04 | | |
| Side 1: Sheathing: 1/2" OS | в | | | |
| Length | L (ft) | 49.37 | - | |
| Unit Shear Capacity | v (lb/ft) | 260 | 8d Nail @ | 6/12 Pattern |
| Side 2: Sheathing: 1/2" Gyp | . Board | | | |
| Length | L (ft) | 49.37 | _ | |
| Unit Shear Capacity | v (lb/ft) | 80 | #6Screw (| 8/12 pattern |
| | V (lbs) | 16785.9 | > 3606 | О.К. |
| Total Force Capacity | • (| | | |



Architects • Engineers • Planners

Job: Stratton Residence-Fox Point Project No.: 13-159 Date: May 4, 2013 Sheet_____of____

Perforated Shear Wall Worksheet SW-#K-2ND FLR



b_o = b1 + b2 +b3

b_{fh} = b - b_o

ho = height, maximum, for openings

V = Shear applied to Wall

v = Unit Shear (from Piers * Perforation Factor)

T = Tension Force for Holddown to System Below C = Compression Force to System Below

** Diagram is for illustrative purposes only. See Elevation Sheets for shear wall being examined.

| C _o Table h₀ / h | | | | | | | | | | |
|--------------------------------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|
| b _{fh} / b | 0.1 | 0.2 | 0.3 | 0.4 | 0.5 | 0.6 | 0.7 | 0.8 | 0.9 | 1.0 |
| 0.0 | 1.000 | 1.000 | 1.000 | 0.802 | 0.670 | 0.602 | 0.480 | 0.420 | 0.358 | 0.330 |
| 0.1 | 1.000 | 1.000 | 1.000 | 0.814 | 0.690 | 0.626 | 0.510 | 0.450 | 0.388 | 0.360 |
| 0.2 | 1.000 | 1.000 | 1.000 | 0.826 | 0.710 | 0.650 | 0.538 | 0.472 | 0.408 | 0.380 |
| 0.3 | 1.000 | 1.000 | 1.000 | 0.844 | 0.740 | 0.680 | 0.570 | 0.510 | 0.448 | 0.420 |
| 0.4 | 1.000 | 1.000 | 1.000 | 0.862 | 0.770 | 0.714 | 0.610 | 0.550 | 0.482 | 0.450 |
| 0.5 | 1.000 | 1.000 | 1.000 | 0.880 | 0.800 | 0.748 | 0.650 | 0.590 | 0.528 | 0.500 |
| 0.6 | 1.000 | 1.000 | 1.000 | 0.898 | 0.830 | 0.782 | 0.694 | 0.646 | 0.588 | 0.560 |
| 0.7 | 1.000 | 1.000 | 1.000 | 0.922 | 0.870 | 0.830 | 0.754 | 0.706 | 0.654 | 0.630 |
| 0.8 | 1.000 | 1.000 | 1.000 | 0.946 | 0.910 | 0.878 | 0.818 | 0.782 | 0.734 | 0.710 |
| 0.9 | 1.000 | 1.000 | 1.000 | 0.970 | 0.950 | 0.934 | 0.902 | 0.878 | 0.846 | 0.830 |
| 1.0 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 |

| Wall Input Values | | |
|---------------------------|---------------------|-----|
| Height of Wall | h (ft) | 8 |
| Maximum Opening Height | h _o (ft) | 7 |
| Width of Wall (total) | b (ft) | 105 |
| Sum of Wall Opening Width | b _o (ft) | 24 |

Calculate Perforation Reduction

| Max Opening Hgt / Wall Hgt | h / h _o | 0.88 |
|------------------------------|----------------------|-------|
| Shear Wall Remaining (piers) | b _{fh} (ft) | 81 |
| Pier length / wall length | b _{fh} / b | 0.771 |
| Perforation factor | C ₀ (ft) | 0.723 |


*Perforation Factor is from Double Intertoplation of C_o Table

| Hold-down | Force | Required | |
|-----------|-------|----------|--|
| | | | |

| Length between Hold-downs | L (ft) | 104.75 |
|---------------------------|---------|--------|
| Tension Force | T (lbs) | 194.52 |

IBC Code: Can sum the sheathing values per side, but the summation of the two must be less that twice the lowest unit shear of the two materials.


| Shear Force applied to Wall | V (lbs) | 2547 | | |
|-----------------------------|---------------------------------------|--------|------------|--------------|
| Force applied by w | vind | | | |
| Unit Shear Calculation | | | | |
| Remaining Pier Length * Co | b _{fh} * C _o (ft) | 58.60 | | |
| Unit Shear, V / Pier length | v (lb/ft) | 43.47 | | |
| 8 | | | | |
| Side 1: Sheathing: 1/2" Gyr | o. Board | _ | _ | |
| Length | L (ft) | 58.60 | | |
| Unit Shear Capacity | v (lb/ft) | 80 | #6 Screw @ | 8/12 Pattern |
| | | | | |
| Side 2: Sheathing: 1/2" Gyp | . Board | | | |
| Length | L (ft) | 58.60 | _ | |
| Unit Shear Capacity | v (ib/ft) | 80 | #6 Screw @ | 8/12 Pattern |
| Total Force Capacity | V (lbs) | 9375.6 | > 2547 | О.К. |
| Equivalent Unit Shear | v (lb/ft) | 160 | > 43.467 | О.К. |
| | | | | |
| | | | | |



Architects • Engineers • Planners

Job: Stratton Residence-Fox Point Project No.: 13-159 Date: May 4, 2013 Sheet____of____

Perforated Shear Wall Worksheet SW-#L-2ND FLR





 $b_0 = b1 + b2 + b3$

- b_{fh} = b b_o ho = height, maximum, for openings
- V = Shear applied to Wall
- v = Unit Shear (from Piers * Perforation Factor)
- T = Tension Force for Holddown to System Below
- C = Compression Force to System Below

** Diagram is for illustrative purposes only. See Elevation Sheets for shear wall being examined.

| | | | | | C _o Tab | ole | | | | |
|---------------------------------|-------------------|----------------------|------------------------------|-------|--------------------|-------------------|---------------------------------------|-------------|----------------|--------------|
| | | | | | h _o /h | | | | | |
| b _{íh} / b | 0.1 | 0.2 | 0.3 | 0.4 | 0.5 | 0.6 | 0.7 | 0.8 | 0.9 | 1.0 |
| 0.0 | 1.000 | 1.000 | 1.000 | 0.802 | 0.670 | 0.602 | 0.480 | 0.420 | 0.358 | 0.330 |
| 0.1 | 1.000 | 1.000 | 1.000 | 0.814 | 0.690 | 0.626 | 0.510 | 0.450 | 0.388 | 0.360 |
| 0.2 | 1.000 | 1.000 | 1.000 | 0.826 | 0.710 | 0.650 | 0.538 | 0.472 | 0.408 | 0.380 |
| 0.3 | 1.000 | 1.000 | 1.000 | 0.844 | 0.740 | 0.680 | 0.570 | 0.510 | 0.448 | 0.420 |
| 0.4 | 1.000 | 1.000 | 1.000 | 0.862 | 0.770 | 0.714 | 0.610 | 0.550 | 0.482 | 0.450 |
| 0.5 | 1.000 | 1.000 | 1.000 | 0.880 | 0.800 | 0.748 | 0.650 | 0.590 | 0.528 | 0.500 |
| 0.6 | 1.000 | 1.000 | 1.000 | 0.898 | 0.830 | 0.782 | 0.694 | 0.646 | 0.588 | 0.560 |
| 0.7 | 1.000 | 1.000 | 1.000 | 0.922 | 0.870 | 0.830 | 0.754 | 0.706 | 0.654 | 0.630 |
| 0.8 | 1.000 | 1.000 | 1.000 | 0.946 | 0.910 | 0.878 | 0.818 | 0.782 | 0.734 | 0.710 |
| 0.9 | 1.000 | 1.000 | 1.000 | 0.970 | 0.950 | 0.934 | 0.902 | 0.878 | 0.846 | 0.830 |
| 1.0 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 | 1.000 |
| | | | | | | | | | | |
| Wali Input Vali | ues | | | | Force Input V | /alue | | | | |
| Height of Wall | | h (ft) | 8 | | Shear Force a | pplied to Wall | V (lbs) | 3606 | _ | |
| Maximum Oper | ning Height | h _o (ft) | 5 | | | | | | | |
| Width of Wall (1 | total) | b (ft) | 57.75 | | | | | | | |
| Sum of Wall Op | pening Width | b _o (ft) | 17 | | Unit Shear Ca | alculation | | | | |
| | | | | | Remaining Pie | er Length * Co | b _{fh} * C _o (ft) | 32.69 | _ | |
| | | | | | Unit Shear, V | / Pier length | v (lb/ft) | 110.32 | | |
| | oration Reduct | | | | | - | · · | | | |
| Max Opening H | lgt / Wall Hgt | h/h₀ | 0.63 | | Side 1: Sheat | hing: 1/2" OSB | | | | |
| Shear Wall Ren | naining (piers) | b _{íh} (ft) | 40.75 | | Length | | L (ft) | 32.69 | — | |
| Pier length / wa | dl length | b _{fh} / b | 0.706 | | Unit Shear Ca | pacity | v (lb/ft) | 80 | 8d Nail @ 6/ | /12 Pattern |
| Perforation fact | or | C ₀ (ft) | 0.802 | | | | | | | |
| | | | | | | hing: 1/2" Gyp. B | | | | |
| *Perforation Fa | ctor is from Dou | ble Intertoplat | tion of C _o Table | | Length | | L (ft) | 32.69 | _ | |
| | | | | | Unit Shear Ca | pacity | v (lb/ft) | 80 | #6 Screw @ | 8/12 Pattern |
| Hold-down For | | | | | | | | | | |
| Length betweer Tension Force | 1 Hold-downs | L (ft) | 57.5 | | Total Force C | | V (lbs) | 5229.7 | > 3606 | 0.К. |
| Tension Force | | T (lbs) | 501.70 | | Equivalent Ur | nit Shear | v (lb/ft) | 160 | > 110.325 | О.К. |
| | | | | | | | | | | |
| | sum the sheath | | | | <u> </u> | | | | | _ |
| i | of the two must | | wice the | | Gypsum is s | crewed at 16" C | C at edge joint | t along hor | izontal butt j | oints |
| lowest unit snea | ar of the two mat | terials. | | | | | | | | |





Architects • Engineers • Planners Project No.: 13-159

Date: May 4, 2013 Sheet____of___

| Anchorage to Foundation Walls except garage overhead door | wall | | |
|--|----------------------|------------------|--|
| Force Worst Case = | 378 1950 lbs | plf | Worst case From Shear Wall |
| Simpson Titen HD = | 1950 105 | 5.16 | ft. Spacing |
| Direct Wind Pressure= -14.4*4.5' | 51.75 psf | | |
| Shear Force= SQRT (J13^2+J9^2) | 381.526 | plf 5.11 | ft. Spacing |
| | | | |
| Use 1/2" dia AB or Simpson 1/2"Diax6" Titen H | D Anchors @ 4 | +'-0" <u>O</u> . | C. at walls wiyhout OH drs |
| Use 1/2" dia AB or Simpson 1/2"Diax6" Titen H Garage overhead door wall | D Anchors @ 4 | ł'-0" O. | C. at walls wiyhout OH drs |
| | D Anchors @ 4 621 | <u>+'-0" 0.</u> | C. at walls wiyhout OH drs Worst case From Shear Wall |
| Garage overhead door wall | | | |
| Garage overhead door wall Force Worst Case = | 621 | | |
| Garage overhead door wall Force Worst Case = | 621 1950 lbs | plf | Worst case From Shear Wall |
| Garage overhead door wall Force Worst Case = Simpson Titen HD = | 621 1950 lbs | plf | Worst case From Shear Wall |

FORTE 10B SUMMARY REPORT

ā

| JOB SUM | MARY REPORT |
|---------|------------------|
| 13-159 | WOOD FRAMING.4te |

| 01: First Floor-Floor Framing | Sig ⁵ ₩, s | | |
|---|--|--|---------------------------------------|
| Member Name | Results | Current Solution | Comments |
| Floor: Joist J-1 | Passed | 1 Piece(s) 11 7/8" TJI® 230 @ 16" OC | |
| Floor: Joist J-2 | Passed | 1 Piece(s) 11 7/8" TJI® 230 @ 16" OC | |
| Floor: Joist J-3 | Passed | 1 Piece(s) 11 7/8" TJI® 230 @ 16" OC | |
| Floor: Joist J-4 | Passed | 1 Piece(s) 11 7/8" TJI® 230 @ 16" OC | |
| Floor: Joist J-5 | Passed | 1 Piece(s) 11 7/8" TJI® 230 @ 16" OC | |
| Floor: Joist J-6 | Passed | 1 Piece(s) 11 7/8" TJI® 560 @ 16" OC | |
| Optional Floor: Joist J-6 | Passed | 1 Piece(s) 11 7/8" TJI® 230 @ 12" OC | |
| 02: second Floor-Roof support headers | | | |
| Member Name | Results | Current Solution | Comments |
| Wall: Header H-201 | Passed | 2 Piece(s) 2 x 6 Spruce-Pine-Fir No. 1 / No. 2 | |
| Wall: Header H-202 | Passed | 2 Piece(s) 2 x 6 Spruce-Pine-Fir No. 1 / No. 2 | |
| Wall: Header H-203 | Passed | 2 Piece(s) 2 x 6 Spruce-Pine-Fir No. 1 / No. 2 | |
| Wall: Header H-204 | Passed | 2 Piece(s) 2 x 12 Spruce-Pine-Fir No. 1 / No. 2 | |
| Wall: Header H-205 | Passed | 2 Piece(s) 1 3/4" x 9 1/2" 2.0E Parallam® PSL | |
| Wall: Header H-206 | Passed | 2 Piece(s) 1 3/4" x 9 1/2" 2.0E Parallam® PSL | · · · · · · · · · · · · · · · · · · · |
| Wall: Header H-207 | Passed | 2 Piece(s) 2 x 4 Spruce-Pine-Fir No. 1 / No. 2 | |
| Wall: Header H-208 | Passed | 2 Piece(s) 2 x 4 Spruce-Pine-Fir No. 1 / No. 2 | |
| Wall: Header H-209 | Passed | 2 Piece(s) 1 3/4" x 9 1/2" 2.0E Parallam® PSL | |
| Wall: Header H-210 | Passed | 2 Piece(s) 1 3/4" x 9 1/2" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 9 1/2" 2.0E Parallam® PSL | |
| Wall: Header H-211 | Passed | 2 Piece(s) 2 x 6 Spruce-Pine-Fir No. 1 / No. 2 | |
| Roof: Flush Beam H-212 | Passed | 3 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL | |
| Roof: Flush Beam H-213 | Passed | | |
| Roof: Flush Beam H-214 | Passed | 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL | |
| Wall: Header H-215 | Passed | 1 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL | |
| 03: second floor-Floor support | Fasseu | 2 Piece(s) 2 x 10 Spruce-Pine-Fir No. 1 / No. 2 | |
| Member Name | Begulta | | |
| Wall: Header H-1 | Results Passed | Current Solution | Comments |
| Wall: Header H-2 | Passed | 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL | |
| Wall: Header H-3 | Passed | 2 Piece(s) 2 x 12 Spruce-Pine-Fir No. 1 / No. 2 | |
| Wall: Header H-4 | 1 | 2 Piece(s) 2 x 12 Spruce-Pine-Fir No. 1 / No. 2 | |
| Wall: Header H-5 | Passed Passed | 2 Piece(s) 2 x 6 Spruce-Pine-Fir No. 1 / No. 2 | |
| Wall: Header H-6 | Passed | 2 Piece(s) 2 x 6 Spruce-Pine-Fir No. 1 / No. 2 | |
| Wall: Header H-7 | - | 2 Piece(s) 2 x 8 Spruce-Pine-Fir No. 1 / No. 2 | |
| Wall: Header H-8 | Passed Passed | 2 Piece(s) 2 x 8 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL | |
| Wall, fieduel 11-0 | Passeu | Z PIECE(S) I 3/4 X II 7/8 Z.UE Parallamiki PSI. | |
| Walls Header H 0 | Decod | | |
| Wall: Header H-9 | Passed | 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL | |
| Wall: Header H-10 | Passed | 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL | |
| Wall: Header H-10 Wall: Header H-11 | Passed Passed | 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 2 x 8 Spruce-Pine-Fir No. 1 / No. 2 | |
| Wall: Header H-10 Wall: Header H-11 Wall: Header H-12 | Passed Passed Passed | 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 2 x 8 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 12 Spruce-Pine-Fir No. 1 / No. 2 | |
| Wall: Header H-10 Wall: Header H-11 Wall: Header H-12 Wall: Header H-13 | Passed Passed Passed Passed | 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 2 x 8 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 12 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 6 Spruce-Pine-Fir No. 1 / No. 2 | |
| Wall: Header H-10 Wall: Header H-11 Wall: Header H-12 Wall: Header H-13 Wall: Header H-14 | Passed Passed Passed Passed Passed | 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 2 x 8 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 12 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 6 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL | |
| Wall: Header H-10 Wall: Header H-11 Wall: Header H-12 Wall: Header H-13 Wall: Header H-14 Wall: Header H-15 | Passed Passed Passed Passed Passed Passed | 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 2 x 8 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 12 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 6 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 9 1/2" 2.0E Parallam® PSL | |
| Wall: Header H-10 Wall: Header H-11 Wall: Header H-12 Wall: Header H-13 Wall: Header H-14 Wall: Header H-15 Wall: Header H-16 | Passed Passed Passed Passed Passed Passed Passed | 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 2 x 8 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 12 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 6 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 9 1/2" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL | |
| Wall: Header H-10 Wall: Header H-11 Wall: Header H-12 Wall: Header H-13 Wall: Header H-14 Wall: Header H-15 Wall: Header H-16 Wall: Header H-17 | Passed Passed Passed Passed Passed Passed Passed Passed | 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 2 x 8 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 12 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 6 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 9 1/2" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 2 x 8 Spruce-Pine-Fir No. 1 / No. 2 | |
| Wall: Header H-10 Wall: Header H-11 Wall: Header H-12 Wall: Header H-13 Wall: Header H-14 Wall: Header H-15 Wall: Header H-16 Wall: Header H-17 Wall: Header H-18 | Passed Passed Passed Passed Passed Passed Passed Passed Passed Passed | 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 2 x 8 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 12 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 6 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 9 1/2" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 2 x 8 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 8 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL | |
| Wall: Header H-10 Wall: Header H-11 Wall: Header H-12 Wall: Header H-13 Wall: Header H-13 Wall: Header H-14 Wall: Header H-15 Wall: Header H-16 Wall: Header H-17 Wall: Header H-18 Wall: Header H-19 | Passed Passed Passed Passed Passed Passed Passed Passed Passed Passed Passed | 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 2 x 8 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 12 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 6 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 9 1/2" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 2 x 8 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 2 x 8 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 10 Spruce-Pine-Fir No. 1 / No. 2 | |
| Wall: Header H-10 Wall: Header H-11 Wall: Header H-12 Wall: Header H-12 Wall: Header H-13 Wall: Header H-14 Wall: Header H-15 Wall: Header H-16 Wall: Header H-17 Wall: Header H-18 Wall: Header H-19 Wall: Header H-20 | Passed Passed Passed Passed Passed Passed Passed Passed Passed Passed Passed Passed Passed | 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 2 x 8 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 12 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 6 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 9 1/2" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 2 x 8 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 2 x 8 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 10 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 10 Spruce-Pine-Fir No. 1 / No. 2 | |
| Wall: Header H-10 Wall: Header H-11 Wall: Header H-12 Wall: Header H-12 Wall: Header H-13 Wall: Header H-14 Wall: Header H-15 Wall: Header H-16 Wall: Header H-17 Wall: Header H-18 Wall: Header H-19 Wall: Header H-20 Floor: Flush Beam H-21 | Passed Passed Passed Passed Passed Passed Passed Passed Passed Passed Passed Passed Passed Passed Passed | 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 2 x 8 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 12 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 6 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 9 1/2" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 9 1/2" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 2 x 8 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 2 x 8 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 10 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 10 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL | |
| Wall: Header H-10 Wall: Header H-11 Wall: Header H-12 Wall: Header H-12 Wall: Header H-13 Wall: Header H-14 Wall: Header H-15 Wall: Header H-16 Wall: Header H-16 Wall: Header H-17 Wall: Header H-18 Wall: Header H-19 Wall: Header H-20 Floor: Flush Beam H-21 Floor: Flush Beam H-22 | Passed Passed Passed Passed Passed Passed Passed Passed Passed Passed Passed Passed Passed Passed Passed Passed | 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 2 x 8 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 12 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 6 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 9 1/2" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 2 x 8 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 10 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL | |
| Wall: Header H-10 Wall: Header H-11 Wall: Header H-12 Wall: Header H-12 Wall: Header H-13 Wall: Header H-14 Wall: Header H-15 Wall: Header H-16 Wall: Header H-16 Wall: Header H-17 Wall: Header H-18 Wall: Header H-19 Wall: Header H-19 Wall: Header H-20 Floor: Flush Beam H-21 Floor: Flush Beam H-22 Floor: Flush Beam H-23 | Passed | 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 2 x 8 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 12 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 6 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 9 1/2" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 2 x 8 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 10 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 10 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL | |
| Wall: Header H-10 Wall: Header H-11 Wall: Header H-12 Wall: Header H-13 Wall: Header H-13 Wall: Header H-14 Wall: Header H-15 Wall: Header H-16 Wall: Header H-16 Wall: Header H-17 Wall: Header H-17 Wall: Header H-19 Wall: Header H-19 Wall: Header H-20 Floor: Flush Beam H-21 Floor: Flush Beam H-22 Floor: Flush Beam H-23 Floor: Flush Beam H-24 | Passed | 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 2 x 8 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 12 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 6 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 9 1/2" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 2 x 8 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 10 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL | |
| Wall: Header H-10 Wall: Header H-11 Wall: Header H-12 Wall: Header H-13 Wall: Header H-13 Wall: Header H-14 Wall: Header H-15 Wall: Header H-16 Wall: Header H-16 Wall: Header H-17 Wall: Header H-17 Wall: Header H-19 Wall: Header H-19 Wall: Header H-20 Floor: Flush Beam H-21 Floor: Flush Beam H-22 Floor: Flush Beam H-23 Floor: Flush Beam H-24 Floor: Flush Beam H-25 | Passed | 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 2 x 8 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 12 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 6 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 9 1/2" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 2 x 8 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 10 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL | |
| Wall: Header H-10Wall: Header H-11Wall: Header H-12Wall: Header H-13Wall: Header H-13Wall: Header H-14Wall: Header H-15Wall: Header H-16Wall: Header H-16Wall: Header H-17Wall: Header H-18Wall: Header H-19Wall: Header H-20Floor: Flush Beam H-21Floor: Flush Beam H-22Floor: Flush Beam H-23Floor: Flush Beam H-24Floor: Flush Beam H-25Floor: Flush Beam H-26 | Passed Pa | 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 2 x 8 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 12 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 6 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 2 x 8 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 10 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 2 x 10 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 4 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL | |
| Wall: Header H-10Wall: Header H-11Wall: Header H-12Wall: Header H-13Wall: Header H-13Wall: Header H-14Wall: Header H-15Wall: Header H-16Wall: Header H-16Wall: Header H-17Wall: Header H-17Wall: Header H-18Wall: Header H-19Wall: Header H-20Floor: Flush Beam H-21Floor: Flush Beam H-22Floor: Flush Beam H-23Floor: Flush Beam H-24Floor: Flush Beam H-25Floor: Flush Beam H-26Wall: Header H-27 | Passed Pa | 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 2 x 8 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 12 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 6 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 9 1/2" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 2 x 8 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 10 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 2 x 10 Spruce-Pine-Fir No. 1 / No. 2 | |
| Wall: Header H-10 Wall: Header H-11 Wall: Header H-12 Wall: Header H-13 Wall: Header H-13 Wall: Header H-14 Wall: Header H-15 Wall: Header H-16 Wall: Header H-17 Wall: Header H-18 Wall: Header H-19 Wall: Header H-20 Floor: Flush Beam H-21 Floor: Flush Beam H-22 Floor: Flush Beam H-23 Floor: Flush Beam H-24 Floor: Flush Beam H-25 Floor: Flush Beam H-26 | Passed Pa | 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 2 x 8 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 12 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 6 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 2 x 8 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 2 x 10 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 2 x 10 Spruce-Pine-Fir No. 1 / No. 2 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 2 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL 4 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL | |

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:35 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

Page 1 of 54

| • | 04: First floor-Floor framing | | ann ann an Aonaichtean an Aonaichtean an Aonaichtean an Aonaichtean an Aonaichtean an Aonaichtean an Aonaichtea Anna Aonaichtean an Ao | 1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1. | |
|---|-------------------------------|---------|---|--|------------------|
| | Member Name | Results | Current Solution | Comments | - ² 1 |
| | Floor: Flush Beam | Passed | 3 Piece(s) 1 3/4" x 11 7/8" 2.0E Parallam® PSL | · · · · · · · · · · · · · · · · · · · | |

5


•

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

·· ·

5/3/2013 10:07:36 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

Page 2 of 54



| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|-------------------|--------------|----------------|------|-----------------------------|
| Member Reaction (lbs) | 757 @ 18' 6 1/2" | 1485 (3.50") | Passed (51%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Shear (lbs) | 720 @ 5 1/2" | 1655 | Passed (44%) | | 1.0 D + 1.0 L (All Spans) |
| Moment (Ft-lbs) | 3300 @ 9' 5 1/2" | 4215 | Passed (78%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Live Load Defl. (in) | 0.350 @ 9' 5 1/2" | 0.606 | Passed (L/623) | | 1.0 D + 1.0 L (All Spans) |
| Total Load Defl. (in) | 0.525 @ 9' 5 1/2" | 0.908 | Passed (L/415) | | 1.0 D + 1.0 L (All Spans) |
| TJ-Pro™ Rating | 43 | Anv | Passed | | |

System : Floor Member Type : Joist Building Use : Residential Building Code : IBC Design Methodology : ASD

SUSTAINABLE FORESTRY INITIATIVE

• Deflection criteria: LL (L/360) and TL (L/240).

 Bracing (Lu): All compression edges (top and bottom) must be braced at 4' 15/16" o/c unless detailed otherwise. Proper attachment and positioning of lateral bracing is required to achieve member stability.

bracing is required to achieve member stability. • A structural analysis of the deck has not been performed.

• Deflection analysis is based on composite action with a single layer of 23/32" Weyerhaeuser Edge™ Panel (24" Span Rating) that is glued and nailed down.

• Additional considerations for the TJ-Pro™ Rating include: 1/2" Gypsum ceiling.

| | 1 1.0 p 4 ⁰ 1 | Bearing | 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 | . Load | s to Suppor | ts (lbs) 🙏 | | |
|-----------------------------|-----------------------------|-----------|---------------------------------------|--------|---------------|------------|------------------|---|
| Supports | Total | Available | Required | Dead | Floor Live | Total | Accessories | |
| 1 - Plate on concrete - SPF | 5.50" | 4.25" | 1.75" | 252 | 504 | 756 | 1 1/4" Rim Board | _ |
| 2 - Plate on steel - SPF | 5.50" | 5.50" | 1.75" | 252 | 504 | 756 | Blocking | |

Rim Board is assumed to carry all loads applied directly above it, bypassing the member being designed.

Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

| Loads | Location | Spacing | Dead (0.90) | Floor Live (1.00) | Comments |
|------------------|--------------|---------|----------------|-------------------|----------------------------|
| 1 - Uniform(PSF) | 0 to 18' 11" | 16" | 20.0 | 40.0 | Residential - Living Areas |

Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.

The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:36 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te





| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|--------------------|--------------|----------------|------|-----------------------------|
| Member Reaction (lbs) | 717 @ 17' 6 1/2" | 1485 (3.50") | Passed (48%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Shear (lbs) | 680 @ 17' 5 1/2" | 1655 | Passed (41%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Moment (Ft-lbs) | 2947 @ 8' 11 1/2" | 4215 | Passed (70%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Live Load Defl. (in) | 0.283 @ 8' 11 1/2" | 0.572 | Passed (L/729) | | 1.0 D + 1.0 L (All Spans) |
| Total Load Defl. (in) | 0.424 @ 8' 11 1/2" | 0.858 | Passed (L/486) | | 1.0 D + 1.0 L (All Spans) |
| TJ-Pro™ Rating | 46 | Any | Passed | | |

System : Floor Member Type : Joist Building Use : Residential Building Code : IBC Design Methodology : ASD

• Deflection criteria: LL (L/360) and TL (L/240).

· Bracing (Lu): All compression edges (top and bottom) must be braced at 4' 3 13/16" o/c unless detailed otherwise. Proper attachment and positioning of lateral bracing is required to achieve member stability.
A structural analysis of the deck has not been performed.

Deflection analysis is based on composite action with a single layer of 23/32" Weyerhaeuser Edge[™] Panel (24" Span Rating) that is glued and nailed down.

• Additional considerations for the TJ-Pro'" Rating include: 1/2" Gypsum ceiling.

| ⁱ , g · ^ν − ^ν − s | | Bearing | e | Load | s to Suppor | ts (lbs) | 4 | |
|--|-------|-----------|----------|------|---------------|----------|------------------|---------|
| Supports | Total | Available | Required | Dead | Floor Live | Total | Accessories | л). |
| 1 - Plate on concrete - SPF | 5.50" | 4.25" | 1.75" | 239 | 478 | 717 | 1 1/4" Rim Board | |
| 2 - Plate on steel - SPF | 5.50" | 5.50" | 1.75" | 239 | 478 | 717 | Blocking | |

Rim Board is assumed to carry all loads applied directly above it, bypassing the member being designed.

Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

| Loads | Location | Spacing | Dead (0.90) | Floor Live (1.00) | Comments | |
|------------------|--------------|---------|----------------|----------------------|----------------------------|--|
| 1 - Uniform(PSF) | 0 to 17' 11" | 16" | 20.0 | 40.0 | Residential - Living Areas | |

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Southable for the defined to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.


The product application, input design loads, dimensions and support information have been provided by Forte Software Operator


| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:36 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

Page 4 of 54

BUSTAINABLE FORESTRY INITIATIVE





| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|--------------------|--------------|----------------|------|-----------------------------|
| Member Reaction (lbs) | 797 @ 19' 6 1/2" | 1485 (3.50") | Passed (54%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Shear (lbs) | 760 @ 19' 5 1/2" | 1655 | Passed (46%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Moment (Ft-Ibs) | 3674 @ 9' 11 1/2" | 4215 | Passed (87%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Live Load Defl. (in) | 0.429 @ 9' 11 1/2" | 0.639 | Passed (L/537) | | 1.0 D + 1.0 L (All Spans) |
| Total Load Defl. (in) | 0.643 @ 9' 11 1/2" | 0.958 | Passed (L/358) | | 1.0 D + 1.0 L (All Spans) |
| TI-Pro™ Ratino | 41 | Anv | Passed | | |

System : Floor Member Type : Joist Building Use : Residential Building Code : IBC Design Methodology : ASD

• Deflection criteria: LL (L/360) and TL (L/240).

· Bracing (Lu): All compression edges (top and bottom) must be braced at 3' 10 7/16" o/c unless detailed otherwise. Proper attachment and positioning of lateral bracing is required to achieve member stability.A structural analysis of the deck has not been performed.

• Deflection analysis is based on composite action with a single layer of 23/32" Weyerhaeuser EdgeTM Panel (24" Span Rating) that is glued and nailed down.

Additional considerations for the TJ-Pro[™] Rating include: 1/2" Gypsum ceiling.

| | Bearing | | | Load | s to Suppor | ts (lbs) | |
|-----------------------------|---------|-----------|----------|------|---------------|----------|------------------|
| Supports | Total | Available | Required | Dead | Floor Live | Total | Accessories |
| 1 - Plate on concrete - SPF | 5.50" | 4.25" | 1.75" | 266 | 531 | 797 | 1 1/4" Rim Board |
| 2 - Plate on concrete - SPF | 5.50" | 5.50" | 1.75" | 266 | 531 | 797 | Blocking |

Rim Board is assumed to carry all loads applied directly above it, bypassing the member being designed.

• Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

| Loads | Location | Spacing | Dead (0.90) | Floor Live (1.00) | Comments |
|------------------|--------------|---------|----------------|----------------------|----------------------------|
| 1 - Uniform(PSF) | 0 to 19' 11" | 16" | 20.0 | 40.0 | Residential - Living Areas |

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.


The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:37 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

SUSTAINABLE FORESTRY INITIATIVE

Overall Length: 20' 5"



All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal.; Drawing is Conceptual

| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|--------------------|--------------|----------------|------|-----------------------------|
| Member Reaction (lbs) | 817 @ 20' 1/2" | 1485 (3.50") | Passed (55%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Shear (lbs) | 780 @ 19' 11 1/2" | 1655 | Passed (47%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Moment (Ft-lbs) | 3868 @ 10' 2 1/2" | 4215 | Passed (92%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Live Load Defl. (in) | 0.473 @ 10' 2 1/2" | 0.656 | Passed (L/499) | | 1.0 D + 1.0 L (All Spans) |
| Total Load Defl. (in) | 0.709 @ 10' 2 1/2" | 0.983 | Passed (L/333) | | 1.0 D + 1.0 L (All Spans) |
| TJ-Pro™ Rating | 38 | Any | Passed | | |

System : Floor Member Type : Joist Building Use : Residential Building Code : IBC Design Methodology : ASD

SUSTAINABLE FORESTRY INITIATIVE

Deflection criteria: LL (L/360) and TL (L/240).

• Bracing (Lu): All compression edges (top and bottom) must be braced at 3' 9 1/4" o/c unless detailed otherwise. Proper attachment and positioning of lateral bracing is required to achieve member stability.

A structural analysis of the deck has not been performed.

Deflection analysis is based on composite action with a single layer of 23/32" Weyerhaeuser Edge[™] Panel (24" Span Rating) that is glued and nailed down.

• Additional considerations for the TJ-Pro[™] Rating include: 1/2" Gypsum ceiling.

| ra a a a a a a a a a a a a a a a a a a | · | Bearing | · · · · · | Load | s to Suppor | ts (lbs) | - ^{- 1} - |
|--|--------------------|-----------|-----------|------|---------------|----------|--------------------|
| Supports | Total [*] | Available | Required | Dead | Floor Live | Total | Accessories |
| 1 - Plate on steel - SPF | 5.50" | 4.25" | 1.75" | 272 | 544 | 816 | 1 1/4" Rim Board |
| 2 - Plate on concrete - SPF | 5.50" | 5.50" | 1.75" | 272 | 544 | 816 | Blocking |

Rim Board is assumed to carry all loads applied directly above it, bypassing the member being designed.

• Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

| Loads | Location | Spacing | Dead (0.90) | FIGOLINE | Comments |
|------------------|-------------|---------|----------------|----------|----------------------------|
| 1 - Uniform(PSF) | 0 to 20' 5" | 16" | 20.0 | 40.0 | Residential - Living Areas |

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.


The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:37 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

Page 6 of 54

Overall Length: 8' 9"



All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal.; Drawing is Conceptual

| Design Results | Actual @ Location | Allowed | Result | . LDF | Load: Combination (Pattern) |
|-----------------------|-------------------|--------------|---------------------|-------|-------------------------------------|
| Member Reaction (lbs) | 819 @ 2' 2 3/4" | 2790 (5.25") | Passed (29%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Shear (lbs) | 460 @ 2' | 1655 | Passed (28%) | _ | 1.0 D + 1.0 L (All Spans) |
| Moment (Ft-lbs) | -568 @ 2' 2 3/4" | 4215 | Passed (13%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Live Load Defl. (in) | 0.009.@ 0 | 0.200 | Passed (2L/999+) | | 1.0 D + 0.75 L + 0.75 S (Alt Spans) |
| Total Load Defl. (in) | 0.025 @ 0 | 0.223 | Passed (2L/999+) | | 1.0 D + 0.75 L + 0.75 S (Alt Spans) |
| TJ-Pro™ Rating | 71 | Anv | Passed | | |

System : Floor Member Type : Joist Building Use : Residential Building Code : IBC Design Methodology : ASD

Deflection criteria: LL (L/360) and TL (L/240).

Overhang deflection criteria: LL (0.2") and TL (2L/240).

* Bracing (Lu): All compression edges (top and bottom) must be braced at 8' 5 1/2" o/c unless detailed otherwise. Proper attachment and positioning of lateral bracing is required to achieve member stability.A structural analysis of the deck has not been performed.

• Deflection analysis is based on composite action with a single layer of 23/32" Weyerhaeuser EdgeTM Panel (24" Span Rating) that is glued and nailed down.

• Additional considerations for the TJ-ProTM Rating include: 1/2" Gypsum ceiling.

| а | | Bearing | , , – | | Load | | | | |
|--------------------------------|-------|---------------------|----------|------|---------------|--------------|------|---------|-------------|
| Supports | Total | Available | Required | Dead | Floor Live | Roof Live | Snow | Total | Accessories |
| 1 - Stud wall - SPF | 5.50" | 5.50" | 3.50" | 512 | 306 | 96 | 144 | 1058 | Blocking |
| 2 - Hanger on 11 7/8" PSL beam | 3.50" | Hanger ¹ | 1.75" | 21 | 182/-6 | -16 | -24 | 203/-46 | See note 1 |

Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

• At hanger supports, the Total Bearing dimension is equal to the width of the material that is supporting the hanger

¹ See Connector grid below for additional information and/or requirements.

| Connector: Simp | pson Strong-Ti | ie Connectors | · · · · | | * | 5 ¹ | | - | |
|------------------------|----------------|---------------|----------------|----------------------|-------------------------------|----------------|---------------|--------------|-------------|
| Support | | Model | | Seat Length | Top Nails | Fac | e Nails | Member Nails | Accessories |
| 2 - Face Mount Hanger | | IUS2.37/11.88 | | 2.00" | N/A | 10-10 | d x 1-1/2 | N/A | |
| Loads | Location | "Spacing | Dead (0.90) | Floor Live (1.00) | Roof Live (non-snow: 1.25) | Snow (1.15) | Comments | | |
| 1 - Uniform(PSF) | 0 to 8' 9" | 16" | 20.0 | 40.0 | | - | Residential - | Living Areas | - |
| 2 - Uniform(PLF) | 0 to 2' | N/A | 150.0 | - | 40.0 | 60.0 | 1 | | 1 |

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.

The product application, input design loads, dimensions and support information have been provided by Forte Software Operator


| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:38 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

SUSTAINABLE FORESTRY INITIATIVE

Page 7 of 54





| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|---------------------|--------------|----------------|------|-----------------------------|
| Member Reaction (lbs) | 884 @ 4 1/2" | 1725 (3.50") | Passed (51%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Shear (lbs) | 856 @ 5 1/2" | 2050 | Passed (42%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Moment (Ft-lbs) | 4652 @ 11' 1 15/16" | 9500 | Passed (49%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Live Load Defl. (in) | 0.451 @ 11' 8 5/16" | 0.772 | Passed (L/616) | | 1.0 D + 1.0 L (All Spans) |
| Total Load Defl. (in) | 0.677 @ 11' 8 5/16" | 1.158 | Passed (L/411) | | 1.0 D + 1.0 L (All Spans) |
| TJ-Pro™ Rating | 36 | Anv | Passed | | |

System : Floor Member Type : Joist Building Use : Residential Building Code : IBC Design Methodology : ASD

• Deflection criteria: LL (L/360) and TL (L/240).

• Bracing (Lu): All compression edges (top and bottom) must be braced at 7' 1 9/16" o/c unless detailed otherwise. Proper attachment and positioning of lateral

bracing is required to achieve member stability. • A structural analysis of the deck has not been performed.

Deflection analysis is based on composite action with a single layer of 23/32" Weyerhaeuser Edge™ Panel (24" Span Rating) that is glued and nailed down.

Additional considerations for the TJ-Pro™ Rating include: 1/2" Gypsum ceiling.

| | | Bearing | | | s to Suppor | ts (ibs) | • • |
|---------------------|-------|-----------|----------|------|-----------------|----------|------------------|
| Supports | Total | Available | Required | Dead | ° Floor Live | Total | Accessories |
| 1 - Stud wall - SPF | 5.50" | 4.25" | 1.75" | 298 | 595 | 893 | 1 1/4" Rim Board |
| 2 - Stud wall - SPF | 5.50" | 5.50" | 1.75" | 168 | 336 | 504 | Blocking |

Rim Board is assumed to carry all loads applied directly above it, bypassing the member being designed.

• Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

| Loads | Location | Spacing | Dead (0.90) | Floor Live (1.00) | Comments |
|------------------|-----------------|---------|----------------|----------------------|----------------------------|
| 1 - Uniform(PSF) | 0 to 17' 5 1/2" | 16" | 20.0 | 40.0 | Residential - Living Areas |

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.


The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Assoclates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:38 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

Page 8 of 54

Overall Length: 23' 11"



All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal.;Drawing is Conceptual

| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|---------------------|--------------|----------------|------|-----------------------------|
| Member Reaction (lbs) | 663 @ 4 1/2" | 1485 (3.50") | Passed (45%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Shear (lbs) | 642 @ 5 1/2" | 1655 | Passed (39%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Moment (Ft-Ibs) | 3489 @ 11' 1 15/16" | 4215 | Passed (83%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Live Load Defl. (in) | 0.578 @ 11' 8 5/16" | 0.772 | Passed (L/481) | | 1.0 D + 1.0 L (All Spans) |
| Total Load Defl. (in) | 0.867 @ 11' 8 5/16" | 1.158 | Passed (L/321) | | 1.0 D + 1.0 L (All Spans) |
| TJ-Pro™ Rating | 30 | Anv | Passed | | |

System : Floor Member Type : Joist Building Use : Residential Building Code : IBC Design Methodology : ASD

• Deflection criteria: LL (L/360) and TL (L/240).

Bracing (Lu): All compression edges (top and bottom) must be braced at 3' 11 5/8" o/c unless detailed otherwise. Proper attachment and positioning of lateral bracing is required to achieve member stability.

bracing is required to achieve member stability. • A structural analysis of the deck has not been performed.

• Deflection analysis is based on composite action with a single layer of 23/32" Weyerhaeuser EdgeTM Panel (24" Span Rating) that is glued and nailed down.

Additional considerations for the TJ-Pro[™] Rating include: 1/2" Gypsum ceiling.

| B with of the second se | | Bearing | | | s to Suppor | ts (lbs) | 8 |
|--|-------|-----------|----------|------|---------------|----------|------------------|
| Supports | Total | Available | Required | Dead | Floor Live | Total | Accessories |
| 1 - Stud wall - SPF | 5.50" | 4.25" | 1.75" | 223 | 446 | 669 | 1 1/4" Rim Board |
| 2 - Stud wall - SPF | 5.50" | 5.50" | 1.75" | 126 | 252 | 378 | Blocking |

Rim Board is assumed to carry all loads applied directly above it, bypassing the member being designed.


· Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

| Loads | Location | Spacing | Dead (0.90) | Floor Live (1.00) | Comments |
|------------------|-----------------|---------|----------------|----------------------|----------------------------|
| 1 - Uniform(PSF) | 0 to 17' 5 1/2" | 12" | 20.0 | 40.0 | Residential - Living Areas |

Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.


The product application, input design loads, dimensions and support information have been provided by Forte Software Operator



5/3/2013 10:07:39 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

Page 9 of 54





| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|--------------------|--------------|-----------------|------|-----------------------------|
| Member Reaction (lbs) | 195 @ 0 | 1913 (1.50") | Passed (10%) | | 1.0 D + 1.0 S (All Spans) |
| Shear (ibs) | 135 @ 7" | 1708 | Passed (8%) | 1.15 | 1.0 D + 1.0 S (All Spans) |
| Moment (Ft-lbs) | 183 @ 1' 10 1/2" | 1649 | Passed (11%) | 1.15 | 1.0 D + 1.0 S (All Spans) |
| Live Load Defl. (in) | 0.005 @ 1' 10 1/2" | 0.125 | Passed (L/999+) | | 1.0 D + 1.0 S (All Spans) |
| Total Load Defl. (in) | 0.008 @ 1' 10 1/2" | 0.188 | Passed (L/999+) | | 1.0 D + 1.0 S (All Spans) |

System : Wall Member Type : Header Building Use : Residential Building Code : IBC Design Methodology : ASD

SUSTAINABLE FORESTRY INITIATIVE

Deflection criteria: LL (L/360) and TL (L/240).

· Bracing (Lu): All compression edges (top and bottom) must be braced at 3' 9" o/c unless detailed otherwise. Proper attachment and positioning of lateral

bracing is required to achieve member stability. • Applicable calculations are based on NDS 2005 methodology.

| $\begin{array}{cccccccccccccccccccccccccccccccccccc$ | | Bearing | а'н 5 ⁷ г. | к. у , Р к | Loads to S | upports (lb | 5) · | |
|--|-------|-----------|--------------------------|------------------|------------|-------------|-------|-------------|
| Supports | Total | Available | Required | Dead | Roof | Snow | Total | Accessories |
| 1 - Trimmer - SPF | 1.50" | 1.50" | 1.50" | 83 | 75 | 113 | 271 | None |
| 2 - Trimmer - SPF | 1.50" | 1.50" | 1.50" | 83 | 75 | 113 | 271 | None |

| Loads | Location | Tributary Width | Dead (0.90) | Roof Live (non-snow: 1.25) | Snow (1.15) | Comments |
|------------------|------------|--------------------|----------------|-------------------------------|----------------|----------------------------|
| 1 - Uniform(PSF) | 0 to 3' 9" | 2' | 20.0 | 20.0 | 30.0 | Residential - Living Areas |

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.


The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:39 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

Page 10 of 54





| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|-------------------|--------------|-----------------|------|-----------------------------|
| Member Reaction (lbs) | 326 @ 0 | 1913 (1.50") | Passed (17%) | | 1.0 D + 1.0 S (All Spans) |
| Shear (lbs) | 265 @ 5' 8" | 1708 | Passed (16%) | 1.15 | 1.0 D + 1.0 S (All Spans) |
| Moment (Ft-lbs) | 509 @ 3' 1 1/2" | 1649 | Passed (31%) | 1.15 | 1.0 D + 1.0 S (All Spans) |
| Live Load Defl. (in) | 0.035 @ 3' 1 1/2" | 0.208 | Passed (L/999+) | | 1.0 D + 1.0 S (All Spans) |
| Total Load Defl. (in) | 0.061 @ 3' 1 1/2" | 0.313 | Passed (L/999+) | | 1.0 D + 1.0 S (All Spans) |

System : Wall Member Type : Header Building Use : Residential Building Code : IBC Design Methodology : ASD

Deflection criteria: LL (L/360) and TL (5/16").

Bracing (Lu): All compression edges (top and bottom) must be braced at 6' 3" o/c unless detailed otherwise. Proper attachment and positioning of lateral
 because in provide the action of the provided to action of the p

bracing is required to achieve member stability. • Applicable calculations are based on NDS 2005 methodology.

| | | _ | Bearing | | - | | upports (lbs | · · · · · · | |
|-------------------|--------|-------|-----------|----------|------|--------------|--------------|-------------|-------------|
| Supports | d 1 | Total | Available | Required | Dead | Roof Live | Snow | Total | Accessories |
| 1 - Trimmer - SPF | | 1.50" | 1.50" | 1.50" | 138 | 125 | 188 | 451 | None |
| 2 - Trimmer - SPF | | 1.50" | 1.50" | 1.50" | 138 | 125 | 188 | 451 | None |

| Loads | Location | Tributary Width | Dead (0.90) | Roof Live | Snow (1.15) | Comments |
|------------------|------------|--------------------|----------------|-----------|----------------|----------------------------|
| 4 11-16 | | | <u> </u> | | | |
| 1 - Uniform(PSF) | 0 to 6' 3" | 2' | 20.0 | 20.0 | 30.0 | Residential - Living Areas |

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.


The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

SUSTAINABLE FORESTRY INITIATIVE

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:40 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te





| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|-------------------|--------------|-----------------|------|-----------------------------|
| Member Reaction (lbs) | 378 @ 0 | 1913 (1.50") | Passed (20%) | | 1.0 D + 1.0 S (All Spans) |
| Shear (lbs) | 317 @ 7" | 1708 | Passed (19%) | 1.15 | 1.0 D + 1.0 S (All Spans) |
| Moment (Ft-lbs) | 684 @ 3' 7 1/2" | 1649 | Passed (42%) | 1.15 | 1.0 D + 1.0 S (All Spans) |
| Live Load Defl. (in) | 0.064 @ 3' 7 1/2" | 0.242 | Passed (L/999+) | | 1.0 D + 1.0 S (All Spans) |
| Total Load Defl. (in) | 0.111 @ 3' 7 1/2" | 0.313 | Passed (L/782) | | 1.0 D + 1.0 S (All Spans) |

System : Wall Member Type : Header Building Use : Residential Building Code : IBC Design Methodology : ASD

• Deflection criteria: LL (L/360) and TL (5/16").

· Bracing (Lu): All compression edges (top and bottom) must be braced at 7' 3" o/c unless detailed otherwise. Proper attachment and positioning of lateral

bracing is required to achieve member stability. • Applicable calculations are based on NDS 2005 methodology.

| · · · · · · · · · · · · · · · · · · · | 1 1 | Bearing | * voe v - | | Loads to S | upports (lb | 5) | |
|---------------------------------------|-------|-----------|--------------|------|--------------|-------------|-------|-------------|
| Supports | Total | Available | Required | Dead | Roof Live | Snow | Total | Accessories |
| 1 - Trimmer - SPF | 1.50" | 1.50" | 1.50" | 160 | 145 | 218 | 523 | None |
| 2 - Trimmer - SPF | 1.50" | 1.50" | 1.50" | 160 | 145 | 218 | 523 | None |

| Loads | Location | Tributary Width | Dead (0.90) | Roof Live (non-snow: 1.25) | Snow (1.15) | Comments |
|------------------|------------|--------------------|----------------|-------------------------------|----------------|----------------------------|
| 1 - Uniform(PSF) | 0 to 7' 3" | 2' | 20.0 | 20.0 | 30.0 | Residential - Living Areas |

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclalms any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not Intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.


The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:40 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

Page 12 of 54





| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|-------------------|--------------|-----------------|------|-----------------------------|
| Member Reaction (lbs) | 2657 @ 1 1/2" | 3825 (3.00") | Passed (69%) | | 1.0 D + 1.0 S (All Spans) |
| Shear (lbs) | 1816 @ 6' 3 3/4" | 3493 | Passed (52%) | 1.15 | 1.0 D + 1.0 S (All Spans) |
| Moment (Ft-lbs) | 4655 @ 3' 9" | 5306 | Passed (88%) | 1.15 | 1.0 D + 1.0 S (All Spans) |
| Live Load Defl. (in) | 0.052 @ 3' 9" | 0.242 | Passed (L/999+) | | 1.0 D + 1.0 S (All Spans) |
| Total Load Defl. (in) | 0.088 @ 3' 9" | 0.363 | Passed (L/984) | | 1.0 D + 1.0 S (All Spans) |

System : Wall Member Type : Header Building Use : Residential Building Code : IBC Design Methodology : ASD

SUSTAINABLE FORESTRY INITIATIVE

Deflection criteria: LL (L/360) and TL (L/240).

· Bracing (Lu): All compression edges (top and bottom) must be braced at 6' 6 3/4" o/c unless detailed otherwise. Proper attachment and positioning of lateral

bracing is required to achieve member stability. • Applicable calculations are based on NDS 2005 methodology.

| 5. P | Bearing | | | | Loads to S | 4 v. , | | |
|-------------------|---------|-----------|----------|------|--------------|--------|-------|-------------|
| Supports | Total | Available | Required | Dead | Roof Live | Snow | Total | Accessories |
| 1 - Trimmer - SPF | 3.00" | 3.00" | 2.08" | 1082 | 1050 | 1575 | 3707 | None |
| 2 - Trimmer - SPF | 3.00" | 3.00" | 2.08" | 1082 | 1050 | 1575 | 3707 | None |

| Loads | Location | Tributary Width | Dead (0.90) | Roof Live (non-snow: 1.25) | Snow (1.15) | Comments |
|------------------|------------|--------------------|----------------|-------------------------------|----------------|----------------------------|
| 1 - Uniform(PSF) | 0 to 7' 6" | 14' | 20.0 | 20.0 | 30.0 | Residential - Living Areas |

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.


ε,

The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:41 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

Overall Length: 7' 9"



All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal.;Drawing is Conceptual

| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|--------------------|---------------|----------------|------|-----------------------------|
| Member Reaction (lbs) | 4109 @ 3" | 11419 (4.50") | Passed (36%) | | 1.0 D + 1.0 S (All Spans) |
| Shear (Ibs) | 2872 @ 6' 7" | 7393 | Passed (39%) | 1.15 | 1.0 D + 1.0 S (All Spans) |
| Moment (Ft-Ibs) | 6967 @ 3' 10 1/2" | 15016 | Passed (46%) | 1.15 | 1.0 D + 1.0 S (All Spans) |
| Live Load Defl. (in) | 0.093 @ 3' 10 1/2" | 0.242 | Passed (L/939) | | 1.0 D + 1.0 S (All Spans) |
| Total Load Defl. (in) | 0.156 @ 3' 10 1/2" | 0.363 | Passed (L/558) | | 1.0 D + 1.0 S (All Spans) |

System : Wall Member Type : Header Building Use : Residential Building Code : IBC Design Methodology : ASD

SUSTAINABLE FORESTRY INITIATIVE

• Deflection criteria: LL (L/360) and TL (L/240).

Bracing (Lu): All compression edges (top and bottom) must be braced at 7' 9" o/c unless detailed otherwise. Proper attachment and positioning of lateral bracing is required to achieve member stability.

| · · · · | Bearing | | | | Loads to S | | | |
|-------------------|---------|-----------|----------|------|--------------|------|-------|-------------|
| Supports | Total | Available | Required | Dead | Roof Live | Snow | Total | Accessories |
| 1 - Trimmer - SPF | 4.50" | 4.50" | 1.62" | 1668 | 1628 | 2441 | 5737 | None |
| 2 - Trimmer - SPF | 4.50" | 4.50" | 1.62" | 1668 | 1628 | 2441 | 5737 | None |

| r ^a s a L | ран ₁ | Tributary | Dead | Roof Live | Snow | |
|----------------------|------------------|-----------|--------|------------------|--------|----------------------------|
| Loads | Location | Width | (0.90) | (non-snow: 1.25) | (1.15) | Comments |
| 1 - Uniform(PSF) | 0 to 7' 9" | 21' | 20.0 | 20.0 | 30.0 | Residential - Living Areas |

Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.

The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:41 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

Page 14 of 54



| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|-------------------|---------------|----------------|------|-----------------------------|
| Member Reaction (lbs) | 5302 @ 3" | 11419 (4.50") | Passed (46%) | | 1.0 D + 1.0 S (All Spans) |
| Shear (lbs) | 4065 @ 1' 2" | 7393 | Passed (55%) | 1.15 | 1.0 D + 1.0 S (All Spans) |
| Moment (Ft-lbs) | 11962 @ 5' | 15016 | Passed (80%) | 1.15 | 1.0 D + 1.0 S (All Spans) |
| Live Load Defl. (in) | 0.255 @ 5' | 0.317 | Passed (L/446) | | 1.0 D + 1.0 S (All Spans) |
| Total Load Defl. (in) | 0.430 @ 5' | 0.475 | Passed (L/265) | | 1.0 D + 1.0 S (All Spans) |

System : Wall Member Type : Header Building Use : Residential Building Code : IBC Design Methodology : ASD

Deflection criteria: LL (L/360) and TL (L/240).

• Bracing (Lu): All compression edges (top and bottom) must be braced at 9' 5 7/16" o/c unless detailed otherwise. Proper attachment and positioning of lateral bracing is required to achieve member stability.

| | | Bearing | | Loads to Supports (lbs) | | | | |
|-------------------|-------|-----------|----------|-------------------------|--------------|------|-------|-------------|
| Supports | Total | Available | Required | Dead | Roof Live | Snow | Total | Accessories |
| 1 - Trimmer - SPF | 4.50" | 4.50" | 2.09" | 2152 | 2100 | 3150 | 7402 | None |
| 2 - Trimmer - SPF | 4.50" | 4.50" | 2.09" | 2152 | 2100 | 3150 | 7402 | None |

| | | Tributary | Dead | Roof Live | Snow | , |
|------------------|----------|-----------|--------|------------------|------------|----------------------------|
| Loads | Location | Width | (0.90) | (non-snow: 1.25) | ··· (1.15) | Comments |
| 1 - Uniform(PSF) | 0 to 10' | 21' | 20.0 | 20.0 | 30.0 | Residential - Living Areas |

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.

The product application, input design loads, dimensions and support information have been provided by Forte Software Operator


| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:42 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

Page 15 of 54

SUSTAINABLE FORESTRY INITIATIVE





| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|-------------------|--------------|-----------------|------|-----------------------------|
| Member Reaction (lbs) | 115@0 | 1913 (1.50") | Passed (6%) | | 1.0 D + 1.0 S (All Spans) |
| Shear (lbs) | 73 @ 5" | 1087 | Passed (7%) | 1.15 | 1.0 D + 1.0 S (All Spans) |
| Moment (Ft-lbs) | 65 @ 1' 1 1/2" | 770 | Passed (8%) | 1.15 | 1.0 D + 1.0 S (All Spans) |
| Live Load Defl. (in) | 0.002 @ 1' 1 1/2" | 0.075 | Passed (1/999+) | | 1.0 D + 1.0 S (All Spans) |
| Total Load Defl. (in) | 0.004 @ 1' 1 1/2" | 0.112 | Passed (L/999+) | | 1.0 D + 1.0 S (All Spans) |

System : Wall Member Type : Header Building Use : Residential Building Code : IBC Design Methodology : ASD

SUSTAINABLE FORESTRY INITIATIVE

• Deflection criteria: LL (L/360) and TL (L/240).

· Bracing (Lu): All compression edges (top and bottom) must be braced at 2' 3" o/c unless detailed otherwise. Proper attachment and positioning of lateral

Applicable calculations are based on NDS 2005 methodology.

Bearing Loads to Supports (lbs) Supports Roof Total Available Required Dead Snow Total Accessories Live 1 - Trimmer - SPF 1.50 1.50" 1.50" 48 45 68 161 None 2 - Trimmer - SPF 1.50" 1.50" 1.50" 48 45 68 161 None

| | . . | Tributary | Dead | Roof Live | Snow | |
|------------------|------------|-----------|--------|------------------|--------|----------------------------|
| Loads | Location | Width | (0.90) | (non-snow; 1.25) | (1.15) | Comments |
| 1 - Uniform(PSF) | 0 to 2' 3" | 2' | 20.0 | 20.0 | 30.0 | Residential - Living Areas |

Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.

The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:42 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

Page 16 of 54



| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|-------------------|--------------|-----------------|------|---|
| Member Reaction (lbs) | 218 @ 0 | 1913 (1.50") | Passed (11%) | | 1.0 D + 1.0 S (All Spans) |
| Shear (lbs) | 175 @ 5" | 1087 | Passed (16%) | 1.15 | 1.0 D + 1.0 S (All Spans) |
| Moment (Ft-lbs) | 232 @ 2' 1 1/2" | 770 | Passed (30%) | 1.15 | 1.0 D + 1.0 S (All Spans) |
| Live Load Defl. (in) | 0.029 @ 2' 1 1/2" | 0.142 | Passed (L/999+) | | 1.0 D + 1.0 S (All Spans) |
| Total Load Defl. (in) | 0.050 @ 2' 1 1/2" | 0.213 | Passed (1/999+) | | $1.0 \text{ D} \pm 1.0 \text{ S}$ (All Spans) |

System : Wall Member Type : Header Building Use : Residential Building Code : IBC Design Methodology : ASD

SUSTAINABLE FORESTRY INITIATIVE

Deflection criteria: LL (L/360) and TL (L/240).

· Bracing (Lu): All compression edges (top and bottom) must be braced at 4' 3" o/c unless detailed otherwise. Proper attachment and positioning of lateral

bracing is required to achieve member stability.
Applicable calculations are based on NDS 2005 methodology.

| | 1 | Bearing Loads to Supports (Ibs | | | | | | \$ |
|-------------------|-------|--------------------------------|-------------------|------|--------------|------|-------|-------------|
| Supports | Total | Available | Required | Dead | Roof Live | Snow | Total | Accessories |
| 1 - Trimmer - SPF | 1.50" | 1.50" | 1.50 ⁿ | 91 | 85 | 128 | 304 | None |
| 2 - Trimmer - SPF | 1.50" | 1.50" | 1.50" | 91 | 85 | 128 | 304 | None |

| Loads | Location , . | Tributary Width | Dead (0.90) | Roof Live (non-snow: 1.25) | Snow (1.15) | Comments |
|------------------|--------------|--------------------|----------------|-------------------------------|----------------|----------------------------|
| 1 - Uniform(PSF) | 0 to 4' 3" | 2' | 20.0 | 20.0 | 30.0 | Residential - Living Areas |

Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.


The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:43 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

Page 17 of 54





| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|--------------------|---------------|----------------|------|-----------------------------|
| Member Reaction (lbs) | 4109 @ 3" | 11419 (4.50") | Passed (36%) | | 1.0 D + 1.0 S (All Spans) |
| Shear (lbs) | 2872 @ 6' 7" | 7393 | Passed (39%) | 1.15 | 1.0 D + 1.0 S (All Spans) |
| Moment (Ft-lbs) | 6967 @ 3' 10 1/2" | 15016 | Passed (46%) | 1.15 | 1.0 D + 1.0 S (All Spans) |
| Live Load Defl. (in) | 0.093 @ 3' 10 1/2" | 0.242 | Passed (L/939) | | 1.0 D + 1.0 S (All Spans) |
| Total Load Defl. (in) | 0.156 @ 3' 10 1/2" | 0.363 | Passed (L/558) | | 1.0 D + 1.0 S (All Spans) |

System : Wall Member Type : Header Building Use : Residential Building Code : IBC Design Methodology : ASD

SUSTAINABLE FORESTRY INITIATIVE

• Deflection criteria: LL (L/360) and TL (L/240).

Bracing (Lu): All compression edges (top and bottom) must be braced at 7' 9" o/c unless detailed otherwise. Proper attachment and positioning of lateral bracing is required to achieve member stability.

| ± | | Bearing | | | Loads to S | upports (ib | | |
|-------------------|-------|-----------|----------|------|--------------|-------------|-------|-------------|
| Supports | Total | Available | Required | Dead | Roof Live | Snow | Total | Accessories |
| 1 - Trimmer - SPF | 4.50" | 4.50" | 1.62" | 1668 | 1628 | 2441 | 5737 | None |
| 2 - Trimmer - SPF | 4.50" | 4.50" | 1.62" | 1668 | 1628 | 2441 | 5737 | None |

| a a North a | , | Tributary | Dead | Roof Live | Snow . | |
|------------------|------------|-----------|--------|------------------|--------|----------------------------|
| Loads | Location | Width | (0.90) | (non-snow; 1.25) | (1.15) | Comments |
| 1 - Uniform(PSF) | 0 to 7' 9" | 21' | 20.0 | 20.0 | 30.0 | Residential - Living Areas |

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.


The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:43 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

Page 18 of 54

Overall Length: 10'



All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal.; Drawing is Conceptual

| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|-------------------|---------------|----------------|------|-----------------------------|
| Member Reaction (lbs) | 5302 @ 3" | 11419 (4.50") | Passed (46%) | | 1.0 D + 1.0 S (All Spans) |
| Shear (lbs) | 4065 @ 1' 2" | 7393 | Passed (55%) | 1.15 | 1.0 D + 1.0 S (All Spans) |
| Moment (Ft-lbs) | 11962 @ 5' | 15016 | Passed (80%) | 1.15 | 1.0 D + 1.0 S (All Spans) |
| Live Load Defl. (in) | 0.255 @ 5' | 0.317 | Passed (L/446) | | 1.0 D + 1.0 S (All Spans) |
| Total Load Defl. (in) | 0.430 @ 5' | 0.475 | Passed (L/265) | | 1.0 D + 1.0 S (All Spans) |

System : Wall Member Type : Header Building Use : Residential Building Code : IBC Design Methodology : ASD

SUSTAINABLE FORESTRY INITIATIVE

• Deflection criteria: LL (L/360) and TL (L/240).

 Bracing (Lu): All compression edges (top and bottom) must be braced at 9' 5 7/16" o/c unless detailed otherwise. Proper attachment and positioning of lateral bracing is required to achieve member stability.

| ν ⁻¹⁰ λ | | Bearing | | | Loads to S | upports (lbs | | |
|--------------------|-------|-----------|----------|------|--------------|--------------|-------|-------------|
| Supports | Total | Available | Required | Dead | Roof Live | Snow | Total | Accessories |
| 1 - Trimmer - SPF | 4.50" | 4.50" | 2.09" | 2152 | 2100 | 3150 | 7402 | None |
| 2 - Trimmer - SPF | 4.50" | 4.50" | 2.09" | 2152 | 2100 | 3150 | 7402 | None |

| | | Tributary | Dead | Roof Live | Snow | |
|------------------|----------|-----------|--------|------------------|--------|----------------------------|
| Loads | Location | Width | (0.90) | (non-snow: 1.25) | (1.15) | Comments |
| 1 - Uniform(PSF) | 0 to 10' | 21' | 20.0 | 20.0 | 30.0 | Residential - Living Areas |

Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.


The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:44 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

Page 19 of 54





| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|-------------------|--------------|-----------------|------|-----------------------------|
| Member Reaction (lbs) | 378 @ 0 | 1913 (1.50") | Passed (20%) | | 1.0 D + 1.0 S (All Spans) |
| Shear (lbs) | 317 @ 7" | 1708 | Passed (19%) | 1.15 | 1.0 D + 1.0 S (All Spans) |
| Moment (Ft-lbs) | 684 @ 3' 7 1/2" | 1649 | Passed (42%) | 1.15 | 1.0 D + 1.0 S (All Spans) |
| Live Load Defl. (in) | 0.064 @ 3' 7 1/2" | 0.242 | Passed (L/999+) | | 1.0 D + 1.0 S (All Spans) |
| Total Load Defl. (in) | 0.111 @ 3' 7 1/2" | 0.313 | Passed (L/782) | | 1.0 D + 1.0 S (All Spans) |

System : Wall Member Type : Header Building Use : Residential Building Code : IBC Design Methodology : ASD

SUSTAINABLE FORESTRY INITIATIVE

• Deflection criteria: LL (L/360) and TL (5/16").

· Bracing (Lu): All compression edges (top and bottom) must be braced at 7' 3" o/c unless detailed otherwise. Proper attachment and positioning of lateral

bracing (Ld). An compression edges (top and bottom) must be bracing is required to achieve member stability.
Applicable calculations are based on NDS 2005 methodology.

| ೆಕ್ಕೆ ಕಾರ್ಯಕ್ರಿಕ್ ಜ್ಯಾತ್ ವರ್ಷ ಗ್ರಾ. ಸ್ಥಾನಕ್ರಿಕ್ | | Bearing | 65 91 4 6 1 | Loads to Supports (lbs) | | | **. | |
|---|-------|-----------|----------------|-------------------------|--------------|------|-------|-------------|
| Supports | Total | Available | Required | Dead | Roof Live | Snow | Total | Accessories |
| 1 - Trimmer - SPF | 1.50" | 1.50" | 1.50" | 160 | 145 | 218 | 523 | None |
| 2 - Trimmer - SPF | 1.50" | 1.50" | 1.50" | 160 | 145 | 218 | 523 | None |

| Loads | Location | Tributary Width | Dead (0.90) | Roof Live (non-snow: 1.25) | Snow (1.15) | Comments |
|------------------|------------|--------------------|----------------|-------------------------------|----------------|----------------------------|
| 1 - Uniform(PSF) | 0 to 7' 3" | 2' | 20.0 | 20.0 | 30.0 | Residential - Living Areas |

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent he need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.


The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:44 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

Page 20 of 54

Overall Length: 14' 9"



All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal.; Drawing is Conceptual

| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|-------------------|--------------|----------------|------|-----------------------------|
| Member Reaction (lbs) | 6705 @ 14' 7" | 7809 (3.50") | Passed (86%) | | 1.0 D + 1.0 S (All Spans) |
| Shear (lbs) | 5526 @ 13' 5 5/8" | 13861 | Passed (40%) | 1.15 | 1.0 D + 1.0 S (All Spans) |
| Moment (Ft-lbs) | 23339 @ 7' 5 1/2" | 34332 | Passed (68%) | 1.15 | 1.0 D + 1.0 S (All Spans) |
| Live Load Defl. (in) | 0.367 @ 7' 5 1/2" | 0.475 | Passed (L/466) | | 1.0 D + 1.0 S (All Spans) |
| Total Load Defl. (in) | 0.625 @ 7' 5 1/2" | 0.712 | Passed (L/273) | | 1.0 D + 1.0 S (All Spans) |

System : Roof Member Type : Flush Beam Building Use : Residential Building Code : IBC Design Methodology : ASD Member Pitch: 0/12

SUSTAINABLE FORESTRY INITIATIVE

Deflection criteria: LL (L/360) and TL (L/240).

Bracing (Lu): All compression edges (top and bottom) must be braced at 12' 10 3/4" o/c unless detailed otherwise. Proper attachment and positioning of lateral bracing is required to achieve member stability.

| ٠ · · · · | | Bearing Loads to Supports (Ibs) | | | | | | |
|---------------------|-------|---------------------------------|----------|------|-----------|------|-------|-------------|
| Supports | Total | Available | Required | Dead | Roof Live | Snow | Total | Accessories |
| 1 - Stud wall - SPF | 5.50" | 5.50" | 3.07" | 2830 | 2685 | 4028 | 9543 | Blocking |
| 2 - Stud wall - SPF | 3.50* | 3.50" | 3.00" | 2767 | 2625 | 3938 | 9330 | Blocking |

Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

| Loads | Location | Tributary Width | Dead (0.90) | Roof Live (non-snow: 1.25) | Snow (1.15) | Comments | |
|------------------|-------------|--------------------|----------------|-------------------------------|----------------|----------|--|
| 1 - Uniform(PSF) | 0 to 14' 9" | 18' | 20.0 | 20.0 | 30.0 | Roof | |

Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.

The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:45 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

Page 21 of 54



| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|--------------------|--------------|----------------|------|-----------------------------|
| Member Reaction (lbs) | 5557 @ 10' 11 1/2" | 5557 (2.12") | Passed (100%) | | 1.0 D + 1.0 S (All Spans) |
| Shear (lbs) | 4794 @ 10' 2 3/4" | 9241 | Passed (52%) | 1.15 | 1.0 D + 1.0 S (All Spans) |
| Moment (Ft-lbs) | 14760 @ 5' 7 3/4" | 22888 | Passed (64%) | 1.15 | 1.0 D + 1.0 S (All Spans) |
| Live Load Defl. (in) | 0.313 @ 5' 7 3/4" | 0.480 | Passed (L/553) | | 1.0 D + 1.0 S (All Spans) |
| Total Load Defl. (in) | 0.606 @ 5' 7 3/4" | 0.721 | Passed (L/285) | | 1.0 D + 1.0 S (All Spans) |

System : Roof Member Type : Flush Beam Building Use : Residential Building Code : IBC Design Methodology : ASD Member Pitch: 11/12

Deflection criteria: LL (L/360) and TL (L/240).

Bracing (Lu): All compression edges (top and bottom) must be braced at 10' 3/16" o/c unless detailed otherwise. Proper attachment and positioning of lateral
bracing is required to achieve member stability.

| Bearing | | | | | Loads to S | | | |
|--------------------------------|-------|---------------------|----------|------|--------------|------|-------|-------------|
| Supports | Total | Available | Required | Dead | Roof Live | Snow | Total | Accessories |
| 1 - Beveled Plate - SPF | 5.50" | 5.50" | 3.97" | 2857 | 2033 | 3049 | 7939 | Blocking |
| 2 - Hanger on 11 7/8" SYP beam | 3.50" | Hanger ¹ | 2.12" | 2793 | 2018 | 3026 | 7837 | See note 1 |

Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

• At hanger supports, the Total Bearing dimension is equal to the width of the material that is supporting the hanger

• 1 See Connector grid below for additional information and/or requirements.

| Connector: Simpson Stron | g-Tie Connectors | - | ý) i | · · · · · · · · · · · · · · · · · · · | | |
|--------------------------|---------------------|-------------|-----------|---------------------------------------|--------------|-------------|
| Support | Model | Seat Length | Top Nails | Face Nails | Member Nails | Accessories |
| 2 - Face Mount Hanger | Connector not found | N/A | N/A | N/A | N/A | |


| Loads | Location | Tributary Width | Dead (0.90) | Roof Live (non-snow: 1.25) | Snow (1.15) | Comments |
|------------------|-------------|--------------------|----------------|-------------------------------|----------------|----------|
| 1 - Uniform(PSF) | 0 to 11' 3" | 18' | 20.0 | 20.0 | 30.0 | Roof |

| Weyerhaeuser Notes | SUSTAINABLE FORESTRY INITIATIVE |
|---|---------------------------------|
| Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for Installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. | Ĭ |
| The product application, Input design loads, dimensions and support information have been provided by Forte Software Operator | |

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:45 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

Overall Length: 4' 9"



All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal.; Drawing is Conceptual

| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|-------------------|--------------|-----------------|------|-----------------------------|
| Member Reaction (lbs) | 313 @ 5 1/2" | 1969 (1.50") | Passed (16%) | | 1.0 D + 1.0 S (All Spans) |
| Shear (Ibs) | 158 @ 1' 5 3/8" | 4620 | Passed (3%) | 1.15 | 1.0 D + 1.0 S (All Spans) |
| Moment (Ft-Ibs) | 313 @ 2' 5 1/2" | 11444 | Passed (3%) | 1.15 | 1.0 D + 1.0 S (All Spans) |
| Live Load Defl. (in) | 0.002 @ 2' 5 1/2" | 0.133 | Passed (1/999+) | | 1.0 D + 1.0 S (All Spans) |
| Total Load Defl. (in) | 0.004 @ 2' 5 1/2" | 0.200 | Passed (L/999+) | | 1.0 D + 1.0 S (All Spans) |

System : Roof Member Type : Flush Beam Building Use : Residential Building Code : IBC Design Methodology : ASD Member Pitch: 0/12

Deflection criteria: LL (L/360) and TL (L/240).

forestry standards.

Bracing (Lu): All compression edges (top and bottom) must be braced at 4' o/c unless detailed otherwise. Proper attachment and positioning of lateral bracing
is required to achieve member stability.

| . ä | | Bearing | | | Loads to S | | | |
|--------------------------------|-------|---------------------|----------|------|--------------|------|-------|-------------|
| Supports | Total | Available | Required | Dead | Roof Live | Snow | Total | Accessories |
| 1 - Hanger on 11 7/8" PSL beam | 5.50" | Hanger ¹ | 1.50" | 160 | 148 | 221 | 529 | See note 1 |
| 2 - Hanger on 11 7/8" PSL beam | 3.50" | Hanger | 1.50" | 150 | 138 | 206 | 494 | See note 1 |

· At hanger supports, the Total Bearing dimension is equal to the width of the material that is supporting the hanger

• 1 See Connector grid below for additional information and/or requirements.

| Connector: Simpson Strong-Tie Connectors | | | | | | | | |
|--|---------------|-------------|-----------|----------------|---------------|-------------|--|--|
| Support | Model | Seat Length | Top Nails | Face Nails | Member Nails | Accessories | | |
| 1 - Face Mount Hanger | IUS1.81/11.88 | 2.00" | N/A | 10-10d x 1-1/2 | 2-10d x 1-1/2 | | | |
| 2 - Face Mount Hanger | IUS1.81/11.88 | 2.00" | N/A | 10-10d x 1-1/2 | 2-10d x 1-1/2 | | | |


| б ³¹ т. | * * | Tributary | Dead | Roof Live | Snow | |
|--------------------|------------|-----------|--------|------------------|--------|----------|
| Loads | Location | Width | (0.90) | (non-snow: 1.25) | (1.15) | Comments |
| 1 - Uniform(PSF) | 0 to 4' 9" | 3' | 20.0 | 20.0 | 30.0 | Roof |

| Weyerhaeuser Notes | j A | | | . • | | 6 | | |
|---|--|--|--|-----|--|---|--|--|
| Weyerhaeuser warrants that the sizing of its product Weyerhaeuser expressly disclaims any other warrant | | | | | | Y | | |
| www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to incumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to | | | | | | | | |
| assure that this calculation is compatible with the ov | sure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable | | | | | | | |

The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:46 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAM/NG.4te



| Design Results | Actual @ Location | Allowed | Result 🧃 | LDF | Load: Combination (Pattern) |
|-----------------------|-------------------|--------------|-----------------|------|-----------------------------|
| Member Reaction (lbs) | 1428 @ 1 1/2" | 3825 (3.00") | Passed (37%) | | 1.0 D + 1.0 S (All Spans) |
| Shear (lbs) | 1064 @ 1' 1/4" | 2872 | Passed (37%) | 1.15 | 1.0 D + 1.0 S (All Spans) |
| Moment (Ft-lbs) | 2681 @ 4' | 3946 | Passed (68%) | 1.15 | 1.0 D + 1.0 S (All Spans) |
| Live Load Defl. (in) | 0.062 @ 4' | 0.258 | Passed (1/999+) | | 1.0 D + 1.0 S (All Spans) |
| Total Load Defl. (in) | 0.105 @ 4' | 0.387 | Passed (L/889) | | 1.0 D + 1.0 S (All Spans) |

System : Wall Member Type : Header Building Use : Residential Building Code : IBC Design Methodology : ASD

SUSTAINABLE FORESTRY INITIATIVE

• Deflection criteria: LL (L/360) and TL (L/240).

Bracing (Lu): All compression edges (top and bottom) must be braced at 8' o/c unless detailed otherwise. Proper attachment and positioning of lateral bracing

Applicable calculations are based on NDS 2005 methodology.

| | 4. 6 . 1 | Bearing | ngi. Ngi m | e" > | Loads to S | upports (lb | s) | • |
|-------------------|------------------------|-----------|---------------|------|--------------|-------------|-------|-------------|
| Supports | Total | Available | Required | Dead | Roof Live | Snow | Total | Accessories |
| 1 - Trimmer - SPF | 3.00" | 3.00" | 1.50" | 588 | 560 | 840 | 1988 | None |
| 2 - Trimmer - SPF | 3.00" | 3.00" | 1.50" | 588 | 560 | 840 | 1988 | None |

| | | Tributary | Dead | Roof Live | Snow | s |
|------------------|----------|-----------|--------|------------------|--------|----------------------------|
| Loads | Location | Width | (0.90) | (non-snow: 1.25) | (1.15) | Comments |
| 1 - Uniform(PSF) | 0 to 8' | 7' | 20.0 | 20.0 | 30.0 | Residential - Living Areas |

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.


The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:47 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

Page 24 of 54

Overall Length: 9' 9"



All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal.; Drawing is Conceptual

| Design Results | Actual @ Location | Allowed - | Result | LDF | Load: Combination (Pattern) |
|-----------------------|--------------------|--------------|-----------------|------|-------------------------------------|
| Member Reaction (lbs) | 5152 @ 1 1/2" | 7613 (3.00") | Passed (68%) | | 1.0 D + 0.75 L + 0.75 S (All Spans) |
| Shear (lbs) | 3646 @ 8' 6 1/8" | 8035 | Passed (45%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Moment (Ft-lbs) | 11315 @ 4' 10 1/2" | 19902 | Passed (57%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Live Load Defl. (in) | 0.112 @ 4' 10 1/2" | 0.317 | Passed (L/999+) | | 1.0 D + 0.75 L + 0.75 S (All Spans) |
| Total Load Defl. (in) | 0.231 @ 4' 10 1/2" | 0.475 | Passed (L/493) | | 1.0 D + 0.75 L + 0.75 S (All Spans) |

System : Wall Member Type : Header Building Use : Residential Building Code : IBC Design Methodology : ASD

BUSTAINABLE FORESTRY INITIATIVE

Deflection criteria: LL (L/360) and TL (L/240).

Bracing (Lu): All compression edges (top and bottom) must be braced at 9' 9" o/c unless detailed otherwise. Proper attachment and positioning of lateral bracing is required to achieve member stability.

| 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 | Bearing | | | | Load | s to Suppor | | | |
|---------------------------------------|---------|-----------|----------|------|---------------|--------------|------|-------|-------------|
| Supports | Total | Available | Required | Dead | Floor Live | Roof Live | Snow | Total | Accessories |
| 1 - Trimmer - SPF | 3.00" | 3.00" | 2.03" | 2647 | 2243 | 731 | 1097 | 6718 | None |
| 2 - Trimmer - SPF | 3.00" | 3.00" | 2.03" | 2647 | 2243 | 731 | 1097 | 6718 | None |

| Loads | Location | Tributary Width | Dead (0.90) | Floor Live (1.00) | Roof Live (non-snow: 1.25) | Snow (1.15) | Comments |
|------------------|------------|--------------------|----------------|----------------------|-------------------------------|----------------|----------------------------|
| 1 - Uniform(PSF) | 0 to 9' 9" | 11' 6" | 20.0 | 40.0 | - | - | Residential - Living Areas |
| 2 - Uniform(PSF) | 0 to 9' 9" | 7' 6" | 20.0 | - | 20.0 | 30.0 | |
| 3 - Uniform(PLF) | 0 to 9' 9" | N/A | 150.0 | | - | - | |

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.


The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:47 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

Page 25 of 54

Overall Length: 8' 6"



All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal.; Drawing is Conceptual

| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|-------------------|--------------|-----------------|------|-----------------------------|
| Member Reaction (lbs) | 2268 @ 1 1/2" | 3825 (3.00") | Passed (59%) | | 1.0 D + 1.0 S (All Spans) |
| Shear (Ibs) | 1634 @ 7' 3 3/4" | 3493 | Passed (47%) | 1.15 | 1.0 D + 1.0 S (All Spans) |
| Moment (Ft-Ibs) | 4539 @ 4' 3" | 5306 | Passed (86%) | 1.15 | 1.0 D + 1.0 S (All Spans) |
| Live Load Defl. (in) | 0.047 @ 4' 3" | 0.275 | Passed (L/999+) | | 1.0 D + 1.0 S (All Spans) |
| Total Load Defl. (in) | 0.112 @ 4' 3" | 0.412 | Passed (L/887) | | 1.0 D + 1.0 S (All Spans) |

System : Wall Member Type : Header Building Use : Residential Building Code : IBC Design Methodology : ASD

SUSTAINABLE FORESTRY INITIATIVE

Deflection criteria: LL (L/360) and TL (L/240).

Bracing (Lu): All compression edges (top and bottom) must be braced at 7' 2 1/8" o/c unless detailed otherwise. Proper attachment and positioning of lateral

bracing is required to achieve member stability. Applicable calculations are based on NDS 2005 methodology.

| 4 # · · | | Bearing | • | | Loads to S | upports (lb | s) | | • |
|-------------------|-------|-----------|----------|------|--------------|-------------|-------|-------------|---|
| Supports | Total | Available | Required | Dead | Roof Live | Snow | Total | Accessories | |
| 1 - Trimmer - SPF | 3.00" | 3.00" | 1.78" | 1311 | 638 | 956 | 2905 | None | |
| 2 - Trimmer - SPF | 3.00" | 3.00" | 1.78" | 1311 | 638 | 956 | 2905 | None | |

| Loads | Location | Tributary Width | Dead (0.90) | Roof Live (non-snow: 1.25) | Snow (1.15) | Comments |
|------------------|------------|--------------------|----------------|-------------------------------|----------------|----------|
| 1 - Uniform(PSF) | 0 to 8' 6" | 7' 6" | 20.0 | 20.0 | 30.0 | |
| 2 - Uniform(PLF) | 0 to 8' 6" | N/A | 150.0 | - | - | |

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.

~

The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

ł.

<u>،</u>


 Forte Software Operator
 Job Notes

 Robert Williams, PE TDI Associates, Inc. Architects & Engineers (262) 437-0400 bob.w@tdiae.com
 Stratton Residence Joy Peot Shields Architect Fox Point, Wisconsin TDI project no. 13-159
 5/3/2013 10:07:48 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

PASSED

Page 26 of 54

Overall Length: 6' 6"



All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal.; Drawing is Conceptual

| Design Results | Actual @ Location | Allowed | Result . | LDF | Load: Combination (Pattern) |
|-----------------------|-------------------|--------------|-----------------|------|-------------------------------------|
| Member Reaction (lbs) | 3014 @ 1 1/2" | 3825 (3.00") | Passed (79%) | | 1.0 D + 0.75 L + 0.75 S (All Spans) |
| Shear (lbs) | 1750 @ 5' 3 3/4" | 3038 | Passed (58%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Moment (Ft-lbs) | 4143 @ 3' 3" | 4614 | Passed (90%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Live Load Defl. (in) | 0.030 @ 3' 3" | 0.208 | Passed (L/999+) | | 1.0 D + 0.75 L + 0.75 S (All Spans) |
| Total Load Defl. (in) | 0.064 @ 3' 3" | 0.313 | Passed (L/999+) | | 1.0 D + 0.75 L + 0.75 S (All Spans) |

System : Wall Member Type : Header Building Use : Residential Building Code : IBC Design Methodology : ASD

SUSTAINABLE FORESTRY INITIATIVE

Deflection criteria: LL (L/360) and TL (L/240).

· Bracing (Lu): All compression edges (top and bottom) must be braced at 6' 6" o/c unless detailed otherwise. Proper attachment and positioning of lateral

bracing is required to achieve member stability. • Applicable calculations are based on NDS 2005 methodology.

| | Bearing | | | | Load | | | | |
|-------------------|---------|-----------|----------|------|---------------|--------------|------|-------|-------------|
| Supports | Total | Available | Required | Dead | Floor Live | Roof Live | Snow | Total | Accessories |
| 1 - Trimmer - SPF | 3.00" | 3.00" | 2.36" | 1588 | 1170 | 488 | 731 | 3977 | None |
| 2 - Trimmer - SPF | 3.00" | 3.00" | 2.36" | 1588 | 1170 | 488 | 731 | 3977 | None |

| Loads | Location | Tributary Width | Dead (0.90) | Floor Live (1.00) | Roof Live (non-snow: 1.25) | Snow (1.15) | Comments |
|------------------|------------|--------------------|----------------|----------------------|-------------------------------|----------------|----------------------------|
| 1 - Uniform(PSF) | 0 to 6' 6" | 9' | 20.0 | 40.0 | - | - | Residential - Living Areas |
| 2 - Uniform(PSF) | 0 to 6' 6" | 7' 6" | 20.0 | - | 20.0 | 30.0 | |
| 3 - Uniform(PLF) | 0 to 6' 6" | N/A | 150.0 | - | - | - | |


Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.

The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:48 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te



| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|-------------------|--------------|-----------------|------|-------------------------------------|
| Member Reaction (lbs) | 766 @ 0 | 1913 (1.50") | Passed (40%) | | 1.0 D + 0.75 L + 0.75 S (All Spans) |
| Shear (lbs) | 500 @ 7" | 1485 | Passed (34%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Moment (Ft-lbs) | 732 @ 2' 1 1/2" | 1434 | Passed (51%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Live Load Defl. (in) | 0.015 @ 2' 1 1/2" | 0.142 | Passed (L/999+) | | 1.0 D + 0.75 L + 0.75 S (All Spans) |
| Total Load Defl. (in) | 0.045 @ 2' 1 1/2" | 0.213 | Passed (L/999+) | | 1.0 D + 0.75 L + 0.75 S (All Spans) |

System : Wall Member Type : Header Building Use : Residential Building Code : IBC Design Methodology : ASD

SUSTAINABLE FORESTRY INITIATIVE

• Deflection criteria: LL (L/360) and TL (L/240).

· Bracing (Lu): All compression edges (top and bottom) must be braced at 4' 3" o/c unless detailed otherwise. Proper attachment and positioning of lateral

bracing is required to achieve member stability. • Applicable calculations are based on NDS 2005 methodology.

| | a los a la companya de la companya d | Bearing | - €.84 ⁰ * | Loads to Supports (lbs) | | | | | | 1 10 10 10 10 10 10 10 10 10 10 10 10 10 |
|-------------------|--|-----------|---------------------------|-------------------------|---------------|--------------|------|-------|-------------|--|
| Supports | Total | Available | Required | Dead | Floor Live | Roof Live | Snow | Total | Accessories | u |
| 1 - Trimmer - SPF | 1.50" | 1.50" | 1.50" | 519 | 170 | 106 | 159 | 954 | None | |
| 2 - Trimmer - SPF | 1.50" | 1.50" | 1.50" | 519 | 170 | 106 | 159 | 954 | None | |

| Loads | Location | Tributary Width | Dead (0.90) | Floor Live (1.00) | Roof Live (non-snow: 1.25) | Snow (1.15) | Comments |
|------------------|------------|--------------------|----------------|----------------------|-------------------------------|----------------|----------------------------|
| 1 - Uniform(PSF) | 0 to 4' 3" | 2' | 20.0 | 40.0 | - | - | Residential - Living Areas |
| 2 - Uniform(PSF) | 0 to 4' 3" | 2' 6" | 20.0 | - | 20.0 | 30.0 | |
| 3 - Uniform(PLF) | 0 to 4' 3" | N/A | 150.0 | - | - | - | |

ೆಕ್ಕಿ ಗೇಟ್ಸ್


Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Square Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable for the overall device. forestry standards.

The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:49 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te





| Design Results | Actual @ Location | Allowed | Result | LDF. | Load: Combination (Pattern) |
|-----------------------|-------------------|--------------|-----------------|------|-------------------------------------|
| Member Reaction (lbs) | 405 @ 0 | 1913 (1.50") | Passed (21%) | | 1.0 D + 0.75 L + 0.75 S (All Spans) |
| Shear (lbs) | 176 @ 7" | 1485 | Passed (12%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Moment (Ft-lbs) | 205 @ 1' 1 1/2" | 1434 | Passed (14%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Live Load Defl. (in) | 0.001 @ 1' 1 1/2" | 0.075 | Passed (L/999+) | | 1.0 D + 0.75 L + 0.75 S (All Spans) |
| Total Load Defl. (in) | 0.004 @ 1' 1 1/2" | 0.112 | Passed (1/999+) | | 1.0 D + 0.75 L + 0.75 S (All Spans) |

System : Wall Member Type : Header Building Use : Residential Building Code : IBC Design Methodology : ASD

SUSTAINABLE FORESTRY INITIATIVE

Deflection criteria: LL (L/360) and TL (L/240).

Bracing (Lu): All compression edges (top and bottom) must be braced at 2' 3" o/c unless detailed otherwise. Proper attachment and positioning of lateral
bracing is required to achieve method to the life.

bracing is required to achieve member stability. Applicable calculations are based on NDS 2005 methodology.

| · · · · | | Bearing | | Loads to Supports (lbs) | | | | | |
|-------------------|-------|-----------|----------|-------------------------|---------------|--------------|------|-------|-------------|
| Supports | Total | Available | Required | Dead | Floor Live | Roof Live | Snow | Total | Accessories |
| 1 - Trimmer - SPF | 1.50" | 1.50" | 1.50" | 275 | 90 | 56 | 84 | 505 | None |
| 2 - Trimmer - SPF | 1.50" | 1.50" | 1.50" | 275 | 90 | 56 | 84 | 505 | None |

| Loads | Location | Tributary Width | Dead (0.90) | Floor Live (1.00) | Roof Live (non-snow: 1.25) | Snow (1.15) | Comments |
|------------------|------------|--------------------|----------------|----------------------|-------------------------------|----------------|----------------------------|
| 1 - Uniform(PSF) | 0 to 2' 3" | 2' | 20.0 | 40.0 | - | - | Residential - Living Areas |
| 2 - Uniform(PSF) | 0 to 2' 3" | 2' 6" | 20.0 | - | 20.0 | 30.0 | |
| 3 - Uniform(PLF) | 0 to 2' 3" | N/A | 150.0 | - | - | - | |

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.


The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:49 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

Page 29 of 54





| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|-------------------|--------------|-----------------|------|-----------------------------|
| Member Reaction (lbs) | 571 @ 0 | 1913 (1.50") | Passed (30%) | | 1.0 D + 1.0 S (All Spans) |
| Shear (lbs) | 476 @ 8 3/4" | 2251 | Passed (21%) | 1.15 | 1.0 D + 1.0 S (All Spans) |
| Moment (Ft-lbs) | 1249 @ 4' 4 1/2" | 2645 | Passed (47%) | 1.15 | 1.0 D + 1.0 S (All Spans) |
| Live Load Defl. (in) | 0.074 @ 4' 4 1/2" | 0.292 | Passed (L/999+) | | 1.0 D + 1.0 S (All Spans) |
| Total Load Defl. (in) | 0.129 @ 4' 4 1/2" | 0.313 | Passed (L/814) | | 1.0 D + 1.0 S (All Spans) |

System : Wall Member Type : Header Building Use : Residential Building Code : IBC Design Methodology : ASD

SUSTAINABLE FORESTRY INITIATIVE

Deflection criteria: LL (L/360) and TL (5/16").

· Bracing (Lu): All compression edges (top and bottom) must be braced at 8' 9" o/c unless detailed otherwise. Proper attachment and positioning of lateral

bracing is required to achieve member stability. • Applicable calculations are based on NDS 2005 methodology.

| | Bearing Loads to Supports (lbs) | | | | | Loads to Supports (ibs) | | | | |
|-------------------|---------------------------------|-----------|----------|------|--------------|-------------------------|-------|-------------|--|--|
| Supports | Total | Available | Required | Dead | Roof Live | Snow | Total | Accessories | | |
| 1 - Trimmer - SPF | 1.50" | 1.50" | 1.50" | 243 | 219 | 328 | 790 | None | | |
| 2 - Trimmer - SPF | 1.50" | 1.50" | 1.50" | 243 | 219 | 328 | 790 | None | | |

| Loads | Location | Tributary Width | Dead (0.90) | Roof Live (non-snow: 1.25) | Snow (1.15) | Comments | * ¹ |
|------------------|------------|--------------------|----------------|-------------------------------|----------------|----------|----------------|
| 1 - Uniform(PSF) | 0 to 8' 9" | 2' 6" | 20.0 | 20.0 | 30.0 | | |

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.


The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:50 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

Page 30 of 54

Overall Length: 3' 6"



All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal.; Drawing is Conceptual

| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|-------------------|--------------|-----------------|------|-------------------------------------|
| Member Reaction (lbs) | 2943 @ 1 1/2" | 3825 (3.00") | Passed (77%) | | 1.0 D + 0.75 L + 0.75 S (All Spans) |
| Shear (lbs) | 1322 @ 10 1/4" | 1958 | Passed (68%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Moment (Ft-lbs) | 1948 @ 1' 9" | 2300 | Passed (85%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Live Load Defl. (in) | 0.016 @ 1' 9" | 0.108 | Passed (L/999+) | | 1.0 D + 0.75 L + 0.75 S (All Spans) |
| Total Load Defl. (in) | 0.032 @ 1' 9" | 0.162 | Passed (L/999+) | | 1.0 D + 0.75 I + 0.75 S (All Spans) |

System : Wall Member Type : Header Building Use : Residential Building Code : IBC Design Methodology : ASD

SUSTAINABLE FORESTRY INITIATIVE

• Deflection criteria: LL (L/360) and TL (L/240).

Bracing (Lu): All compression edges (top and bottom) must be braced at 3' 6" o/c unless detailed otherwise. Proper attachment and positioning of lateral

bracing is required to achieve member stability.
Applicable calculations are based on NDS 2005 methodology.

| · · · · · · · · · · · · · · · · · · · | | Bearing | | | Load | | | | |
|---------------------------------------|-------|-----------|----------|------|---------------|--------------|------|-------|-------------|
| Supports | Total | Available | Required | Dead | Floor Live | Roof Live | Snow | Total | Accessories |
| 1 - Trimmer - SPF | 3.00" | 3.00" | 2.31" | 1427 | 1155 | 578 | 866 | 4026 | None |
| 2 - Trimmer - SPF | 3.00" | 3.00" | 2.31" | 1427 | 1155 | 578 | 866 | 4026 | None |

| Loads | Location | Tributary Width | Dead (0.90) | Floor Live (1.00) | Roof Live (non-snow: 1.25) | Snow (1.15) | Comments |
|------------------|------------|--------------------|-------------|----------------------|-------------------------------|----------------|----------------------------|
| 1 - Uniform(PSF) | 0 to 3' 6" | 16' 6" | 20.0 | 40.0 | - | - | Residential - Living Areas |
| 2 - Uniform(PSF) | 0 to 3' 6" | 16' 6" | 20.0 | - | 20.0 | 30.0 | |
| 3 - Uniform(PLF) | 0 to 3' 6" | N/A | 150.0 | - | - | - | |

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.

The product application, input design loads, dimensions and support information have been provided by Forte Software Operator


| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:50 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

Page 31 of 54

â

Overall Length: 8' 6"



All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal.; Drawing is Conceptual

| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|-------------------|--------------|-----------------|------|-------------------------------------|
| Member Reaction (lbs) | 5628 @ 1 1/2" | 7613 (3.00") | Passed (74%) | | 1.0 D + 0.75 L + 0.75 S (All Spans) |
| Shear (Ibs) | 3892 @ 1' 2 7/8" | 8035 | Passed (48%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Moment (Ft-lbs) | 11000 @ 4' 3" | 19902 | Passed (55%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Live Load Defl. (in) | 0.087 @ 4' 3" | 0.275 | Passed (L/999+) | | 1.0 D + 0.75 L + 0.75 S (All Spans) |
| Total Load Defi. (in) | 0.173 @ 4' 3" | 0.412 | Passed (L/574) | | 1.0 D + 0.75 L + 0.75 S (All Spans) |

System : Wall Member Type : Header Building Use : Residential Building Code : IBC Design Methodology : ASD

SUSTAINABLE FORESTRY INITIATIVE

Deflection criteria: LL (L/360) and TL (L/240).

Bracing (Lu): All compression edges (top and bottom) must be braced at 8' 6" o/c unless detailed otherwise. Proper attachment and positioning of lateral bracing is required to achieve member stability.

| · | Bearing | | | | Load | | | | |
|-------------------|---------|-----------|----------|------|---------------|--------------|------|-------|-------------|
| Supports | Total | Available | Required | Dead | Floor Live | Roof Live | Snow | Total | Accessories |
| 1 - Trimmer - SPF | 3.00" | 3.00" | 2.22" | 2775 | 2720 · | 723 | 1084 | 7302 | None |
| 2 - Trimmer - SPF | 3.00" | 3.00" | 2.22" | 2775 | 2720 | 723 | 1084 | 7302 | None |

| Loads | Location | Tributary Width | Dead (0.90) | Floor Live (1.00) | Roof Live (non-snow: 1.25) | Snow (1.15) | Comments |
|------------------|------------|--------------------|----------------|----------------------|-------------------------------|----------------|----------------------------|
| 1 - Uniform(PSF) | 0 to 8' 6" | 16' | 20.0 | 40.0 | - | - | Residential - Living Areas |
| 2 - Uniform(PSF) | 0 to 8' 6" | 8' 6" | 20.0 | - | 20.0 | 30.0 | |
| 3 - Uniform(PLF) | 0 to 8' 6" | N/A | 150.0 | - | - | - | |


Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.

The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes | | | | | |
|---|----------------------------|--|--|--|--|--|
| Robert Williams, PE | Stratton Residence | | | | | |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect | | | | | |
| (262) 437-0400 | Fox Point, Wisconsin | | | | | |
| bob.w@tdiae.com | TDI project no. 13-159 | | | | | |

5/3/2013 10:07:51 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te Overall Length: 7'



All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal.;Drawing is Conceptual

| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|-------------------|--------------|-----------------|------|-------------------------------------|
| Member Reaction (lbs) | 5120 @ 1 1/2" | 7613 (3.00") | Passed (67%) | | 1.0 D + 0.75 L + 0.75 S (All Spans) |
| Shear (lbs) | 3307 @ 5' 9 1/8" | 9241 | Passed (36%) | 1.15 | 1.0 D + 0.75 L + 0.75 S (All Spans) |
| Moment (Ft-lbs) | 8332 @ 3' 6" | 22888 | Passed (36%) | 1.15 | 1.0 D + 0.75 L + 0.75 S (All Spans) |
| Live Load Defl. (in) | 0.046 @ 3' 6" | 0.225 | Passed (L/999+) | | 1.0 D + 0.75 L + 0.75 S (All Spans) |
| Total Load Defl. (in) | 0.093 @ 3' 6" | 0.338 | Passed (L/871) | | 1.0 D + 0.75 L + 0.75 S (All Spans) |

System : Wall Member Type : Header Building Use : Residential Building Code : IBC Design Methodology : ASD

SUSTAINABLE FORESTRY INITIATIVE

Deflection criteria: LL (L/360) and TL (L/240).

Bracing (Lu): All compression edges (top and bottom) must be braced at 7' o/c unless detailed otherwise. Proper attachment and positioning of lateral bracing
is required to achieve member stability.

| | | Bearing | 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 | 1 | Load | , , , , , , , , , , , , , , , , , , , | | | | |
|-------------------|-------|-----------|---|------|---------------|---------------------------------------|------|-------|-------------|--|
| Supports | Total | Available | Required | Dead | Floor Live | Roof Live | Snow | Total | Accessories | |
| 1 - Trimmer - SPF | 3.00" | 3.00" | 2.02" | 2600 | 1260 | 1400 | 2100 | 7360 | None | |
| 2 - Trimmer - SPF | 3.00" | 3.00" | 2.02" | 2600 | 1260 | 1400 | 2100 | 7360 | None | |

| Loads | а Ч С С С С С С С | Location | Tributary Width | Dead (0.90) | Floor Live (1.00) | Roof Live | Snow (1.15) | Comments |
|------------------|---|----------|--------------------|----------------|----------------------|-----------|----------------|----------------------------|
| 1 - Uniform(PSF) | | 0 to 7' | 9' | 20.0 | 40.0 | - | - | Residential - Living Areas |
| 2 - Uniform(PSF) | | 0 to 7' | 20' | 20.0 | - | 20.0 | 30.0 | |
| 3 - Uniform(PLF) | - | 0 to 7' | N/A | 150.0 | - | - | - | |

Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.

The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:51 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

Overall Length: 9' 6"



All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal.; Drawing is Conceptual

| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|-------------------|--------------|----------------|------|-------------------------------------|
| Member Reaction (lbs) | 6949 @ 1 1/2" | 7613 (3.00") | Passed (91%) | | 1.0 D + 0.75 L + 0.75 S (All Spans) |
| Shear (lbs) | 5136 @ 8' 3 1/8" | 9241 | Passed (56%) | 1.15 | 1.0 D + 0.75 L + 0.75 S (All Spans) |
| Moment (Ft-Ibs) | 15647 @ 4' 9" | 22888 | Passed (68%) | 1.15 | 1.0 D + 0.75 L + 0.75 S (All Spans) |
| Live Load Defl. (in) | 0.143 @ 4' 9" | 0.308 | Passed (L/778) | | 1.0 D + 0.75 L + 0.75 S (All Spans) |
| Total Load Defl. (in) | 0.290 @ 4' 9" | 0.463 | Passed (L/383) | | 1.0 D + 0.75 L + 0.75 S (All Spans) |

System : Wall Member Type : Header Building Use : Residential Building Code : IBC Design Methodology : ASD

Deflection criteria: LL (L/360) and TL (L/240).

• Bracing (Lu): All compression edges (top and bottom) must be braced at 9' 4 1/16" o/c unless detailed otherwise. Proper attachment and positioning of lateral bracing is required to achieve member stability.

| | Bearing | | | | Load | | | | |
|-------------------|---------|-----------|----------|------|---------------|--------------|------|-------|-------------|
| Supports | Total | Available | Required | Dead | Floor Live | Roof Live | Snow | Total | Accessories |
| 1 - Trimmer - SPF | 3.00" | 3.00" | 2.74" | 3529 | 1710 | 1900 | 2850 | 9989 | None |
| 2 - Trimmer - SPF | 3.00" | 3.00" | 2.74" | 3529 | 1710 | 1900 | 2850 | 9989 | None |

| Loads | Location | Tributary Width | Dead (0.90) | Floor Live (1.00) | Roof Live (non-snow: 1.25) | Snow (1.15) | Comments |
|------------------|------------|--------------------|----------------|----------------------|-------------------------------|----------------|----------------------------|
| 1 - Uniform(PSF) | 0 to 9' 6" | 9' | 20.0 | 40.0 | - | - | Residential - Living Areas |
| 2 - Uniform(PSF) | 0 to 9' 6" | 20' | 20.0 | - | 20.0 | 30.0 | |
| 3 - Uniform(PLF) | 0 to 9' 6" | N/A | 150.0 | - | - | - | |


Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.

The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:52 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te



| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|-------------------|--------------|-----------------|------|-----------------------------|
| Member Reaction (lbs) | 1239 @ 1 1/2" | 3825 (3.00") | Passed (32%) | | 1.0 D + 1.0 L (All Spans) |
| Shear (lbs) | 816 @ 4' 1 3/4" | 1958 | Passed (42%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Moment (Ft-lbs) | 1397 @ 2' 6" | 2300 | Passed (61%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Live Load Defl. (in) | 0.017 @ 2' 6" | 0.158 | Passed (L/999+) | | 1.0 D + 1.0 L (All Spans) |
| Total Load Defl. (in) | 0.043 @ 2' 6" | 0.237 | Passed (L/999+) | | 1.0 D + 1.0 (All Spans) |

System : Wall Member Type : Header Building Use : Residential Building Code : JBC Design Methodology : ASD

SUSTAINABLE FORESTRY INITIATIVE

• Deflection criteria: LL (L/360) and TL (L/240).

· Bracing (Lu): All compression edges (top and bottom) must be braced at 5' o/c unless detailed otherwise. Proper attachment and positioning of lateral bracing

is required to achieve member stability. • Applicable calculations are based on NDS 2005 methodology.

| n na ka | | Bearing | ,o . | Loads to Supports (lbs) | | | | н | | |
|---|-------|-----------|----------|-------------------------|---------------|--------------|------|-------|-------------|---|
| Supports | Total | Available | Required | Dead | Floor Live | Roof Live | Snow | Total | Accessories | |
| 1 - Trimmer - SPF | 3.00" | 3.00" | 1.50" | 739 | 500 | 100 | 150 | 1489 | None | - |
| 2 - Trimmer - SPF | 3.00" | 3.00" | 1.50" | 739 | 500 | 100 | 150 | 1489 | None | |

| Loads | Location | Tributary Width | Dead (0.90) | Floor Live (1.00) | Roof Live (non-snow: 1.25) | Snow (1.15) | Comments |
|------------------|----------|--------------------|----------------|----------------------|-------------------------------|----------------|----------------------------|
| 1 - Uniform(PSF) | 0 to 5' | 5' | 20.0 | 40.0 | - | - | Residential - Living Areas |
| 2 - Uniform(PSF) | 0 to 5' | 2' | 20.0 | - | 20.0 | 30.0 | |
| 3 - Uniform(PLF) | 0 to 5' | N/A | 150.0 | | - 1 | _ | |

Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.

The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:52 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

Page 35 of 54



| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|-------------------|--------------|-----------------|------|-----------------------------|
| Member Reaction (lbs) | 1620 @ 1 1/2" | 3825 (3.00") | Passed (42%) | | 1.0 D + 1.0 L (All Spans) |
| Shear (lbs) | 1028 @ 5' 3 3/4" | 3038 | Passed (34%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Moment (Ft-lbs) | 2434 @ 3' 3" | 4614 | Passed (53%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Live Load Defl. (in) | 0.014 @ 3' 3" | 0.208 | Passed (L/999+) | | 1.0 D + 1.0 L (All Spans) |
| Total Load Defl. (in) | 0.034 @ 3' 3" | 0.313 | Passed (1/999+) | | 1.0 D + 1.0 L (All Spans) |

System : Wall Member Type : Header Building Use : Residential Building Code : IBC Design Methodology : ASD

SUSTAINABLE FORESTRY INITIATIVE

• Deflection criteria: LL (L/360) and TL (L/240).

Bracing (Lu): All compression edges (top and bottom) must be braced at 6' 6" o/c unless detailed otherwise. Proper attachment and positioning of lateral

bracing is required to achieve member stability. Applicable calculations are based on NDS 2005 methodology.

| | , a | Bearing | 9 ⁴ . | | Load | s to Suppor | ts (ibs) | *. | | |
|-------------------|-------|-----------|------------------|------|---------------|--------------|----------|-------------------|-------------|--|
| Supports | Total | Available | Required | Dead | Floor Live | Roof Live | Snow | Total | Accessories | |
| 1 - Trimmer - SPF | 3.00" | 3.00" | 1.50" | 970 | 650 | 130 | 195 | 1 9 45 | None | |
| 2 - Trimmer - SPF | 3.00" | 3.00" | 1.50" | 970 | 650 | 130 | 195 | 1945 | None | |

| Loads | Location , | Tributary Width | Dead (0.90) | Floor Live (1.00) | Roof Live (non-snow: 1.25) | Snow (1.15) | Ċomments |
|------------------|------------|--------------------|----------------|----------------------|-------------------------------|----------------|----------------------------|
| 1 - Uniform(PSF) | 0 to 6' 6" | 5' | 20.0 | 40.0 | - | - | Residential - Living Areas |
| 2 - Uniform(PSF) | 0 to 6' 6" | 2' | 20.0 | - | 20.0 | 30.0 | |
| 3 - Uniform(PLF) | 0 to 6' 6" | N/A | 150.0 | - | - | - | |


Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.

The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@Idiae.com | TDI project no. 13-159 |

5/3/2013 10:07:53 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te



| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|-------------------|--------------|-----------------|------|-------------------------------------|
| Member Reaction (lbs) | 382 @ 0 | 1913 (1.50") | Passed (20%) | | 1.0 D + 0.75 L + 0.75 S (All Spans) |
| Shear (lbs) | 170 @ 1' 8" | 1485 | Passed (11%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Moment (Ft-Ibs) | 199 @ 1' 1 1/2" | 1434 | Passed (14%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Live Load Defl. (in) | 0.001 @ 1' 1 1/2" | 0.075 | Passed (L/999+) | | 1.0 D + 0.75 L + 0.75 S (All Spans) |
| Total Load Defl. (in) | 0.003 @ 1' 1 1/2" | 0.112 | Passed (L/999+) | | 1.0 D + 0.75 L + 0.75 S (All Spans) |

System : Wall Member Type : Header Building Use : Residential Building Code : IBC Design Methodology : ASD

SUSTAINABLE FORESTRY INITIATIVE

• Deflection criteria: LL (L/360) and TL (L/240).

FORTE

· Bracing (Lu): All compression edges (top and bottom) must be braced at 2' 3" o/c unless detailed otherwise. Proper attachment and positioning of lateral

bracing is required to achieve member stability.

Applicable calculations are based on NDS 2005 methodology.

| | | Bearing | н <mark>н</mark> ика 4 | Loads to Supports (lbs) | | | | | a * | 5 5 - 7 |
|-------------------|-----------|-----------|---------------------------|-------------------------|---------------|--------------|------|-------|-------------|------------|
| Supports | Total | Available | Required | Dead | Floor Live | Roof Live | Snow | Total | Accessories | :r |
| 1 - Trimmer - SPF | 1.50" | 1.50" | 1.50" | 263 | 90 | 45 | 68 | 466 | None | |
| 2 - Trimmer - SPF | 1.50" | 1.50" | 1.50" | 263 | 90 | 45 | 68 | 466 | None | |

| Loads | Location | "Tributary Width | Dead (0.90) | Floor Live (1.00) | Roof Live (non-snow: 1.25) | Snow (1.15) | Comments |
|------------------|------------|---------------------|----------------|----------------------|-------------------------------|----------------|----------------------------|
| 1 - Uniform(PSF) | 0 to 2' 3" | 2' | 20.0 | 40.0 | - | - | Residential - Living Areas |
| 2 - Uniform(PSF) | 0 to 2' 3" | 2' | 20.0 | - | 20.0 | 30.0 | |
| 3 - Uniform(PLF) | 0 to 2' 3" | N/A | 150.0 | - | - | - | |

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.


The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob,w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:53 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

Page 37 of 54





| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|--------------------|---------------|-----------------|------|-------------------------------------|
| Member Reaction (lbs) | 7718 @ 3" | 11419 (4.50") | Passed (68%) | | 1.0 D + 0.75 L + 0.75 S (All Spans) |
| Shear (lbs) | 5965 @ 1' 4 3/8" | 8035 | Passed (74%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Moment (Ft-lbs) | 10675 @ 2' | 19902 | Passed (54%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Live Load Defl. (in) | 0.073 @ 3' 8 3/16" | 0.242 | Passed (L/999+) | | 1.0 D + 0.75 L + 0.75 S (All Spans) |
| Total Load Defl. (in) | 0.143 @ 3' 8 9/16" | 0.363 | Passed (L/609) | | 1.0 D + 0.75 L + 0.75 S (All Spans) |

System : Wall Member Type : Header Building Use : Residential Building Code : IBC Design Methodology : ASD

SUSTAINABLE FORESTRY INITIATIVE

• Deflection criteria: LL (L/360) and TL (L/240).

^r Bracing (Lu): All compression edges (top and bottom) must be braced at 7' 9" o/c unless detailed otherwise. Proper attachment and positioning of lateral bracing is required to achieve member stability.

| | а с 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 | Bearing Loads to Supports (Ibs) | | | | | ÷я., | * ¹ | | |
|-------------------|--|---------------------------------|----------|------|---------------|--------------|------|----------------|-------------|---|
| Supports | Total | Available | Required | Dead | Floor Live | Roof Live | Snow | Total | Accessories | 2 |
| 1 - Trimmer - SPF | 4.50" | 4.50" | 3.04" | 3699 | 3034 | 1550 | 2325 | 10608 | None | |
| 2 - Trimmer - SPF | 4.50" | 4.50" | 2.02" | 2664 | 966 | 1550 | 2325 | 7505 | None | |

| tan | | Tributary | Dead | Floor Live | Roof Live | Snow | |
|---|------------|-----------|--------|------------|------------------|--------|----------------------------|
| Loads | Location | Width | (0.90) | (1.00) | (non-snow: 1.25) | (1.15) | Comments |
| 1 - Point(lb) | 2' | N/A | 2000 | 4000 | - | - | Residential - Living Areas |
| 2 - Uniform(PSF) | 0 to 7' 9" | 20' | 20.0 | - | 20.0 | 30.0 | |
| 3 - Uniform(PLF) | 0 to 7' 9" | N/A | 150.0 | - | - | - | |

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blockis) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.


The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:54 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

Page 38 of 54

Overall Length: 6' 6"



All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal.; Drawing is Conceptual

| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|-------------------|--------------|-----------------|------|-----------------------------|
| Member Reaction (lbs) | 4259 @ 1 1/2" | 7613 (3.00") | Passed (56%) | | 1.0 D + 1.0 S (All Spans) |
| Shear (lbs) | 2894 @ 1' 1/2" | 7393 | Passed (39%) | 1.15 | 1.0 D + 1.0 S (All Spans) |
| Moment (Ft-lbs) | 6398 @ 3' 3" | 15016 | Passed (43%) | 1.15 | 1.0 D + 1.0 S (All Spans) |
| Live Load Defl. (in) | 0.059 @ 3' 3" | 0.208 | Passed (L/999+) | | 1.0 D + 1.0 S (All Spans) |
| Total Load Defi. (in) | 0.112 @ 3' 3" | 0.313 | Passed (L/669) | | 1.0 D + 1.0 S (All Spans) |

System : Wall Member Type : Header Building Use : Residential Building Code : IBC Design Methodology : ASD

SUSTAINABLE FORESTRY INITIATIVE

Deflection criteria: LL (L/360) and TL (L/240).

 Bracing (Lu): All compression edges (top and bottom) must be braced at 6' 6" o/c unless detailed otherwise. Proper attachment and positioning of lateral bracing is required to achieve member stability.

| | | Bearing Loads to Supports (Ibs) | | | | | | |
|-------------------|-------|---------------------------------|----------|------|--------------|------|-------|-------------|
| Supports | Totai | Available | Required | Dead | Roof Live | Snow | Total | Accessories |
| 1 - Trimmer - SPF | 3.00" | 3.00" | 1.68" | 2016 | 1495 | 2243 | 5754 | None |
| 2 - Trimmer - SPF | 3.00" | 3.00" | 1.68" | 2016 | 1495 | 2243 | 5754 | None |

| Loads | Location | Tributary Width | Dead (0.90) | Roof Live (non-snow: 1.25) | Snow (1.15) | Comments |
|------------------|------------|--------------------|----------------|-------------------------------|----------------|----------|
| 1 - Uniform(PSF) | 0 to 6' 6" | 23' | 20.0 | 20.0 | 30.0 | |
| 2 - Uniform(PLF) | 0 to 6' 6" | N/A | 150.0 | - | - | |

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.


The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:54 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

Page 39 of 54





| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|-------------------|---------------|----------------|------|-------------------------------------|
| Member Reaction (lbs) | 7315 @ 3" | 11419 (4.50") | Passed (64%) | | 1.0 D + 0.75 L + 0.75 S (All Spans) |
| Shear (lbs) | 5319 @ 1' 4 3/8" | 9241 | Passed (58%) | 1.15 | 1.0 D + 0.75 L + 0.75 S (All Spans) |
| Moment (Ft-lbs) | 16504 @ 5' | 22888 | Passed (72%) | 1.15 | 1.0 D + 0.75 L + 0.75 S (All Spans) |
| Live Load Defl. (in) | 0.158 @ 5' | 0.317 | Passed (L/723) | | 1.0 D + 0.75 L + 0.75 S (All Spans) |
| Total Load Defl. (in) | 0.320 @ 5' | 0.475 | Passed (L/356) | | 1.0 D + 0.75 L + 0.75 S (All Spans) |

System : Wall Member Type : Header Building Use : Residential Building Code : IBC Design Methodology : ASD

SUSTAINABLE FORESTRY INITIATIVE

• Deflection criteria: LL (L/360) and TL (L/240).

Bracing (Lu): All compression edges (top and bottom) must be braced at 8' 7 15/16" o/c unless detailed otherwise. Proper attachment and positioning of lateral bracing is required to achieve member stability.

| | 8 4 K 7 | Bearing | 1 | L | Load | s to Suppor | ts (lbs) | | , r. | e |
|-------------------|---------|-----------|----------|------|---------------|--------------|----------|-------|-------------|-----|
| Supports | Total | Available | Required | Dead | Floor Live | Roof Live | Snow | Total | Accessories | × ' |
| 1 - Trimmer - SPF | 4.50" | 4.50" | 2.88" | 3715 | 1800 | 2000 | 3000 | 10515 | None | |
| 2 - Trimmer - SPF | 4.50" | 4.50" | 2.88" | 3715 | 1800 | 2000 | 3000 | 10515 | None | |

| Loads | Location | Tributary Width | Dead (0.90) | Floor Live (1.00) | Roof Live (non-snow: 1.25) | Snow (1.15) | Comments |
|------------------|----------|--------------------|----------------|----------------------|-------------------------------|----------------|----------------------------|
| 1 - Uniform(PSF) | 0 to 10' | 9' | 20.0 | 40.0 | - | - | Residential - Living Areas |
| 2 - Uniform(PSF) | 0 to 10' | 20' | 20.0 | - | 20.0 | 30.0 | |
| 3 - Uniform(PLF) | 0 to 10' | N/A | 150.0 | - | - | - | |

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.


The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:55 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

Page 40 of 54





| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|-------------------|--------------|-----------------|------|---------------------------------------|
| Member Reaction (lbs) | 1131 @ 0 | 1913 (1.50") | Passed (59%) | | 1.0 D + 0.75 L + 0.75 S (All Spans) |
| Shear (lbs) | 780 @ 5' 6 1/4" | 1958 | Passed (40%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Moment (Ft-lbs) | 1589 @ 3' 1 1/2" | 2300 | Passed (69%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Live Load Defl. (in) | 0.030 @ 3' 1 1/2" | 0.208 | Passed (L/999+) | | 1.0 D + 0.75 L + 0.75 S (All Spans) |
| Total Load Defl. (in) | 0.093 @ 3' 1 1/2" | 0.313 | Passed (1/805) | | $10D \pm 0.75I \pm 0.75S$ (All Spans) |

System : Wall Member Type : Header Building Use : Residential Building Code : IBC Design Methodology : ASD

SUSTAINABLE FORESTRY INITIATIVE

2.4

• Deflection criteria: LL (L/360) and TL (5/16").

· Bracing (Lu): All compression edges (top and bottom) must be braced at 6' 3" o/c unless detailed otherwise. Proper attachment and positioning of lateral

bracing is required to achieve member stability.Applicable calculations are based on NDS 2005 methodology.

| | | Bearing | | | Load | s to Suppor | ts (lbs) | | ана. 19 г. | × |
|-------------------|-------|-----------|----------|------|-------|--------------|----------|-------|---------------|---|
| Supports | Total | Available | Required | Dead | Floor | Roof Live | Snow | Total | Accessories | 1 |
| 1 - Trimmer - SPF | 1.50" | 1.50" | 1.50" | 767 | 250 | 156 | 234 | 1407 | None | |
| 2 - Trimmer - SPF | 1.50" | 1.50" | 1.50" | 767 | 250 | 156 | 234 | 1407 | None | |

| Loads | Location | Tributary Width | Dead (0.90) | Floor Live (1.00) | (non-snow: 1.25) | Snow (1.15) | Comments |
|------------------|------------|--------------------|----------------|----------------------|------------------|----------------|----------------------------|
| 1 - Uniform(PSF) | 0 to 6' 3" | 2' | 20.0 | 40.0 | - | - | Residential - Living Areas |
| 2 - Uniform(PSF) | 0 to 6' 3" | 2' 6" | 20.0 | - | 20.0 | 30.0 | |
| 3 - Uniform(PLF) | 0 to 6' 3" | N/A | 150.0 | - | - | - | |

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details.


(www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.

The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:55 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

Overall Length: 6' 6"



All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal.; Drawing is Conceptual

| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|-------------------|--------------|-----------------|------|-----------------------------|
| Member Reaction (lbs) | 3552 @ 1 1/2" | 7613 (3.00") | Passed (47%) | | 1.0 D + 1.0 L (All Spans) |
| Shear (lbs) | 2197 @ 5' 3 1/8" | 8035 | Passed (27%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Moment (Ft-lbs) | 5337 @ 3' 3" | 19902 | Passed (27%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Live Load Defl. (in) | 0.035 @ 3' 3" | 0.208 | Passed (L/999+) | | 1.0 D + 1.0 L (All Spans) |
| Total Load Defl. (in) | 0.053 @ 3' 3" | 0.313 | Passed (L/999+) | | 1.0 D + 1.0 L (All Spans) |

System : Wall Member Type : Header Building Use : Residential Building Code : IBC Design Methodology : ASD

SUSTAINABLE FORESTRY INITIATIVE

Deflection criteria: LL (L/360) and TL (L/240).

 Bracing (Lu): All compression edges (top and bottom) must be braced at 6' 6" o/c unless detailed otherwise. Proper attachment and positioning of lateral bracing is required to achieve member stability.

| рани и на брани 1. андини и на брани 1. | | Bearing | 18 P. 1 | Load | s to Suppor | ts (lbs) | |
|---|-------|-----------|----------|------|---------------|----------|-------------|
| Supports | Total | Available | Required | Dead | Floor Live | Total | Accessories |
| 1 - Trimmer - SPF | 3.00" | 3.00" | 1.50" | 1212 | 2340 | 3552 | None |
| 2 - Trimmer - SPF | 3.00" | 3.00" | 1.50" | 1212 | 2340 | 3552 | None |

| Loads | Location | Tributary Width | Dead (0.90) | Floor Live (1.00) | Comments |
|------------------|------------|--------------------|----------------|----------------------|----------------------------|
| 1 - Uniform(PSF) | 0 to 6' 6" | 18' | 20.0 | 40.0 | Residential - Living Areas |


Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.

The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:56 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te Overall Length: 6' 6"



All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal.; Drawing is Conceptual

| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|-------------------|--------------|-----------------|------|-----------------------------|
| Member Reaction (lbs) | 900 @ 1 1/2" | 3825 (3.00") | Passed (24%) | | 1.0 D + 1.0 L (All Spans) |
| Shear (lbs) | 618 @ 5' 5 3/4" | 2498 | Passed (25%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Moment (Ft-lbs) | 1353 @ 3' 3" | 3431 | Passed (39%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Live Load Defl. (in) | 0.010 @ 3' 3" | 0.208 | Passed (L/999+) | | 1.0 D + 1.0 L (All Spans) |
| Total Load Defl. (in) | 0.034 @ 3' 3" | 0,313 | Passed (L/999+) | | 1.0 D + 1.0 L (All Spans) |

System : Wall Member Type : Header Building Use : Residential Building Code : IBC Design Methodology : ASD

BUSTAINABLE FORESTRY INITIATIVE

Deflection criteria: LL (L/360) and TL (L/240).

Bracing (Lu): All compression edges (top and bottom) must be braced at 6' 6" o/c unless detailed otherwise. Proper attachment and positioning of lateral
bracing is required to achieve method to achieve method.

bracing is required to achieve member stability.Applicable calculations are based on NDS 2005 methodology.

| e | | Bearing | | | s to Suppor | | |
|-------------------|-------|-----------|----------|------|---------------|-------|-------------|
| Supports | Total | Available | Required | Dead | Floor Live | Total | Accessories |
| 1 - Trimmer - SPF | 3.00" | 3.00" | 1.50" | 640 | 260 | 900 | None |
| 2 - Trimmer - SPF | 3.00" | 3.00" | 1.50" | 640 | 260 | 900 | None |

| Loads | Location | Tributary Width | Dead (0.90) | Floor Live (1.00) | Comments |
|------------------|------------|--------------------|----------------|----------------------|----------------------------|
| 1 - Uniform(PSF) | 0 to 6' 6" | 2' | 20.0 | 40.0 | Residential - Living Areas |
| 2 - Uniform(PLF) | 0 to 6' 6" | N/A | 150.0 | - | |

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.

11


The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:56 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

Page 43 of 54

Overall Length: 9'



All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal.;Drawing is Conceptual

| Design Results | Actual @ Location | Allowed | Result and a | LDF | Load: Combination (Pattern) |
|-----------------------|-------------------|--------------|-----------------|------|-----------------------------|
| Member Reaction (lbs) | 1247 @ 1 1/2" | 3825 (3.00") | Passed (33%) | | 1.0 D + 1.0 L (All Spans) |
| Shear (lbs) | 964 @ 1' 1/4" | 2498 | Passed (39%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Moment (Ft-lbs) | 2651 @ 4' 6" | 3431 | Passed (77%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Live Load Defl. (in) | 0.038 @ 4' 6" | 0.292 | Passed (L/999+) | | 1.0 D + 1.0 L (All Spans) |
| Total Load Defl. (in) | 0.132 @ 4' 6" | 0.438 | Passed (L/796) | | 1.0 D + 1.0 L (All Spans) |

System : Wall Member Type : Header Building Use : Residential Building Code : IBC Design Methodology : ASD

SUSTAINABLE FORESTRY INITIATIVE

Deflection criteria: LL (L/360) and TL (L/240).

· Bracing (Lu): All compression edges (top and bottom) must be braced at 9' o/c unless detailed otherwise. Proper attachment and positioning of lateral bracing

Applicable calculations are based on NDS 2005 methodology.

| a a a a a a a a a a a a a a a a a a a | Bearing | | | Loads to Supports (ibs) | | | |
|---------------------------------------|---------|-----------|----------|-------------------------|---------------|-------|-------------|
| Supports | Totai | Available | Required | Dead | Floor Live | Total | Accessories |
| 1 - Trimmer - SPF | 3.00" | 3.00" | 1.50" | 887 | 360 | 1247 | None |
| 2 - Trimmer - SPF | 3.00" | 3.00" | 1.50" | 887 | 360 | 1247 | None |

| Loads | Location | Tributary Width | Dead (0.90) | Floor Live," (1.00) | Comments |
|------------------|----------|--------------------|----------------|------------------------|----------------------------|
| 1 - Uniform(PSF) | 0 to 9' | 2' | 20.0 | 40.0 | Residential - Living Areas |
| 2 - Uniform(PLF) | 0 to 9' | N/A | 150.0 | - | |

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.

- 3 B

The product application, input design loads, dimensions and support information have been provided by Forte Software Operator


| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:57 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

PASSED

Page 44 of 54

Overall Length: 18' 9"



All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal.; Drawing is Conceptual

| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|--------------------|--------------|----------------|------|-----------------------------|
| Member Reaction (lbs) | 2823 @ 18' 7" | 3347 (2.25") | Passed (84%) | | 1.0 D + 1.0 L (All Spans) |
| Shear (lbs) | 2763 @ 1' 5 3/8" | 8035 | Passed (34%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Moment (Ft-lbs) | 13910 @ 8' 8" | 19902 | Passed (70%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Live Load Defl. (in) | 0.305 @ 9' 2.5/16" | 0.608 | Passed (L/718) | | 1.0 D + 1.0 L (All Spans) |
| Total Load Defl. (in) | 0.893 @ 9' 3 7/8" | 0.913 | Passed (L/245) | | 1.0 D + 1.0 L (All Spans) |

System : Floor Member Type : Flush Beam Building Use : Residential Building Code : IBC Design Methodology : ASD

• Deflection criteria: LL (L/360) and TL (L/240).

Bracing (Lu): All compression edges (top and bottom) must be braced at 10' 8 7/16" o/c unless detailed otherwise. Proper attachment and positioning of lateral bracing is required to achieve member stability.

| | Bearing | | | Load | s to Suppor | ts (lbs) | |
|---------------------|---------|-----------|----------|------|---------------|----------|------------------|
| Supports | Total | Available | Required | Dead | Floor Live | Total | Accessories |
| 1 - Stud wall - SPF | 5.50" | 4.25" | 2.11" | 2324 | 1568 | 3892 | 1 1/4" Rim Board |
| 2 - Stud wall - SPF | 3.50" | 2.25" | 1.90" | 1959 | 892 | 2851 | 1 1/4" Rim Board |

• Rim Board is assumed to carry all loads applied directly above it, bypassing the member being designed.

| Loads | Location | Tributary Width | Dead (0.90) | Floor Live (1.00) | Comments |
|------------------|-------------|--------------------|----------------|----------------------|----------------------------|
| 1 - Uniform(PSF) | 0 to 18' 9" | 2' | 20.0 | 40.0 | Residential - Living Areas |
| 2 - Point(lb) | 6' | N/A | 240 | 480 | |
| 3 - Uniform(PLF) | 0 to 18' 9" | N/A | 150.0 | - | |
| 4 - Point(lb) | 0 | N/A | 240 | 480 | |

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.

The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |


5/3/2013 10:07:57 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

SUSTAINABLE FORESTRY INITIATIVE

Page 45 of 54

MEMBER REPORT second floor-Floor support, Floor: Flush Beam H-22 2 piece(s) 1 3/4 x 11 7/8" 2.0E Parallam® PSL

Overall Length: 10' 9"



All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal.;Drawing is Conceptual

| Design Results | Actual @ Location | Allowed | Résult | LDF | Load: Combination (Pattern) |
|-----------------------|-------------------|--------------|-----------------|------|-----------------------------|
| Member Reaction (lbs) | 1486 @ 1 1/2" | 3938 (1.50") | Passed (38%) | | 1.0 D + 1.0 L (All Spans) |
| Shear (lbs) | 1206 @ 9' 7 5/8" | 8035 | Passed (15%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Moment (Ft-Ibs) | 3900 @ 5' 4 1/2" | 19902 | Passed (20%) | 1.00 | 1.0 D + 1.0 L (Ali Spans) |
| Live Load Defl. (in) | 0.025 @ 5' 4 1/2" | 0.350 | Passed (L/999+) | | 1.0 D + 1.0 L (All Spans) |
| Total Load Defl. (in) | 0.090 @ 5' 4 1/2" | 0.525 | Passed (L/999+) | | 1.0 D + 1.0 L (All Spans) |

System : Floor Member Type : Flush Beam Building Use : Residential Building Code : IBC Design Methodology : ASD

• Deflection criteria: LL (L/360) and TL (L/240).

 Bracing (Lu): All compression edges (top and bottom) must be braced at 10° 6" o/c unless detailed otherwise. Proper attachment and positioning of lateral bracing is required to achieve member stability.

| | | 1000 100 100 100 1000 100 100 100 1000 100 1 | Bearing | | Load | s to Suppor | ts (lbs) | | 1 g 4 - 6 1 g 4 - 6 |
|-----------------|-----------------|--|---------------------|----------|------|---------------|----------|-------------|----------------------------|
| Supports | | Total | Available | Required | Dead | Floor Live | Total | Accessories | 5 10 1 1 10 1 1 10 1 |
| 1 - Hanger on 1 | 1 7/8" PSL beam | 1.50" | Hanger ¹ | 1.50" | 1089 | 430 | 1519 | See note 1 | |
| 2 - Hanger on 1 | 1 7/8" PSL beam | 1.50" | Hanger ¹ | 1.50" | 1089 | 430 | 1519 | See note 1 | |

• At hanger supports, the Total Bearing dimension is equal to the width of the material that is supporting the hanger

• 1 See Connector grid below for additional information and/or requirements.

| Connector: Simpson Stron | g-Tie Connectors | la la la la | in the second | i de la | i de la composición d | 1 |
|--------------------------|------------------|-------------|---|---|---|-------------|
| Support | Model | Seat Length | Top Nails | Face Nails | Member Nails | Accessories |
| 1 - Face Mount Hanger | MIU3.56/11 | 2.50" | N/A | 20-10d x 1-1/2 | 2-10d x 1-1/2 | |
| 2 - Face Mount Hanger | MIU3.56/11 | 2.50" | N/A | 20-10d x 1-1/2 | 2-10d x 1-1/2 | |

41

| Loads | Location | Tributary Width | Dead (0.90) | Floor Live (1.00) | Comments |
|------------------|-------------|--------------------|----------------|----------------------|----------------------------|
| 1 - Uniform(PSF) | 0 to 10' 9" | 2' | 20.0 | 40.0 | Residential - Living Areas |
| 2 - Uniform(PLF) | 0 to 10' 9" | N/A | 150.0 | - | |

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.

Å.

The product application, input design loads, dimensions and support information have been provided by Forte Software Operator


grief et

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:58 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

4

Page 46 of 54



| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|--------------------|--------------|-----------------|------|-----------------------------|
| Member Reaction (lbs) | 3006 @ 1 1/2" | 3938 (1.50") | Passed (76%) | | 1.0 D + 1.0 L (All Spans) |
| Shear (lbs) | 1924 @ 4' 7 5/8" | 8035 | Passed (24%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Moment (Ft-lbs) | 4133 @ 2' 10 1/2" | 19902 | Passed (21%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Live Load Defl. (in) | 0.023 @ 2' 10 1/2" | 0.183 | Passed (L/999+) | | 1.0 D + 1.0 L (All Spans) |
| Total Load Defl. (in) | 0.034 @ 2' 10 1/2" | 0.275 | Passed (L/999+) | | 1.0 D + 1.0 L (All Spans) |

System : Floor Member Type : Flush Beam Building Use : Residential Building Code : IBC Design Methodology : ASD

Deflection criteria: LL (L/360) and TL (L/240).

 Bracing (Lu): All compression edges (top and bottom) must be braced at 5' 6" o/c unless detailed otherwise. Proper attachment and positioning of lateral bracing is required to achieve member stability.

| | | Bearing | | | s to Suppor | ts (lbs) | |
|--------------------------------|-------|---------------------|----------|------|---------------|----------|-------------|
| Supports | Total | Available | Required | Dead | Floor Live | Total | Accessories |
| 1 - Hanger on 11 7/8" PSL beam | 1.50" | Hanger ¹ | 1.50" | 1071 | 2070 | 3141 | See note 1 |
| 2 - Hanger on 11 7/8" PSL beam | 1.50" | Hanger ¹ | 1.50" | 1071 | 2070 | 3141 | See note 1 |

• At hanger supports, the Total Bearing dimension is equal to the width of the material that is supporting the hanger

¹ See Connector grid below for additional information and/or requirements.

| Connector: Simpson Strong-Tie Connectors | | | | | | | | |
|--|---------------------|-------------|-----------|------------|--------------|-------------|--|--|
| Support | Model | Seat Length | Top Nails | Face Nails | Member Nails | Accessories | | |
| 1 - Face Mount Hanger | Connector not found | N/A | N/A | N/A | N/A | | | |
| 2 - Face Mount Hanger | Connector not found | N/A | N/A | N/A | N/A | | | |

| Loads | Location | Tributary Width | Dead (0.90) | Floor Live (1.00) | Comments |
|------------------|------------|--------------------|----------------|----------------------|----------------------------|
| 1 - Uniform(PSF) | 0 to 5' 9" | 18' | 20.0 | 40.0 | Residential - Living Areas |

Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.

The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:58 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te





| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|-------------------|--------------|----------------|------|-----------------------------|
| Member Reaction (lbs) | 2843 @ 18' 2" | 5206 (3.50") | Passed (55%) | | 1.0 D + 1.0 L (All Spans) |
| Shear (lbs) | 2442 @ 17' 5/8" | 8035 | Passed (30%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Moment (Ft-lbs) | 12442 @ 9' 3" | 19902 | Passed (63%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Live Load Defl. (in) | 0.488 @ 9' 3" | 0.594 | Passed (L/439) | | 1.0 D + 1.0 L (All Spans) |
| Total Load Defl. (in) | 0.764 @ 9' 3" | 0.892 | Passed (L/280) | | 1.0 D + 1.0 L (All Spans) |

System : Floor Member Type : Flush Beam Building Use : Residential Building Code : IBC Design Methodology : ASD

• Deflection criteria: LL (L/360) and TL (L/240).

• Bracing (Lu): All compression edges (top and bottom) must be braced at 12' 2 11/16" o/c unless detailed otherwise. Proper attachment and positioning of lateral bracing is required to achieve member stability.

| $\begin{array}{cccccccccccccccccccccccccccccccccccc$ | 4 ÷.4 | Bearing | : | Load | s to Suppor | ts (ibs) | |
|--|-------|-----------|----------|------|---------------|----------|------------------|
| Supports | Total | Available | Required | Dead | Floor Live | Total | Accessories |
| 1 - Stud wall - SPF | 5.50" | 4.25" | 1.92" | 1044 | 1850 | 2894 | 1 1/4" Rim Board |
| 2 - Stud wail - SPF | 3.50" | 3.50" | 1.91" | 1026 | 1817 | 2843 | Blocking |

• Rim Board is assumed to carry all loads applied directly above it, bypassing the member being designed.

i Fa

Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

| Loads | Location | Tributary Width | Dead (0.90) | Floor Live (1.00) | Comments |
|------------------|-------------|--------------------|----------------|----------------------|----------------------------|
| 1 - Uniform(PSF) | 0 to 18' 4" | 5' | 20.0 | 40.0 | Residential - Living Areas |

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.

The product application, input design loads, dimensions and support information have been provided by Forte Software Operator


SUSTAINABLE FORESTRY INITIATIVE

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:07:59 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

Page 48 of 54

Overall Length: 18' 1"



All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal.; Drawing is Conceptual

| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|-------------------|--------------|----------------|------|-----------------------------|
| Member Reaction (lbs) | 2804 @ 17' 11" | 5206 (3.50") | Passed (54%) | | 1.0 D + 1.0 L (All Spans) |
| Shear (lbs) | 2403 @ 1' 5 3/8" | 8035 | Passed (30%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Moment (Ft-lbs) | 12096 @ 9' 1 1/2" | 19902 | Passed (61%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Live Load Defl. (in) | 0.462 @ 9' 1 1/2" | 0.586 | Passed (L/457) | | 1.0 D + 1.0 L (All Spans) |
| Total Load Defl. (in) | 0.723 @ 9' 1 1/2" | 0.879 | Passed (L/292) | | 1.0 D + 1.0 L (All Spans) |

System : Floor Member Type : Flush Beam Building Use : Residential Building Code : IBC Design Methodology : ASD

SUSTAINABLE FORESTRY INITIATIVE

Deflection criteria: LL (L/360) and TL (L/240).

Bracing (Lu): All compression edges (top and bottom) must be braced at 12' 7 1/2" o/c unless detailed otherwise. Proper attachment and positioning of lateral bracing is required to achieve member stability.

| dar _{en} | | · Bearing | | | s to Suppor | ts (lbs) | |
|---------------------|-------|-----------|----------|------|---------------|----------|------------------|
| Supports | Total | Available | Required | Dead | Floor Live | Total | Accessories |
| 1 - Stud wall - SPF | 5.50" | 4.25" | 1.90" | 1030 | 1825 | 2855 | 1 1/4" Rim Board |
| 2 - Stud wall - SPF | 3.50" | 3.50" | 1.88" | 1012 | 1792 | 2804 | Blocking |

• Rim Board is assumed to carry all loads applied directly above it, bypassing the member being designed.

Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

| Loads | Location | Tributary Width | Dead (0.90) | Floor Live (1.00) | Comments |
|------------------|-------------|--------------------|----------------|----------------------|----------------------------|
| 1 - Uniform(PSF) | 0 to 18' 1" | 5' | 20.0 | 40.0 | Residential - Living Areas |


Weyerhaeuser Notes Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.

The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

Forte Software Operator Job Notes Robert Williams, PE Stratton Residence TDI Associates, Inc. Architects & Engineers (262) 437-0400 Stratton Residence bob.w@tdiae.com TDI project no. 13-159

5/3/2013 10:07:59 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

Overall Length: 18' 1"



All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal.; Drawing is Conceptual

| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|-------------------|---------------|----------------|------|-----------------------------|
| Member Reaction (lbs) | 7489 @ 17' 11" | 10413 (3.50") | Passed (72%) | | 1.0 D + 1.0 L (All Spans) |
| Shear (lbs) | 6418 @ 1' 5 3/8" | 16071 | Passed (40%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Moment (Ft-lbs) | 32307 @ 9' 1 1/2" | 39805 | Passed (81%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Live Load Defl. (in) | 0.508 @ 9' 1 1/2" | 0.586 | Passed (L/415) | | 1.0 D + 1.0 L (All Spans) |
| Total Load Defl. (in) | 0.965 @ 9' 1 1/2" | 0.879 | Failed (L/219) | | 1.0 D + 1.0 L (All Spans) |

System : Floor Member Type : Flush Beam Building Use : Residential Building Code : IBC Design Methodology : ASD

SUSTAINABLE FORESTRY INITIATIVE

• Deflection criteria: LL (L/360) and TL (L/240).

• Bracing (Lu): All compression edges (top and bottom) must be braced at 13' 10 13/16" o/c unless detailed otherwise. Proper attachment and positioning of lateral bracing is required to achieve member stability.

| | | Bearing | | | s to Suppor | ts (lbs) | |
|---------------------|-------|-----------|----------|------|---------------|----------|------------------|
| Supports | Total | Available | Required | Dead | Floor Live | Total | Accessories |
| 1 - Stud wall - SPF | 5.50" | 4.25" | 2.53" | 3610 | 4015 | 7625 | 1 1/4" Rim Board |
| 2 - Stud wall - SPF | 3.50" | 3.50" | 2.52" | 3547 | 3942 | 7489 | Blocking |

• Rim Board is assumed to carry all loads applied directly above it, bypassing the member being designed.

Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

| Loads | Location | Tributary Width | Dead (0.90) | Floor Live (1.00) | Comments |
|------------------|-------------|--------------------|----------------|----------------------|----------------------------|
| 1 - Uniform(PSF) | 0 to 18' 1" | 11' | 20.0 | 40.0 | Residential - Living Areas |
| 2 - Uniform(PLF) | 0 to 18' 1" | N/A | 150.0 | - | |

Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.

The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes | | | | |
|---|----------------------------|--|--|--|--|
| Robert Williams, PE | Stratton Residence | | | | |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect | | | | |
| (262) 437-0400 | Fox Point, Wisconsin | | | | |
| bob.w@tdiae.com | TDI project no. 13-159 | | | | |

5/3/2013 10:08:00 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

Overall Length: 3' 3"



All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal.; Drawing is Conceptual

| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) | |
|-----------------------|-------------------|--------------|-----------------|------|-----------------------------|--|
| Member Reaction (lbs) | 1766 @ 0 | 1913 (1.50") | Passed (92%) | | 1.0 D + 1.0 L (All Spans) | |
| Shear (Ibs) | 793 @ 2' 4 1/4" | 2498 | Passed (32%) | 1.00 | 1.0 D + 1.0 L (All Spans) | |
| Moment (Ft-lbs) | 1435 @ 1' 7 1/2" | 3431 | Passed (42%) | 1.00 | 1.0 D + 1.0 L (All Spans) | |
| Live Load Defl. (in) | 0.007 @ 1' 7 1/2" | 0.108 | Passed (L/999+) | | 1.0 D + 1.0 L (All Spans) | |
| Total Load Defl. (in) | 0.010 @ 1' 7 1/2" | 0.162 | Passed (1/999+) | | 1.0 D + 1.0 L (All Spans) | |

System : Wall Member Type : Header Building Use : Residential Building Code : IBC Design Methodology : ASD

· Deflection criteria: LL (L/360) and TL (L/240).

Bracing (Lu): All compression edges (top and bottom) must be braced at 3' 3" o/c unless detailed otherwise. Proper attachment and positioning of lateral
bracing is required to achieve member stability.

Applicable calculations are based on NDS 2005 methodology.

| · · · | Bearing | | | Load | s to Suppor | ts (lbs) | <i>v</i> ! |
|-------------------|---------|-----------|----------|------|---------------|----------|-------------|
| Supports | Total | Available | Required | Dead | Floor Live | Total | Accessories |
| 1 - Trimmer - SPF | 1.50" | 1.50" | 1.50" | 596 | 1170 | 1766 | None |
| 2 - Trimmer - SPF | 1.50" | 1.50" | 1.50" | 596 | 1170 | 1766 | None |

| Loads | . Location | Tributary Width | Dead (0.90) | Floor Live (1.00) | Comments |
|------------------|------------|--------------------|----------------|----------------------|----------------------------|
| 1 - Uniform(PSF) | 0 to 3' 3" | 18' | 20.0 | 40.0 | Residential - Living Areas |

Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not Intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.


The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

SUSTAINABLE FORESTRY INITIATIVE

| Forte Software Operator | Job Notes | | | | |
|---|----------------------------|--|--|--|--|
| Robert Williams, PE | Stratton Residence | | | | |
| IDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect | | | | |
| 262) 437-0400 | Fox Point, Wisconsin | | | | |
| pob.w@tdiae.com | TDI project no. 13-159 | | | | |

5/3/2013 10:08:00 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAM/NG.4te





| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|-------------------|--------------|-----------------|------|-----------------------------|
| Member Reaction (lbs) | 1452 @ 0 | 3806 (1.50") | Passed (38%) | | 1.0 D + 1.0 L (All Spans) |
| Shear (lbs) | 835 @ 4' 1 5/8" | 8035 | Passed (10%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Moment (Ft-lbs) | 1905 @ 2' 7 1/2" | 19902 | Passed (10%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Live Load Defl. (in) | 0.010 @ 2' 7 1/2" | 0.175 | Passed (L/999+) | | 1.0 D + 1.0 L (All Spans) |
| Total Load Defl. (in) | 0.015 @ 2' 7 1/2" | 0.262 | Passed (L/999+) | | 1.0 D + 1.0 L (All Spans) |

System : Wall Member Type : Header Building Use : Residential Building Code : IBC Design Methodology : ASD

Deflection criteria: LL (L/360) and TL (L/240).

 Bracing (Lu): All compression edges (top and bottom) must be braced at 5' 3" o/c unless detailed otherwise. Proper attachment and positioning of lateral bracing is required to achieve member stability.

| n national and a set of the set | ار اراد ۲۰۰۰ م | Bearing | 5 5 5 5 5 5 10 5 10 5 10 5 10 5 10 5 10 | Load | s to Suppor | ts (lbs) | 1 1.0 1 1.0 1 1.0 | р. в .е. |
|--|-------------------|-----------|--|------|---------------|----------|-------------------------|-----------------|
| Supports | Total | Available | Required | Dead | Floor Live | Total | Accessories | · · · |
| 1 - Trimmer - SPF | 1.50" | 1.50" | 1.50" | 507 | 945 | 1452 | None | |
| 2 - Trimmer - SPF | 1.50" | 1.50" | 1.50" | 507 | 945 | 1452 | None | |

| Loads | Location | Tributary Width | Dead (0.90) | Floor Live (1.00) | Comments |
|------------------|------------|--------------------|----------------|----------------------|----------------------------|
| 1 - Uniform(PSF) | 0 to 5' 3" | 9' | 20.0 | 40.0 | Residential - Living Areas |

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.


The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:08:01 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

SUSTAINABLE FORESTRY INITIATIVE





| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|---------------------|--------------|-----------------|------|-----------------------------|
| Member Reaction (lbs) | 1545 @ 4' 3" | 1913 (1.50") | Passed (81%) | | 1.0 D + 1.0 L (All Spans) |
| Shear (lbs) | 1249 @ 3' 2 1/4" | 3038 | Passed (41%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Moment (Ft-lbs) | 2277 @ 2' 6" | 4614 | Passed (49%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Live Load Defl. (in) | 0.007 @ 2' 1 7/8" | 0.142 | Passed (L/999+) | | 1.0 D + 1.0 L (All Spans) |
| Total Load Defl. (in) | 0.013 @ 2' 1 13/16" | 0.213 | Passed (L/999+) | | 1.0 D + 1.0 L (All Spans) |

System : Wall Member Type : Header Building Use : Residential Building Code : IBC Design Methodology : ASD

Deflection criteria: LL (L/360) and TL (L/240).

Bracing (Lu): All compression edges (top and bottom) must be braced at 4' 3" o/c unless detailed otherwise. Proper attachment and positioning of lateral
bracing is required to achieve member stability.

bracing is required to achieve member stability. • Applicable calculations are based on NDS 2005 methodology.

| | Bearing | | | Load | s to Suppor | ts (lbs) | |
|-------------------|---------|-----------|----------|------|---------------|----------|-------------|
| Supports | Total | Available | Required | Dead | Floor Live | Total | Accessories |
| 1 - Trimmer - SPF | 1.50" | 1.50" | 1.50" | 644 | 615 | 1259 | None |
| 2 - Trimmer - SPF | 1.50" | 1.50" | 1.50" | 740 | 805 | 1545 | None |

| Loads | | Tributary | Dead | Floor Live | |
|------------------|------------|-----------|--------|------------|----------------------------|
| LUdus | Location | Width | (0.90) | (1.00) | Comments |
| 1 - Uniform(PSF) | 0 to 4' 3" | 2' | 20.0 | 40.0 | Residential - Living Areas |
| 2 - Uniform(PLF) | 0 to 4' 3" | N/A | 150.0 | - | |
| 3 - Point(lb) | 2' 6" | N/A | 540 | 1080 | |

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.

The product application, input design loads, dimensions and support information have been provided by Forte Software Operator


SUSTAINABLE FORESTRY INITIATIVE

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:08:01 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

Page 53 of 54

Overall Length: 17' 11"



All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal.; Drawing is Conceptual

| Design Results | Actual @ Location | Allowed | Result | LDF | Load: Combination (Pattern) |
|-----------------------|-------------------|--------------|----------------|------|-----------------------------|
| Member Reaction (lbs) | 9351 @ 4" | 9483 (4.25") | Passed (99%) | | 1.0 D + 1.0 L (All Spans) |
| Shear (lbs) | 9163 @ 1' 5 3/8" | 12053 | Passed (76%) | 1.00 | 1.0 D + 1.0 L (All Spans) |
| Moment (Ft-Ibs) | 24355 @ 3' | 29854 | Passed (82%) | 1.00 | 1.0 D + 1.0 L (Ali Spans) |
| Live Load Defl. (in) | 0.500 @ 8' 5/8" | 0.575 | Passed (L/414) | | 1.0 D + 1.0 L (All Spans) |
| Total Load Defl. (in) | 0.778 @ 8' 1" | 0.863 | Passed (L/266) | | 1.0 D + 1.0 L (All Spans) |

System : Floor Member Type : Flush Beam Building Use : Residential Building Code : IBC Design Methodology : ASD

• Deflection criteria: LL (L/360) and TL (L/240).

Bracing (Lu): All compression edges (top and bottom) must be braced at 11' 3/16" o/c unless detailed otherwise. Proper attachment and positioning of lateral bracing is required to achieve member stability.

| | Bearing | | | Load | s to Suppor | ts (lbs) | • |
|-----------------------------|---------|-----------|----------|------|---------------|----------|------------------|
| Supports | Total | Available | Required | Dead | Floor Live | Total | Accessories |
| 1 - Plate on concrete - SPF | 5.50" | 4.25" | 4.19" | 3236 | 6127 | 9363 | 1 1/4" Rim Board |
| 2 - Plate on steel - SPF | 5.50" | 5.50" | 1.50" | 1027 | 1706 | 2733 | Blocking |

• Rim Board is assumed to carry all loads applied directly above it, bypassing the member being designed.

Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

| Loads | Location | Tributary Width | Dead (0.90) | Floor Live (1.00) | Comments |
|------------------|--------------|--------------------|----------------|----------------------|----------------------------|
| 1 - Uniform(PSF) | 0 to 17' 11" | 2' | 20.0 | 40.0 | Residential - Living Areas |
| 2 - Point(Ib) | 3' | N/A | 3200 | 6400 | |

Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Refer to current Weyerhaeuser literature for installation details. (www.woodbywy.com) Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards.


The product application, input design loads, dimensions and support information have been provided by Forte Software Operator

| Forte Software Operator | Job Notes |
|---|----------------------------|
| Robert Williams, PE | Stratton Residence |
| TDI Associates, Inc. Architects & Engineers | Joy Peot Shields Architect |
| (262) 437-0400 | Fox Point, Wisconsin |
| bob.w@tdiae.com | TDI project no. 13-159 |

5/3/2013 10:08:02 PM Forte v4.0, Design Engine: V5.6.1.203 13-159 WOOD FRAMING.4te

(2) SUSTAINABLE FORESTRY INITIATIVE









8535 W. Kaul Avenue Milwaukee, WI 53225

Rec # 13279

VILLAGE OF FOX POINT MILWAUKEE COUNTY, WISCONSIN

9/16/5-1 ck. 440/ No.

APPLICATION FOR PERMIT

TO THE INSPECTION DEPARTMENT:

i.

-

The undersigned hereby applies for a permit for the execution of electrical installation for light, heat or power, as hereinafter prescribed.

| | | e exact street and number. I | o not Brid comon, | | |
|---------|-------------------------------|---------------------------------------|-----------------------|-------------|---|
| | Owner Norbert | Friedlen | | | |
| | Lot | | | | |
| 4. | Building or structure | | | | |
| 5. | | | | | |
| | - y' | Number | Rate of Fee | | Fees |
| 6. | Lighting Outlets | · · · · · · · · · · · · · · · · · · · | | a \$ 10 | |
| | Fixtures | | | - | .20 |
| 8. | Range Circuit or Outlet | | | | 1.00 |
| 9. | Range Connection | | | | |
| | Water Heaters & other Heat | | | | ······································ |
| 11. | | Ea | h Additional Kilowatt | 10 | |
| 12. | | | | | |
| 13. | | | | | ••••••••••••••••••••••••••••••••••••••• |
| 14. | | | | | |
| 15. | | | 1.r11.r. per 11.r | .10 | |
| 10. | Individual Outlets | | | ".05 | |
| 16. | Rectifiers and Transformers | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | Estimated cost \$ | | Total fees | 1.40 | |
| | e of inspection { Fixtures | Will call | | Note: Minim | um Fee \$1.00 |
| | · | Will call | | Note: Minin | um Fee \$1.00 |
| | e of inspection {Wiring | Will call | | Note: Minim | num Fee \$1.00 |

Address....

8416 W. Lisbon Avenue

THE OF FOR FOR SEP 10 FORT

INSPECTION DEPARTMENT VILLAGE OF FOX POINT

£

r

. -


7200 North Santa Monica Blvd. Milwaukee, Wisconsin 53217

APPLICATION FOR CERTIFICATE OF OCCUPANCY

| No | Date |
|---|---|
| | Fox Point, Wisconsin |
| • | |
| | |
| | ON IT NO KERI SARAJIAN |
| (Stre | |
| Building Owner's Telephone No. 714 - 534 - 60 | 695 |
| Name of Business or Firm | |
| Location of Business or Firm in Building | |
| Telephone No. of Business or Firm | |
| | Female |
| | <u></u> |
| Business or Firm Owner's Name | - A ₂ |
| Owner's Residence Address(Str | eet) (City) |
| Owner's Residential Telephone No | |
| | pairs or alterations are performed, they will be made by: |
| Applicant Owner Occupant | Other |
| | Applicant's Signature |
| | |
| Approved Date | IQU Fee Permit Issued GC#F45403 |

... My upriling Mus Edow Dory #17 AFCT 14) curre Belin Scient Sf Unith wort 25" Soppet cash the as horf P Stud Ilds Var Sell 19 Kne Shy Ilde in Flent USIT It we know that no theat 19 Work PU Curush TU CUMPS Cutsen PETCH BUNGHAN BULLER


(Conto Decing - Ar And 19 FOWER AT 3) Court telogy cour Port will 1)- Pros Unshird SAGARA () Furne bet he Mankaha) Octure Usine D was that that O & 25 AF Alt Unit BOTH CACH V Cours we such E Con 12 for which the 14 Moter franke



PDF created with pdfFactory Pro trial version www.pdffactory.com

(Greg) (915-2493) D Plaster ling in ortsing will - Colare dasy 3) Lot This lein Ruces with WARFor Barry (Eng Szen Slow 3 Outlet Missing Fren Bedraun (Emit Upstavi) (Excens Zivo " ut citil sparse) (41/2) A for the part for her (2) 28125 SAN VS-4 Court And F Hussey (seens Flor / heres T (5002) 3 Ply 1005 Hiss Fill to Be ties Due with 3 Hisso. Fischer Cinnya R.-4.2 Dealing The uses (2). 5/8 322.42 Ð Ð Non il in Duny 6-12 reda @ 4 Ply. Den @ String Prayness Deflerby the Plan (orach supports my 2-ply Berny \$ PVC UN TYE

,



5. 4 d $(\mathcal{L}$ 859 Plumber Classen n. Hala 6 15 Owner ... Drainlayer? **Application and Record** 1015-8000000 Address 320 4 - Of Aman Que Address ... Fox Point, Wis., R To the VILLAGE OF FOX POINT, PLUMBING AND WATER INSPECTION DEPARTMENT: The undersigned hereby make application to do the work of ______ consisting of laying a inch.laying a.... inch e Afre PERMITS ISSUED drain pipe from Main to Curb service pipe from Main to Curb; Kind No. lot line to premises at curb to to No. 1015 - E Generlie Pl earles El <u>799</u> Sewer and Plumbing 1015 No. ... 54 Water Remarks: Remarks: 542 Street 528 the following premises owned by Name of owner Address Description Lot Block Top Parp. And. Denem .4 W 1/4 Jecs 78 N-RVLE In the performance of this work the undersigned Plumber or Drain Layer hereby agree to be bounden by and submit to all statutes, city ordinances, and rules and regulations prescribed by the Village Board for the government of Plumbers and House Drain Layers. clarence n 2 Jackory License No. <u>2.317</u> Plumber FEES 116 FIXTURES WITH DRAIN OR WATER CONNECTIONS Storm Sewer Connection ... \$. No. No. Sanitary Sewer Connection 830 2-Bath Tubs Wash Basins Water Connection 400 tures 2 a 2----Ice Box Water Closets Fix 700 Water Meter Showers 20 Laundry Tubs Sanitary Bubblers ... Basement Drains .. Total HHI-HEATER 1 Deposit to cover street repairs <u>25.</u>53 Sinks Urinals Permit Clerkwater service pipe was laid in E. Chucaninch...... othya, 233 anitary sewer connection was made in fife manhole. au - C./(......inch......storm sewer connection was made in.....feet.....of manhole. Outside Drain House Drain Report Inspection Soil and Under Floor Report **Final Inspection** Return Water On On Off Off Installation Approved Application Approved IN Ĺ Water and Plumbing Inspector MARKS COMPLAINT RECORD ŧŧ 306385 Knr 330 ~ as #2650 (Peru 375 ta Lewe

| | 1 | | - | | , | |
|---|------------|-----|--------|---|---|-------|
| Owner R. E. Bethke | I | | | | | |
| Plumber Clarence N. Hahn W-543 Permit No. S-799 859 Entered | ¢ | | | | | |
| Street 1015 E. Quarles Place |) | | | | | |
| | | | · · | | | : |
| | | | | - | | I |
| | | | , , | | | |
| | | | | | | 4 |
| | | · · | | | | ł |

· · · · · ·

1

| Plumber C. S. C. Drainlayer Address 4924 - 9112 | laby | No | 2681 | | | | 11 VI C | 50 |
|--|--|---|--|---|------------|---|-------------------------------------|---|
| Drainlaver | Υ | | | n | | wner | H bud | len |
| Address 4924 - 912 | hit A | ppiicati | ion and | Keco | ra | | 1015-0 | marle |
| rel. No14 1-280 | ,0 | | | | | | 9-11-57 | |
| To the VILLAGE OF | | PLUMBING | AND WATE | R INSPEC | | | | • |
| y make application to do th | | | | | | | | |
| aying ainch. | - | | | _ | | | PERMITS IS | SUED No. |
| lrain pipe from Main to | Lot line | service pij | pe from M | ain to | Lot line | . | | |
| o Building | | | uilding | | | S | ewer and Plumbin | ng. Zese |
| o Dunung | | 10 | unung | | | | Tater | 1 |
| | 1 | at | | | | | treet | |
| 1015- 8 | O , k | 0 | | | | | leter | |
| | Address at which | work is to be | done | Fox P | Point, Wis | ^{5.} W | Vater Usage | |
| <u></u> . | Subdivisio | n | | | 1 | Lot | ····· | Block |
| | | | | | - | | | |
| In the performance of the statutes, city ordinances, and | his work the und I rules and regula | lersigned Plur ations prescri | mber or Drain bed by the V | Layer he | reby agre | es to b e gover | e bounden by and nment of Plumbo | l submit to a ers and Hou |
| Drain Layers. License No. | | | | | | 2 1 | | |
| License No | | | \leq | -J.C | -00 00 | 5 | | Plumb |
| FIXTURES WITH DRAI | N OR WATER C | CONNECTION | NS T | | | 1 | FEES | |
| No. | • |] | No. | Water 1 | Usage | •••••• | \$ | |
| Hose Bibs | Dishwasher | · | 1 | Sanitar | y Sewer (| Connect | ion | |
| Bath Tubs | | ns | | | | | | |
| Sump Pump | | ets | | Water | Heater | | 4 | ····· |
| Laundry Tubs | | | | Fixtures | s | | | 1.50 |
| | | | | | | | | |
| Sanitary Bubblers | | | | | | | im Zee * | |
| Sinks | Garbage Di | sposal | | Tot | ai | | 271 Lle | 5100 |
| | | | | | | | | |
| Water Heater | Sprinkling | System | | | to cover | street | repairs | |
| Ainch | | water service | e pipe was la | Deposit id in | to cover | street | Plank | Permit Cle |
| Af | | water service | e pipe was la | Deposit | to cover | street | Plank feet | Permit Cler |
| Af Curb box is locatedf | Ceetof | water service Meter No wer connectio | e pipe was la | Deposit id in in | to cover | street | | Permit Cler |
| Ainchf | eetof Water sanitary sev of man | water service Meter No wer connectio hole | e pipe was la | Deposit id in in | to cover | street | <i>Plank</i> | Permit Cles |
| Ainchf Curb box is locatedf inch Ainch | Ceetof | Meter No wer connectio | e pipe was la | Deposit id in in | to cover | street | ed | Permit Cler |
| Ainch | eetof Water sanitary sev of mank storm sev | Meter No wer connectio hole | e pipe was la n was made n was made | Deposit | to cover | street <u> <u> </u> </u> | <i>Plank</i> | Permit Clex |
| Ainch | eetof Water sanitary sev of mank storm sev | Meter No wer connectio hole | e pipe was la n was made n was made | Deposit | to cover | street <u> <u> </u> </u> | <i>Plank</i> | Permit Cles |
| Ainch | eetof Water sanitary sev of mank storm sev | Meter No wer connectio hole | e pipe was la n was made n was made | Deposit | to cover | street <u> <u> </u> </u> | <i>Plank</i> | Permit Cles |
| Ainch. Curb box is locatedf inch. Ainch. feet. Ainch. | ceetof | Meter No wer connectio hole wer connectio | e pipe was la n was made n was made | Deposit id in in | to cover | street <u> <u> </u> </u> | <i>Plank</i> | Permit Clex |
| Ainch. Curb box is locatedf inch. Ainch. feet. Ainch. | eetof Water sanitary sev of manl storm sev of manl | Meter No Wer connection hole wer connection hole Report Ro | e pipe was la m was made n was made | Deposit | tion F | street | ed Final Inspectio | Permit Clex |
| Ainch Curb box is locatedf inch Ainch feet Ainch feet Outside Sewer Report | eetof | Meter No Wer connection hole Report Ro | e pipe was la n was made n was made | Deposit id in in in ing Inspect | to cover | street <u> <u> </u> </u> | Final Inspection | Permit Cles |
| Ainch | eetof Water sanitary sev of manl storm sev of manl | Meter No wer connectio hole Report Ro | e pipe was la m was made n was made | Deposit | to cover | street | Final Inspection | Permit Cles |
| Ainchf Curb box is locatedf inch | eetof | Meter No wer connectio hole Report Ro | e pipe was la n was made n was made | Deposit id in in in ing Inspect | to cover | street <u> <u> </u> </u> | Final Inspectio | Permit Cler |
| Ainchf Curb box is locatedf inch | Teetof | Meter No wer connectio hole Report Ro | e pipe was la n was made n was made | Deposit id in in in ing Inspect | to cover | street <u> <u> </u> </u> | Final Inspection | Permit Cler |
| Ainch | eetof | Meter No Wer connection hole Report Ro | e pipe was la n was made n was made | Deposit id in in in ing Inspect | to cover | street <u> <u> </u> </u> | Final Inspectio | Permit Cler |
| Ainch | eetof | Meter No Wer connection hole Report Ro | e pipe was la n was made n was made ough In Plumb | Deposit id in in in ing Inspect | to cover | street <u> <u> </u> </u> | Final Inspectio | Permit Cler |
| Ainch | eetof | Meter No Wer connection hole Report Ro | e pipe was la n was made n was made ough In Plumb | Deposit | to cover | street | Final Inspectio | Permit Cler |
| Ainch. Curb box is locatedf inch. Ainch. feet. Afeet. Outside Sewer Report Installation Approved As Built | EMARKS | Meter No Wer connection hole wer connection hole Report Ro | e pipe was la m was made n was made | Deposit | to cover | street <u> <u> </u> </u> | Final Inspection | Permit Clex of of of of of of of of of of |
| Ainch. Curb box is locatedf inch. Ainch. feet. Afeet. Outside Sewer Report Installation Approved As Built | EMARKS | Meter No Wer connection hole wer connection hole Report Ro | e pipe was la m was made n was made | Deposit | to cover | street <u> <u> </u> </u> | Final Inspection | Permit Cles of of of of of of of of of of |
| Ainch. Curb box is locatedf inch. Afeet. Afeet. Outside Sewer Report Outside Sewer Report Installation Approved As Built | EMARKS | Meter No Wer connection hole wer connection hole Report Ro | e pipe was la m was made n was made | Deposit | to cover | street | Final Inspection | Permit Clex of of of of of of of of of of |
| Ainch. Curb box is locatedf inch. Ainch. feet. Afeet. Outside Sewer Report Installation Approved As Built | Ceetof Water Sanitary sev Sanitary sev Storm sev Storm sev Of manl Inside Sewer | Meter No Wer connection hole Report Ro | e pipe was la m was made m was made m was made m was made m Applic | Deposit | to cover | street | Final Inspection | Permit Clex of of of of of of of of of of |
| Ainch. Curb box is locatedf inch. Ainch. feet. Ainch. feet. Outside Sewer Report Installation Approved As Built R Justilling add in Clef Locus | Ceetof Water Sanitary sev Sanitary sev Storm sev Storm sev Of manl Inside Sewer | Meter No Wer connection hole Report Ro | e pipe was la m was made m was made m was made m was made m Applic | Deposit | to cover | street | Final Inspection | Permit Cler of of of of of of of of |
| Ainch. Curb box is locatedf inch. Ainch. feet. Ainch. feet. Outside Sewer Report Installation Approved As Built R Justilling add in Clef Locus | Ceetof Water Sanitary sev Sanitary sev Storm sev Storm sev Of manl Inside Sewer | Meter No Wer connection hole Report Ro | e pipe was la m was made m was made m was made m was made m Applic | Deposit | to cover | street | Final Inspection | Permit Cler of of of of of of of of of |
| Ainch. Curb box is locatedf inch. Ainch. feet. Ainch. feet. Outside Sewer Report Installation Approved As Built R Justilling add in Clef Locus | Ceetof Water Sanitary sev Sanitary sev Storm sev Storm sev Of manl Inside Sewer | Meter No Wer connection hole Report Ro | e pipe was la m was made m was made m was made m was made m Applic | Deposit | to cover | street | Final Inspection | Permit Cler of of of of of of of of |

Owner 14, Friedlen

Plumber J. C. Scholedung 2681 Permit No.

Street 1015 C. Quarlie Pl.

· · ·

•

- **-- **-

| 0 . | | | Village of Fox Point | | | |
|-------------------------|-----------------------------------|------------------------------|--------------------------|--|---------------------------------------|--|
| Liling Fee | \$75" Rec | 2# 439837200 | N. Santa Monica B | lvd. | | |
| Data Carl and the st | 61712 |] | Fox Point, WI 53217 | | No. 15547 | - |
| Date Submitted | (2-1)=(2) | | (414) 351-8900 | | No. 1934 1 | · · · · · · · · · · · · · · · · · · · |
| <u> </u> | , | | | | | ······································ |
| (The see density) | | | ION FOR E | | | |
| i ne undersign | ned hereby applies for | | | | | • |
| Type of Project | KEDIPEI | | Address | 1015 EC | PUARLES | S Man |
| Resi | Idence, Garage, Store, Office, Sc | chool, Fence, Shed, Sign, Sv | vimming Pool, Etc. | <u> </u> | | |
| Lot | Block | | Subdivision | | District | |
| Does contemplated | d structure violate the | Village zoning ordin | | | | |
| Height of Structure | e291 | 1611, | - 2 517 |) (in the part of | | (stories or feet) |
| Width (parallel to) | highway) EW | 60'0" | (feet) Depth (perpendi | cular to highway) | 15 1051 | (feet) |
| Distance: Street Li | ine to Front Line of Str | | | | | (feet) |
| Distance: Side Lot | Line to Structure | 47.22' | e W/EST | 40.68 C | EAST | |
| Type of Constructi | | ME | Exterior f | finish 5/6 | | ON E VENER |
| | V Frame | e, Brick-tile, etc. | | S | tucco, Siding, Brick Veneer, E | tc, |
| Height of front yar | rd above street grade_ | <u> </u> | | · · · · | | |
| Number of rooms | | ~[| Baths_ | 412 | | |
| Ga | arage 👘 🕐 | ATE | | | | |
| Estimated cost Bu | ilding | / | , B. P. | | | |
| | ructure | | | | | |
| Is there a private gara | | ATACH | | | | |
| | ed garage violate the Vill | | ? | | | |
| SizeX | | Jumber of Stalls | 3 | Where Situ: | ated <u>BUACH</u> | <u>ep.</u> |
| Have plans been si | ubmitted to the Wiscon | isin Department of I | Industry, Labor and Hu | man Relations for e | examination and approva | al? <u>NO</u> |
| Have plans been ap | pproved as being in co | mpliance with all ap | oplicable sections of th | e Wisconsin Admin | istrative code? | 10 . |
| | the following duplicate | e plans | | in number, which | I certify I will conform | to in the work |
| hereby applied for | 5. 1 1/and | 1.1 / | TA AUMO | | • | |
| Remarks:NE | IN HOME | W/AT | TACHEPE | ARAGE | | |
| | | | | · / | | · · · · · · · · · · · · · · · · · · · |
| ······ | | | | | | · · |
| | | | | | · · · · · · · · · · · · · · · · · · · | |
| Herewith are filed | the specifications that | describe the work in | n question and as show | n on plans above su | ıbmitted. | |

In making the application the undersigned agrees to obey the Fox Point Building and Zoning Codes pertaining to the erection of all structures and also agrees to obey all other ordinances of the Village of Fox Point.

The undersigned, owner or being duly authorized so to do, hereby gives express authorization to the Village of Fox Point, its officers, agents and employees, to enter upon the premises herein described and fill up any excavation, or tear down, remove or enclose the unfinished structure for which a permit is herein requested in the event of cessation of the building, whenever the Building Inspector shall determine that such premises in the unfinished condition of the structure are dangerous to members of the public, including children, even though trespassers. The undersigned further hereby waives all statutory notices and consents to the determination by the Village Board and the levy and placing upon the tax roll of a special assessment in the amount of the cost to the Village, including customary Village overhead charges incurred in filling up any such excavation or tearing down, removing or enclosing any such unfinished structure.

We hereby agree to provide a house number plate or sign readily observable from the public highway which will be installed not less than 15 days after the structure is occupied.

| days after the structure is occupien. | PEG SHIELDS APCHIEGURE |
|---|-------------------------------------|
| Owner of Structure To Stratton | Arch. or Contr. OY PEOT-SHIELOS ALA |
| Address 3004 N HACKEHAVE | Address 3033N. HACKETT AVE |
| City MULWAVKEE State W1 Zip 53211 | City MILWAUKEE State WI Zip 5321 |
| Phone 414-534.6695 | Phone 414 73 2300 |
| Size of Structure(sq. ft.) Pe | ermit FeeReceipt_45403 1/1/ |
| Dwelling Contractor Certification No | Expires7[3 |
| Dwelling Contractor Qualifier Certification No | Expires |
| Building Contractor Certification No | Applicant Signature |
| Date of Approved $(\leq 13 13 13 13 13 13 13 1$ | Architect, Owner, Builder |
| | |

| | | INSPECTIC NOTICE OF N | N REPORT A | | | | | |
|--|--|---|-----------------------------|-------------------------------------|--|--------------------|--|--|
| Report Date | 1-1 | Inspection Date | Permit No.: | State Seal # | Parcel No: | | | |
| 10 | 15/14 | 10/15/14 | 15547 | 428230 | | | | |
| Project Add | ress | | Subdivision | | Lot No.: | Block No.: | | |
| 1015 | E GINIS PLA | ch | Areas Steller | | | | | |
| Inspection Type(s): | | sion Control Foundation gh Electrical Construction | | | rslab Plbg Roug | gh HVAC er: | | |
| Area Inspec | ted, if Partial Inspection: | | | Take Place Now how Are Corrected an |] Take Place Tempora d Inspected | rily for days | | |
| Owner: | | U Ottier. | Contractor: | | | | | |
| Rick | Star Iton | | Applebrask Construction | | | | | |
| 3009 | n Anckett A | Kr. | 3430 h- Curty Link Rong | | | | | |
| Milus | NUI W 532 | ч | Marchan, 41 53097 | | | | | |
| | -11-11-11-11-11-11-11-11-11-11-11-11-11 | | | 1 | | | | |
| | | | | | | | | |
| AN INSPE | CTION OF THE ABOVE PR | REMISES HAS DISCLOSE | D THE FOLLOW | ING NONCOMPL | IANCES: None N | loted | | |
| ORDER NO. | CODE SECTION | | FINDINGS | AND REQUIREM | ENTS | | | |
| D | O SAS 322-37 (3) REMOVE Plaster King From the mul Eculope | | | | | | | |
| 2) SAS 321.27 ELD Planne Kugneer For Fiew Albren /monifies trisise | | | | | | | | |
| 3 | NEC 210-52 (AVI) | Bound Manihour | ne outlet | I in Secon | SLOV (Em) |) Premons | | |
| Ð | 5195 321.27 (3) | PRUME AMILIONE | 1 lestin | int For | 3- phy Ban | (upliff) | | |
| B | NEC 210.52 (A) () | Rosing Anihon | al outlet | ic Dilino | Room (6) | (1) when | | |
| Sa | SK 37210 (2) | Planne levises | plani | Fir Sha | in the contraction | | | |
| 0 | NI IOA () | Alterations | | - 1411. | 4.4 | | | |
| D | SAS 382 31 (6/a) | Extens Soil SI | hall Through | h TH 100 | F System | | | |
| T2) | SPS 321.27(7) | Planne Martin | and coster | HE THES | BIACIN A | 5 Per | | |
| C | (.) | The trois me | mm. thre | 1. | , | | | |
| | | | | | | | | |
| | IMPORT | ANT: Please report when | violations are co | orrected AVOID | DELAY | | | |
| | OF NONCOMPLIANCE: A | all cited violations shall be con | rected within | 30 days after writt | ten notification unless | | | |
| | ted. Each day that the violatio aving jurisdiction. Appeals per | | | te offense and is sub | ject to remedies and p | penalties by the | | |
| Enforcing | Town Village City | County OF: | Bldg Loc | ation Muni # | | unicipal Ordinance | | |
| Jurisdiction: | | | <u> </u> | - 126 | Section:: | | | |
| Inspector's N | Seat Mill, | violations | s Explained To: | | Compliance Dat | X-11 | | |
| Inspector's A | | (0) | Office Hours: | 1 | Telephone No: | FS | | |
| Villac | 4 1/21 /7200 h | Sah Mura Ble | 1 8-930 | Ap/1232-13 | with A14 | 35+89.0 | | |
| Orders Refer | rred for Followup Legal Action | Date Noncomp | liances Verified to S | | ional Fees Collected(+ | | | |
| To: | | (If needed | l, notate orders abov No | | ate-Contracted Agency Original Permit Issua | | | |
| | | | | j binee | original i orifit issua | | | |

Distribution: DPly 1 - Contractor DPly 2 - Inspector/State DPly 3 - Owner DPly 4 - File

| Page | | 1 | |
|------|--------|----|------|
| age | 1.2211 | 1. | 1.20 |

1

_Of _


ÿ.

.

| | Butler Chase str 2.0E WS-L | | Job#: Strat: . 1.75 | ton 50" X 11 | | antity 1 (2p 2-Ply - | | | Description second Fl | | Pag | 20/2014 le 1 of 1 ligner: | 8:34 AM | | |
|---|--|--|--|---|-----------------|--------------------------------|---------------------------|--------------------|------------------------------------|--------------------|----------------------|---------------------------------|-------------------------|------------------------|------|
| 1 Hang | wstam tvt er (HGUS410) | | | | 10'3 9/16" | | | | Nie Contraction | | WILANI 2 S | ÀÙ | | | 1/2" |
| | 8 | | | | | | | | | | | | | | |
| Type: Plies: Moisture Condit Deflection LL: Deflection TL: Importance: Temperature: | Girder 2 360 240 Normal Temp <= 100°F | - | Application Design Me Building C Load Shar Deck: Vibration: | ethod: ASI ode: IBC ring: No 3/4 | | and Glued | Reaction Brg 1 2 | Livi 281 178 | 1 | Dead 941 641 | Snow (| D | Wind 0 0 | Const 0 0 |) |
| alysis Noment Shear | Actual 10258 ft-lb 3144 lb | 5'3 3/4" 1'1 5/8" | | Capacity 0.482 (48% 0.398 (40% |) D+L | L L | | Length 4.000" | In Analysis 1.500" 1.750" | | 941 / 28 641 / 17 | 11 375 | al Ld.C 51 L 21 L | ase Ld. D+L D+L | |
| 2 Multiple pli | | 4'11 3/16" pported on th d together as | 0.482 (L/240) e bottom edg per manufac | |) D+L | L | | | | | | | | | |
| ID | Load Type | | | Trib Width | Side | Dead | | ve | Snow | | Vind | Const. | Comm | ents | |
| 1 | Tie-In | | | (Span)0-1-12 | | 12 PSF | 40 P | | 0 PSF | | PSF | 0 PSF | | | |
| 2 | Tie-In | 0-0-0 | | (Span)0-1-12 | | 12 PSF | 40 P | | 0 PSF | | PSF | 0 PSF | | | |
| 3 | Point | | 0-8-0 | | Far Face | 99 lb | 331 | | 0 lb | | 0 lb | 0 lb | J5 | | |
| 4 | Point | 2.0 | 0-8-0 | | Near Face | 126 lb | 425 | | 0 lb | | 0 lb | 0 lb | | | |
| 5 | Part. Uniform | 1-4- | 0 to 4-0-0 | | Far Face | 90 PLF | 298 P | | 0 PLF | | PLF | 0 PLF | | | |
| 6 | Point Tio In | 0.0 | 2-0-0 | (Spor)0 4 40 | Near Face | 76 lb | 256 | | 0 lb | | 0 lb | 0 lb | | | |
| 1 | Tie-In | | | (Span)0-1-12 | | 12 PSF | 40 P | | 0 PSF | | PSF | 0 PSF | | | |
| 8 | Tie-In | 3-4-0 | | (Span)0-1-12 | | 12 PSF | 40 P | | 0 PSF | | PSF | 0 PSF | IE. | | |
| 9 | Point | | 4-8-0 | | Far Face | 94 lb | 314 | | 0 lb | | 0 lb | 0 lb | J5 | | |
| 10 | Point | E 0 40 | 5-5-4 to 10-3-9 | (Span)1.4.0 | Far Face Top | 792 lb 12 PSF | 2302 40 P | | 0 lb 0 PSF | | 0 lb PSF | 0 lb 0 PSF | G7 | ~ | |
| 11 | Tie-In Self Weight | J-0-12 | 10 10-3-9 | (Span)1-4-0 | юр | 12 PSF 11 PLF | 40 P | U. | U FOF | 0 | . 51 | 0 - 0 - | | | |
| Notes Calculated Structured e structural adequa | d Designs is responsible on acy of this component base and loadings shown. It is | ly of Handling | ms must not be cut | | ponding | fs provide proper | drainage to pre | event | | | | l | | Building S 5700 HWY | |


Powered by iStruct™ 14.4.062

CALCULATED STRUCTURED DESIGNS



Powered by Struct™ 14.4.062


CALCULATED STRUCTURED DESIGNS



Powered by OiStruct™ 14.4.062

.

CALCULATED STRUCTURED DESIGNS



| | | N | | N REPORT A | | | | |
|--|--|--|---|--|--|--|------------------------|--|
| Report Date: | 1 1 | Inspection | | Permit No.: | State Seal # | Parcel No: | | |
| 10 | 15/11_ | 101 | 5/14 | 15547 | 42823 | | | |
| Project Addr | ess | | 4-1 | Subdivision | 100000 | Lot No.: | Block No.: | |
| lois | Footing | Place Erosion Control | Foundation | Bsmt Drai | n Tile 🗖 I | Jnderslab Plbg | Rough HVAC | |
| Type(s): | Rough Plumbing | Rough Electrical | Constructio | n 🗍 Insulation/ | /Energy | inal | Other: | |
| Area Inspect | ed, if Partial Inspection: | | | Occupancy May: Until The Items Bel | | w Take Place Tem and Inspected | porarily for days | |
| Owner: | | | | Contractor: | | | | |
| Rick | Startfun | | | Applebraik Construct. | | | | |
| 3009 | n Hackelt | A.E. | | 3420 Le. Cuty los Rong | | | | |
| Milur | why whe | 132(1 | | Macque | - 1ul | 53097 | 1. 1 | |
| | | | | | | | | |
| AN INSPE | CTION OF THE ABO | VE PREMISES H | AS DISCLOSEI | D THE FOLLOW | ING NONCOL | MPLIANCES: | one Noted | |
| ORDER NO. | CODE SECTION | | | | AND REQUIR | | | |
| @ Sts 322.37 (3) Removes Plaster Two For the mal Euclope | | | | | | | IR | |
| 2) | 5/5 321.27/2 | 16 Prome | Engraces | For Fil | ens · Al | bran /monit, | as trusister | |
| 3 | NEC 210-52(A) | (1) Bonny | Marthon | ne outlet | in & | 10-5 Sherry (4 | msT) Bankon | |
| Ð | 585 371.27 (3 | PROJECT 1 | Ahitora | (lestia | t For | 3-ply Be | Ari Luplift) | |
| B) | NEC 210.52(A) | () Rosing | Ansihon | al outlet | in Du | my Room | 6/12 1.te) | |
| 20 | SAS 32410 R | Plonke | ·100154 | placi | Fir 5 | haven | | |
| | 76 | Altra | trovs | | | 1 | | |
| a | SK 382. 31 16 | (a) Extens | ·sal st | mell Through | h the | SOF Syst | m | |
| 2 | SPS 321.27 7 | Plante | Martin | and contern | AL THE | Bincing | AI PPr | |
| | | DL + | is mo | m.m. fure, | (| | | |
| | | | . 1 | . 1 | . 1 | | | |
| NOTICE | DF NONCOMPLIAN | and the second | and the second se | violations are co | and the second | | nless an extension of | |
| time is grant | ed. Each day that the viving jurisdiction. Appea | iolation continues a | fter notice shall o | constitute a separat | | | | |
| Enforcing Jurisdiction: | Town Village | City County | OF: | | ation Muni # | Authority E Section:: | By Municipal Ordinance | |
| Inspector's N | | sp Agency# | Violations | Explained To: | 160 | Compliance | e Date: | |
| • | Sut MI | 11/ | (o) | haclor | | 30 | Daxa | |
| Inspector's A | ddress: Hall Tree | 1 Sahl | Ulura Blu | Office Hours: 18-Bo | An/123: | Telephone | No: 1) 14) 351-89.0 | |
| Orders Refer To: | red for Followup Legal A | ction Date | | liances Verified to S l, notate orders abov | e.) I | Additional Fees Collec By State-Contracted A Since Original Permit | gency \$ | |
| | Distribu | tion: □Ply 1 – Co | | - Inspector/State | | | | |

Page ____Of _

| Description | | Lot | Blk. | Subd. | |
|--|------------|--|-------|------------------------------|------------|
| | | | | | |
| A MARCON | | | | | |
| being No. 10.15 | on the | South side of | C | Quarter Pl | 2 |
| The above named is p | ermitted · | to employ | Sel | olsky | a Licensed |
| | | | | | |
| | | | | e in | |
| | | And the second | | | |
| | | | | | |
| Or of laying a | | inch | Stori | n Sewer Drain pipe | |
| | | | | 1 | |
| Fixtures with drain or | water co | nnection | | | |
| | | | No. | | |
| and the second state of the second state | No. | | INO. | | No. |
| Bath tubs | No. | Sump Pump | INO. | Wash Basins | No. |
| Bath tubs Laundry tubs | No. | Sump Pump Sinks | No. | Wash Basins Water Closets | No. |
| | No. | | No. | | No. |

| INSPECTION APPROVA | AL |
|--|----------------------------|
| Permit_ 7907 | Date71 |
| TO DEPT. OF BUILDING INSPECTION VILLAGE OF FOX POINT | |
| Please be advised that the undersigned | has made a Heating plant |
| Electrical Inspection of the residence of | of Mr. 21. Frudlen |
| | _and hereby approves same. |
| REMARKS: | |

64

aver. Signed WALTER J. KAISER ELECTRICAL INSPECTOR VILLAGE OF FOX POINT

| Permission is hereby | given to do the necessary | plumbing work on the pre | mises |
|--|--|--|------------|
| · ·······, | | described as | |
| Lot | Block | Subdivision | 5 10110 10 |
| | BIOCK | Subulvision | |
| | | | <u> </u> |
| ocated at 1015 | Quartes Mark | | |
| | tted to employ Dew | Deamh | |
| he above named is permit | tted to employ | rappes | |
| icense No. MPA | for the purpose of | laying ainch | |
| | | | |
| anitary Building Sewer f | | o Premises Connection to be | |
| | | to Premises. Connection to be | |
| | feet | | |
| _aying a | feet | of Building Storm Sewer | |
| Laying a | feet | of Building Storm Sewer | |
| Laying a | feet inch er connection: | of Building Storm Sewer | |
| Laying a | feet inch er connection: No. | of Building Storm Sewer No. | |
| Laying a | feet inch er connection: | of Building Storm Sewer | |
| Laying a | feet inch er connection: No. | of Building Storm Sewer No. | |
| Laying a Fixtures with drain or wate Hose Bibs Bath Tubs | feet er connection: No. Water Heaters | of Building Storm Sewer No. / Water Closets | |
| Laying a Fixtures with drain or wate Hose Bibs | feet inch er connection: No. Water Heaters Wash Mach Waste | of Building Storm Sewer No. / Water Closets Showers | |
| Laying a Fixtures with drain or wate Hose Bibs Bath Tubs Sump Pumps | feet | of Building Storm Sewer No. / Water Closets Showers Floor Drains | |
| Laying a Fixtures with drain or wate Hose Bibs Bath Tubs Sump Pumps Laundry Trays | feet | of Building Storm Sewer No. / Water Closets Showers Floor Drains Food Waste Grinders | |

Building Sewer \$____

Building Drain \$____

Fixtures eccept # 34 35 Rec'd for Permit \$_ Plumbing Inspector

| | SEWER AND PLUMBIN | G DEPA | ARTMENT | |
|---|--------------------------------|-------------------------|-------------------------------|----------|
| Permit No. 99/00 Apr | plication No. 9611 Fox | Point, V | 1402 | 20 |
| Permission is hereby | given to do the necessa | ary plu | imbing work on the pre | mises of |
| | | | described as | |
| Lot | Block | <u> <u>elestate</u></u> | Subdivision | |
| Located at | E quarlos F | Tack | | |
| The above named is permi | tted to employ Gene | te | ers | |
| License No. 22239 | for the purpose | of layin | | |
| Sanitary Building Sewer | from Main to Curb to Lot lir | ne to P | remises. Connection to be | made in |
| Laying a | inch | Build | ding Storm Sewer | |
| Fixtures with drain or wate | | No. | | |
| Hose Bibs | Water Heaters | 1 | Water Closets | No. |
| Bath Tubs | Wash Mach Waste | | Showers | + |
| Sump Pumps | Bidets | 1 | Floor Drains | |
| Laundry Trays | Catch Basins | 1 | Food Waste Grinders | + |
| Drinking Fountains | Dishwashers | 1 | Sprinkling Systems | 11 |
| Sinks | Wash Basins | | Urinals | |
| | | | | |
| as per application made su of the Fox Point Village Co | ubject to the Rules and Regula | itions of | f the Village Board and of Ch | apter 12 |
| Building Sewer \$ | | Fixtur | res \$ | 11 |
| Building Drain \$ | Re | ec'd for | Permit \$ Receipt | # |
| | | ga caalla maranatigaa | | 2010 |

Plumbing Inspector

SEWER AND PLUMBING DEPARTMENT

| | | described as follo | ws |
|-----------------------------|-----------------------------------|--------------------------------------|-----|
| Lot | Block | Subdivision | |
| í. | | | |
| Located at 1015 | E QUALET F | Thee . | |
| The above named is perm | itted to employ | ve Overliken | |
| License No. 22776 | for the purpose of laying | a inch | |
| | m Main to Curb to Lot line to Pre | | |
| | feetof_ | | |
| Laying a | inch Building | Storm Sewer | |
| Fixtures with drain or wat | er connection. | •••••••••••••••••••••••••••••• | ••• |
| | lo. N | o. 1 | No. |
| Hose Bids | Water Heaters | Water Closets | |
| | Wash Machine Waste | Showers | |
| Bath Tubs | | | |
| Bath Tubs Sump Pumps | Bidets | Floor Drains | |
| | Bidets Catch Basins | Floor Drains Floor Waste Grinders | |
| Sump Pumps | | | |
| Sump Pumps Laundry Trays | Catch Basins | Floor Waste Grinders | |

| Building Sewer \$ | Fixtures \$ |
|-------------------|-------------------------|
| Building Drain \$ | Rec'd for permit \$_60= |
| | Receipt # |
| | Plumbing Inspector |
| | 45311 |

SEWER AND PLUMBING DEPARTMENT

| Permit'No. 3-52 Ap | plication No. 13099 Fox F | Point WI 7/1/4/520 |
|---|---------------------------|---|
| | | nbing work on the premises of |
| , , | | described as follows: |
| Lot | Block | Subdivision |
| ÷ | | |
| Located at 1015 | E Quales P | Ince |
| The above named is perm | nitted to employ Why | 1 Buerlie |
| | | ga_4_inch_PVC. |
| | | remises. Connection to be made in |
| | feetof | |
| 50° | | g Storm Sewer |
| Fixtures with drain or wat | ter connection: | ••••••••••••••••••••••••••••••••••••••• |
| 1 | No. N | No. No. |
| Hose Bids | Water Heaters | Water Closets |
| Bath Tubs | Wash Machine Waste | Showers |
| Sump Pumps | Bidets | Floor Drains |
| Laundry Trays | Catch Basins | Floor Waste Grinders |
| Drinking Fountains | Dishwashers | Sprinkling Systems |
| Sinks | Wash Basins | Urinals |
| 11/4" WAL | r Lorfeind | |
| as per application made of Chapter 12 of the Fox | | lations of the Village Board and |
| Building Sewer \$ | Fix | tures \$ |

Building Drain \$_____

Rec'd for permit \$_/co5= mit \$_____ Plumbing Inspector 5

SEWER AND PLUMBING DEPARTMENT

| | | cation No. <u>1360</u> Fo: | | | |
|---|------------------|---|--------|--------------------------------|--------|
| Permission is hereby | given | to do the necessary pl | umb | | |
| Lot | | Block | | described as fo Subdivision | ollows |
| | | | | | - |
| Located at 1015 | R | QUASTRI P | brz | ke | |
| The above named is p | permitte | Quelti P | Lon | the Ibilk | |
| License No. 2207 | 01 | for the purpose of lay | ing o | a inch | |
| | | Main to Curb to Lot line to | | | |
| | | feet | | | |
| 지금 상품이 지지 않는 것은 것이 생각을 챙기고 했다. 것 | | chBuildi | | | |
| Fixtures with drain or | water | connection: | ••••• | ••••• | ••••• |
| | No. | | No. | | No. |
| Hose Bids | 3 | Water Heaters | 1 | Water Closets | 7 |
| Bath Tubs | 1 | Wash Machine Waste | | Showers | 3 |
| Sump Pumps | | Bidets | * | Floor Drains | |
| Laundry Trays | 1 | Catch Basins | | Floor Waste Grinders | |
| Drinking Fountains | | Dishwashers | 1 | Sprinkling Systems | |
| Sinks | 1 | Wash Basins | 8 | Urinals | |
| | | | | | |
| as per application ma of Chapter 12 of the F | de sub ox Poi | ject to the Rules and Reg nt Village Code. | julati | ons of the Village Board | d and |
| Building Sewer \$ | | F | ixture | es \$ | U |
| Building Drain \$ | | R | ec′d | for permit \$95= | |
| | | | | Report # | |
| | | Plumbing Inspector | | TH | |
| | | \smile | | 46821 | 0 |
| a construction of the second second | | | | | |

| Description | | Lot | Blk. | Subd. | |
|--|------------|--------------------|-----------|-----------------------------------|------------|
| Fut Poin | A li | ub. | 4 | 1 | |
| being No. 1015 | on the | Side | of Ed | Juarles | - Pl |
| The above named is po | ermitted t | o employ | Jaha | <u></u> | a License |
| | | / | Cla | Sanitary Se | |
| | | | / | inMain 98 | |
| moni mani to curb to | Lot me t | | | | |
| | | and the second | | a la a a a a | <i>LQ</i> |
| | of | Last | ya y | alen | - <u>.</u> |
| feet | of | Last | yan y | n Sewer Drain pipe | < |
| | of | Last | yan y | allen | |
| | of 0 | Land g | yan y | allen | ££ |
| Or of laying a | of 0 | Land g | yan y | allen | No. |
| Or of laying a | of of or | Land g | yan Storr | allen | ····· |
| Or of laying a Fixtures with drain o Bath tubs | of of or | inch P | yan Storr | n Sewer Drain pipe | ····· |
| Or of laying a Fixtures with drain o | of of or | inch of connection | yan Storr | n Sewer Drain pipe Wash Basins | ····· |

WATER PERMIT

122

| F13 | WAIDAI | | |
|---|--|--------------------------|----------------------|
| Permit No. | Application No. | Fox Point, Wis | 11/319// |
| Permission is hereby give | and the second s | essary to supply with wa | ter the premises of |
| Description | Lot | Blk. | |
| For Point. | lub. | 4 1 | |
| being No | on the | side of | realized |
| The above named is permitted | to employ | a dance | a Licensed |
| Plumber for the purpose of la | ying ainch | servi | ce pipe from Main to |
| Curb: a inch | | | |
| | | | |
| as per application made subject nance No. 66 of the Village of Received for Received for | Fox Point and amendme or Permit \$ | nts. 1116 | rs |
| Returns must be made on | all work done. | WATER INSPECT | or he |
| | | PERMIT CLERI | (· · |

Wanna T/1 "

VILLAGE OF FOX POINT

MILWAUKEE COUNTY, WISCONSIN

No. 158

| | APPLICATI | ON | FOR PERN | ЛТ | , | | |
|----------|---|----------|--|---------------------------------------|---------------|------------|--------|
| то | THE INSPECTION DEPARTMENT: | | | | | | |
| | The undersigned hereby applies for | a peri | nit for the execution o | of elec | trical in | stallatio | on for |
| | light, heat or power, as hereinafter | - | | | | | |
| 1 | Location 1015-E- Qu | oules | Clace | | | | |
| 1. | (Give exact street an | nd numb | er. Do not give corner.) | | | | |
| 2. | Owner A Bethere | | | м | \mathcal{O} | | A / |
| 3. | Lot | <i>I</i> | Subdivision | 5.0p | loin | Z AL | Und. |
| 4. | Building or structure | | | | | 20 | |
| 5. | Contractor Oliver Brow | | | nse No |). | 58 | |
| | | lumbei | ····· | | | Fee | es |
| | Lighting Outlets | | | @ | \$.10 | 3 | 00. |
| 7. | Fixtures | | | •• | .05 | | 35 |
| 8. | Range Circuit or Outlet | / | | ••• | 1.00 | <i>f</i> . | 00 |
| | Range Connection | | | | 1.00 | | |
| 10. | Water Heaters & other Heating Devices | | 1st-Kilowatt Each Additional Kilowatt | | 1.00 | | 00 |
| 11. | Refrigerating Machines | | Each Additional Kilowatt | " | 2.00 | | |
| 12. | Oil Burners and Stokers | | | " | 1.00 | | |
| 13. | Temporary Permits | | Inspection per Hour | " | 2.00 | | |
| 14. | Motors | | H.PH.PH.P. per H.I | P. " | .10 | | |
| 15. | Studded Lights including their | | | | | | |
| | Individual Outlets | | | ••• | .05 | | |
| 16. | Rectifiers and Transformers | | | ••• | 1.00 | | |
| | · · · · · · · · · · · · · · · · · · · | | | | | | |
| | | | ****** | | | | |
| | | | | | | | |
| · | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| <i>.</i> | | | | | | 1 Ka | 20 |
| | Estimated cost \$ | | Total fees | · · · · · · · · · · · · · · · · · · · | | | 35 |
| | e of inspection $\begin{cases} Wiring \dots Will & M \\ Fixtures \dots & \end{cases}$ | stil | 19 | Note: | Minimu | m Foo | ¢1 00 |
| Dat | e of inspection { | 1 | | | | in ree | φ1.00 |
| | [Fixtures | | | | | | |
| | | - | ····· | | · | | |
| | | | | | | | |
| Enc | losed please find \$ | | | | | | ·•• |
| | | | | | | | |
| | | | | | | | ** |
| | | | | | | | |
| • | | | | | | | |
| | | | | | | | |
| •••••• | | | _ | | | | |

It is hereby agreed between the undersigned person, firm or corporation and the Village of Fox Point that for and in consideration of the premises and of the permit for the execution of the electrical installation, for light, heat or power, as particularly described in this application, the work will be done in accordance with all of the provisions of all ordinances regulating the installation of electrical work, electric wiring and apparatus in the Village of Fox Point and all of the subsequent amendments thereto.

Signed Oliver Brower Address 36636 Squire ave.


VILLAGE OF FOX POINT

| VILLAGE OF FO MILWAUKEE COUNTY, V | | 7- 18 No. <u>3228.</u> | - 52 Je |
|--|------------------------|----------------------------------|--------------------|
| | | No. 3928 | |
| APPLICATION FC | R PERMIT | | |
| O THE INSPECTION DEPARTMENT: | | | |
| The undersigned hereby applies for a permit for | the execution of elec | trical installati | on for |
| light, heat or power, as hereinafter prescribed. | 7 | | |
| 1. Location 1015 E Quarle | 2 | | |
| _(Give exact street and number. Do | not give corner.) | | |
| 2. Owner R Botths | | • | |
| 3. LotBlock | Subdivision | | |
| 4. Building or structure Roadland | | | |
| 5. Contractor then The Clubin | | Jo. | |
| Number | Rate of Fees | Fe | es |
| 6. Lighting Outlets | | \$.10 | |
| 7. Fixtures | | .05 | |
| 8. Range Circuit or Outlet | " | 1.00 | |
| 9. Range Connection | ،، | 1.00 | |
| 0. Water Heaters & other Heating Devices 1st Ki | owatt " | 1.00 | |
| 1. Refrigerating Machines | Additional Kilowatt (6 | 2.00 | |
| 2. Oil Burners and Stokers | | 1.00 | |
| 3. Temporary Permits Inspec | | 2.00 | |
| 4. Motors | - | .10 | |
| 5. Studded Lights including their | | | •••••• |
| Individual Outlets | <i>44</i> | .05 | |
| 6. Rectifiers and Transformers | | 1.00 | |
| | | 1.00 | |
| | | | |
| | | | |
| | | | •••••• |
| | | ······ | |
| | | | •••••••••••••••••• |
| | | | •••••• |
| ······································ | | | ••••• |
| \ \ | | | |
| | | | |
| Estimated cost \$ | otal fees | #1.00 | |
| | | <i>fff</i> | ····· |
| Wiring Villey / P | .19.52 Note | : Minimum Fee | \$1.00 |
| Date of inspection { | | . Minimum 1.66 | ; |
| (Fixtures. | | | |
| | | | ••••••••• |
| | | | |
| Enclosed please find \$ | | | |
| | ······ | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

installation, for light, heat or power, as particularly described in this application, the work will be done in accordance with all of the provisions of all ordinances regulating the installation of electrical work, electric wiring and apparatus in the Village of Fox Point and all of the subsequent amendments thereto.

כ Signed igh Rood Address <u>5</u>

l



Industry Resources: Connectors: strongtie.com/products/Alpha_list.html Engineering: mitek-us.com ("Engineering" pulldown) Bracing, etc: sbcindustry.com ("Info for Builders" pulldown) PDF created with pdfFactory Pro trial version www.pdffactory.com

GENERAL ROOF NOTES:

The intent of this document is to show truss placement only. Contractor is responsible for verifying all dimensions and wall heights with the blueprint prior to setting the trusses.

* All dimensions are Feet - Inches - Fractions.

* The Left end of truss (as shown on Drawing) is the end of truss shown with a triangle on placement plan. This is also the painted end of the truss.

* Truss over-framing &/or header material by others (unless otherwise noted). Refer to truss reactions.

Sheath under all valleys (if applicable). Uniformly distribute all over-framing to trusses below as to not impose point-loads.

* See drawings for multi-ply girder connections and permanent bracing locations (if applicable)

See included documents for important bracing information. Refer to job package for additional info & hanger information.

* Cutting or altering trusses without engineer approval voids warranty. Contact AHS prior to cutting any trusses.



Job Notes:

Contractor: Latest Plan Date: 8/23/13 Latest Layout Date: 10/16//14

HANGER SCHEDULE: (19) LUS24 (16) LUS28 (6) HUS28 (1) HGUS28-2

UPLIFT CLIP/STRAP SCHEDULE: (55) H2.5T (8) HTS30C uplift twist straps.





2624 Corporate Circle, East Tray, Wi 53120 P: 262-642-3800 F: 262-642-2716 www.accuratehousing.com

Work Order #: R-5902-13 Client: Wisconsin Building Supply - Su

Job Name: Stratton Residence Model: Elevation: Lot/Sub:

> Truss Tech: Justin Nagi Ext. 7013






PLAT OF SURVEY

CLIENT Frederick Strattor

SITE ADDRESS


1015 East Quarles Place, Village of Fox Point, Milwaukee County, Wisconsin.

LEGAL DESCRIPTION Lot 4, Block 1, Fox Point Subdivision, being a part of the Southwest 1/4 of Section 9, Town 8 North, Range 22 East in the Village of Fox Point, Milwaukee County, Wisconsin.









I Certify that I have surveyed the above described property (Property), and the above map is correct to the best of my professional knowledge and belief and shows the size and location of the Property, its acterior boundaries, the location and dimensions of all visible structures thereon, boundary fences, apparent easements and readways and visible engravehogets, if any. This survey is made for the exclusive use of the present owners of the Property, and also those who publicate difference of the present owners of the present. or guarantee the title thereto, within one (1) year from date hereof.

Date: November 21, 2013


Dull Chapit


DONALD C S-1316 MILWAUKEE AND SURVE

CHAPUT LAND SURVEYS

Donald C. Chaput Registered Land Surveyor Registration Number \$-1318

CHAPUT LAND SURVEYS LLC 234 W. FLORIDA STREFT MILWAUKEE WI 53201 114-224-8058 www.chaputaburyey.com Brawing Ng. 1477-ajs/tjn







Scale 1/4 inch : 1 ft.

| 80CO/ | | oor | | | | |
|--------|----------------|--------|---------------------------|-----------|--------|--------|
| i Jois | 1 | | | | | |
| Qty | Labe | Descri | ption | Width | Depth | Length |
| 7 | J1 | WSI 40 | • | 2.313 | 11.875 | 4-0-1 |
| 1 | J2 | WSI 40 | | 2.313 | 11_B75 | 5-0-0 |
| 20 | J3 | WSI 40 | | 2.313 | 11.875 | 7-0-1 |
| 17 | 34 | WSI 40 | | 2.313 | 11.875 | 9-0-4 |
| - 4 | J 5 | WSI 40 | | 2.313 | 11.875 | 16-0-1 |
| 1 | 8L | WSI 40 | | 2.313 | 11.875 | 18-0-0 |
| 15 | Jđ | WSI 40 | | 2.313 | 11.875 | 19-0-1 |
| 4 | J7 | WS140 | | 2.313 | 11.875 | 20-0- |
| 2 | J12 | WSI 40 | | 2.313 | 11.875 | 22-0-1 |
| 7 | J13 | WSI 40 | | 2.313 | 11.875 | 35-0-1 |
| 3 | J14 | WSI 40 | | 2.313 | 11.075 | 37-04 |
| 8 | 16 | WSI 40 | | 2.313 | 11.875 | 38-0-0 |
| | J10 | WSI 90 | | 3.5 | 11,875 | 23-0-0 |
| 3 | J11 | WSI 90 | | 3.5 | 11.675 | 24-0-0 |
| LVL | | | | | | |
| Qtv | Labe | Descri | ption | Width | Depth | Lengti |
| 2 | B1 | 2.0E W | S-LAM LVL | 1.75 | 11.875 | 2-0-1 |
| 3 | G6 | 2.0E W | S-LAM LVL | 1.75 | 11.875 | 6-0-0 |
| 2 | B2 | 2.0E W | S-LAM LVL | 1.75 | 11.875 | 11-0-0 |
| 12 | Gð | 2.0E W | S-LAM LVL | 1.75 | 11.875 | 11-0-0 |
| 3 | Ge | 2.0E W | S-LAM LVL | 1.75 | 11.875 | 15-0-4 |
| 4 | G7 | 2.0E W | S-LAM LVL | 1.75 | 11.875 | 16-0-1 |
| | G3 | 2.0E W | S-LAN LVL | 1.75 | 11.875 | 18-0-1 |
| 6 | G4 | 2.0E W | S-LAM LVL | 1.75 | 11.875 | 19-0- |
| 2 | G1 | 2.0E W | S-LAM LVL | 1.75 | 11.875 | 20-0-4 |
| 3 | G2 | 2.0E W | S-LAM LVL | 1.75 | 11.875 | 37-0- |
| Rim E | Board | 1 | | | | |
| | Qty L | abei | Description | Thickness | Depth | Length |
| | 27 R | | WS LVL 1.5E 1.25 X 11.875 | 1.25 | 11.675 | 1 |
| Hang | | | | | | |
| | | Label | Description | | | |
| | | H2 | HQUS410 | | | |
| | | Hi | HOUS7.25/12 | | | |
| | | H4 | HU410 (Max) | | | |
| | 94 | | IUS2.37/11.88 (Max) | | | |

| Wisconsin Building Supply | Second Floor Design Method | ASÚ |
|---------------------------|-------------------------------|-----------------|
| W232 N 5700 HWY 74 | Building Code | IBCARC |
| Sussex, Wi | Floor | |
| | Loads | |
| US | Live | 40 |
| 53089 | Dead Deflection Joint | 12 |
| Client | LL Spen L/ | 480 |
| Butter chase | TL Spen L/ | 240 |
| | LL Cant L/ | 180 |
| Project | TL Carl U | 180 |
| Stratton | Deflection Girder | |
| Created | TL Span L/ | 360 |
| | LL Cant U | /40 |
| October 16, 2014 | TL Cent U | 180 |
| Sales Rep | Decking | |
| | Deck | OSE |
| Bob Yurk | Festoner | Nailed & Church |
| Designer | Thickness | 3/4' |

Lu Aun Price W232 N 5760 HWY 74 Sussex, WI 53089 262-246-0611 BUILDING SUPPLY CERTIDUCTIONS Framing placement and all dimensions to be variified by Customer
 Lader Frame perpendicular to panelle webs to sta jost 32'oo typicat.
 Ser bottom novid racing of jost refer to been cate notes
 Additional added Joint for Pertition Webl Above






This layout is to be used as an inclusive guide only. It is means to be used in sequences with the andmestard and service

- Contractor

Landgar arfinition with the descenter frequest lands and weather and holy factors on country former in country

One by sell of the one



BCSI-B1 SUMMARY SHEET - GUIDE FOR HANDLING, INSTALLING, RESTRAINING AND BRACING OF TRUSSES Spans over 60' may require complex permanent bracing. Please always consult a Registered Design Professional.

GENERAL NOTES

requency or location of temporary lateral restraint identifique la frecuencia o localización de restricción lateral and diagonal bracing. Follow the recommendations variostre diagonal temporales. Use las recomendaciones for handling, installing and temporary restraining and bracing of trusses. Refer to BCSI - Guide to los trusses. Vea el folleto BCSI - Guía de Buena Práctica Good Practice for Handling, Installing, Restraining para el Manejo, Instalación, Restricción y Arriostre de los & Bracing of Metal Plate Connected Wood for more detailed information. Trusses*

Truss Design Drawings may specify locations of Los dibujos de diseño de los trusses pueden especificar permanent lateral restraint or reinforcement for las localizaciones de restricción lateral permanente individual truss members. Refer to the BCSI- refuerzo en los miembros individuales del truss. Vea la B3*** for more information. All other permanent hoja resumen BCSI-B3*** para más información. E bracing design is the responsibility of the building resto de los diseños de arriostres permanentes son la designer

WARNING The consequences of improper

aún peor, heridos o muertos.

HANDLING —

NOTICE Avoid lateral bending.

NOTICE The contractor is responsible for

smooth surface to prevent damage

la tierra liso para prevenir el daño.

properly receiving, unloading and storing the trusses at the jobsite. Unload trusses to

El contratista tiene la responsabilidad de

recibir, descargar y almacenar adecuadamente

los trusses en la obra. Descargue los trusses en

Fvite la flexión lateral.

MANEJO

D

C

 \checkmark

andling, erecting, installing, restraining

and bracing can result in a collapse of the

structure, or worse, serious personal injury

iADVERTENCIA! El resultado de un manejo,

levantamiento, instalación, restricción y arrisotre

incorrecto puede ser la caída de la estructura o

AUTTION Exercise care when removing

damaging trusses and prevent injury. Wear

personal protective equipment for the eves.

lice cautela al guttar las ataduras

o los pedaros de ment les sujetar nas gualuras o los pedaros de ment les sujetar nara evitar daño a los trusses y prevenir la ner de jersonal. Lleve el equipo protectivo personil cara oros, pies, manos y cabeza cuando travaja con trusses.

feet, hands and head when working with

banding and handling trusses to avoid

NOTAS GENERALES

Trusses are not marked in any way to identify the Los trusses no están marcados de ningún modo que de manejo, instalación, restricción y arriostre temporal de Trusses de Madera Conectados con Placas de Metal** para información más detallada

responsabilidad del diseñador del edificio

Use Month

C.V.V.C.

special care in

windy weather or

near power lines

and airports

Spreader bar

Use proper rig-

equipment.

ging and hoisting

for truss

RCANTELAN Utilice

cuidado especial en

días ventosos o cerca

de cables eléctricos o

ALTH.

Use equipo apropiado

para levantar e

improvisar.

de aeropuertos.

HOISTING AND PLACEMENT OF TRUSS BUNDLES **RECOMENDACIONES PARA LEVANTAR PAQUETES DE TRUSSES**

DON'T overload the crane 0

- NO sobrecarque la grúa. 0
- NEVER use banding to lift a bundle. NUNCA use las ataduras para levantar un paquete
- A single lift point may be used for bundles of
- top chord pitch trusses up to 45' (13.7 m) and parallel chord trusses up to 30' (9.1 m). Use at least two lift points for bundles of top chord pitch trusses up to 60' (18.3 m) and parallel chord trusses up tô 45[°] (13.7 m). Use at least three lift points for bundles of top chord pitch trusses >60' (18.3m) and parallel chord trusses >45' (13.7 m).

Puede usar un solo lugar de levantar para paquetes de trusses de la cuerda superior hasta 45' v trusses de cuerdas paralelas de 30' o menos. Use por lo menos dos puntos de levantar con grupos de trusses de cuerda superior inclinada

structure with truss bundle. ADVERTENCIA! No sobrecargue la


trusses. Place truss bundles in stable position.

> estable. 11 2

hasta 60' v trusses de cuerdas paralelas hasta

45'. Use por lo menos dos puntos de levantar con grupos de trusses de cuerda superior inclinada

MECHANICAL HOISTING RECOMMENDATIONS FOR SINGLE TRUSSES RECOMENDACIONES PARA LEVANTAR TRUSSES INDIVIDUALES




 $\overline{\mathbf{v}}$ Hold each truss in position with the erection equipment until top chord temporary lateral restraint is installed and the truss is fastened to the bearing points.

Sostenga cada truss en posición con equipo de grúa hasta que la restricción lateral temporal de la cuerda superior esté instalado y el truss está asegurado en los soportes.

INSTALLATION OF SINGLE TRUSSES BY HAND

RECOMMENDACCIONES DE LEVANTAMIENTO DE TRUSSES INDIVIDUALES POR LA MANO



TEMPORARY RESTRAINT & BRACING RESTRICCIÓN Y ARRIOSTRE TEMPORAL

NOTICE Refer to BCSI-B2*** for more

- Vea el resumen BCSI-B2*** para más infor-
- mación. Locate ground braces for first truss directly in line with all rows of top chord temporary
- lateral restraint (see table in the next column). Coloque los arriostres de tierra para el primer truss directamente en línea con cada una de

las filas de restricción lateral temporal de la cuerda superior (vea la tabla en la próxima columna

O DO NOT walk on unbraced trusses. NO camine en trusses




WARNING Do not over load supporting

estructura apoyada con el paquete de


Puse paquetes de trusses en una posición

mas de 60' y trusses de cuerdas paralelas mas de 45'.



Gable End Frame restraint/bracing/ einforcement information. Para información sobre restricción/ arriostre/refuerzo para Armazones

Repita los arrisotres diagonales para cada grupo de 4 trusses.



guardados para más de una semana, ponga bloqueando de altura suficiente detrás de la pila NO almacene en tierra O DO NOT store on de los trusses a 8 hasta 10 pies en centro (o.c.). uneven ground. desigual For trusses stored for more than one week, cover bundles to protect from the environment. Para trusses guardados por más de una semana,

cubra los paquetes para protegerlos del ambiente. Refer to BCSI*** for more detailed information pertaining to handling and jobsite storage of

Vea el folleto BCSI*** para información más detallada sobre el manejo y almacenado de los trusses en área de trabaio.

ERI

O DO NOT store NO almacene unbraced bundles verticalmente los CARLON T CADOLAD trusses sueltos. upright. Trusses may be unloaded directly on the ground at the time of delivery or stored temporarily in contact with the ground after delivery. If trusses are to be stored for more than one week, place blocking of sufficient height beneath the stack of trusses at 8' (2.4 m) to 10' (3 m) on-center Los trusses pueden ser descargados directamente en el suelo en aquel momento de entrega o almacenados temporalmente en contacto con el suelo después de entrega. Si los trusses estarán





HOJA RESUMEN DE LA GUÍA DE BUENA PRÁCTICA PARA EL MANEJO, INSTALACIÓN, RESTRICCIÓN Y ARRIOSTRE DE LOS TRUSSES

Lateral Restraint

(TCTLR)

Brace first truss

securely before

trusses

2x4 min

